

ADDENDUM No. 3

February 3, 2025. The following changes and additional information shall be incorporated into the Contract Documents and Specifications for the **Detention Pond 6 and East Airport Drainage** project. These modifications shall supersede any existing specifications as detailed herein.

Changes:


Change #1: Earthwork Balancing Pads (Addendum #2)

Earthwork balancing pad locations where export material will be placed and compacted were provided in Addendum #2 (Addition #3). The City has decided to remove Area #1 from the placement locations. All placement of export will be south of 33rd Street between 9th Ave and 13th Ave. As a point of clarification, the fill quantities associated with these pads are intended to be used as needed up to the volumes and grades shown. The volumes provided for fill on the balancing pad sheets are not associated with any particular bid item, as the volume being placed will be based on the export quantity from the plan. Also, it should be clarified that compaction testing on the balancing pads will be subject to the testing frequencies indicated in the geotechnical report, which are one test for every 500 SY and at least one test per lift.

All bidders shall acknowledge receipt and acceptance of this Addendum by submitting this signed Addendum with the bid package. Bid forms received without this Addendum will be considered informal.

ALLIANCE CONSULTING

CONTRACTOR

Signature: 
Title: Project Engineer
Date: February 3, 2025

Signature: _____
Title: _____
Date: _____