



March 26, 2025

ADDENDUM #1
North Industries Streets & Stormwater
City of Dickinson, ND

Owner Project #: 202316
Highlands Project #: 231223

TO: All prospective bidders and suppliers on the above referenced project


The following revision(s) shall be made to the contract documents for this project:

- Add the following paragraph to the end of plan note 32 1207-02 GRAVEL SURFACING 4IN:
 - To determine the quantity of gravel used, Engineer will complete a survey of the gravel stockpile before material is supplied to the project, and after the completion of gravel surfacing hauling. Engineer will convert the difference in cubic yards between these stockpile volumes to TON by using a unit weight of 1.875 TON/CY to determine the Plan Quantity of Gravel Surfacing 4IN. Provide a minimum of 10 business days' notice to Engineer before planning to haul gravel surfacing. Haul trucks will not need to be weighed.

This addendum is to be incorporated into the bidder's proposal for this project.

A handwritten signature in blue ink that reads "Andrew Schrank".

Andrew Schrank, PE – Project Manager
Highlands Engineering



office 701 483 2444
fax 701 483 2610

email info@highlandseng.com
web www.highlandseng.com

Highlands Engineering & Surveying, PLLC
319 24th Street East | Dickinson, ND 58601