

SUMMARY

GRADING				
STATION	cu. yards			REMARKS
	UNCL. EXC.	EXCESS EXC.	EMB.+	
1781+70.40				
	738,625	9,282	729,343	
2134+00.00				
TOTAL	738,625	# 9,282	# 729,343	

FOR INFORMATION ONLY

PAVEMENT MARKINGS▲				
ITEM	UNIT	INTERIM APPLICA-TION #	FINAL APPLICA-TION	TOTAL
STRIPING - WHITE PAINT	gallon	520		520
STRIPING - YELLOW PAINT	gallon	398		398
WORDS & SYMBOLS - WHITE PAINT	gallon	8		8
STRIPING - WHITE EPOXY	gallon		347	347
STRIPING - YELLOW EPOXY	gallon		265	265
WORDS & SYMBOLS - WHITE EPOXY	gallon		6	6
TEMPORARY STRIPING	linear feet			115,335
FINAL SWEEP AND BROOM	course mile			6.9

▲ INCLUDES QUATITIES FOR FLOWING WELLS REST AREA

BASED ON 2 APPLICATIONS.

RUMBLE STRIPS					
STATION		miles		gals	REMARKS
		RUMBLE STRIPS		EMULSIFIED ASPHALT FOG SEAL #	
		INTER- MITTENT	CENTERLINE TYPE 3		
FROM	TO				
1781+70.40	2134+00.00	6.6		387	LT.
1781+70.40	2134+00.00		6.6	387	
1781+70.40	2134+00.00	6.6		387	RT.
SUBTOTAL		13.2	6.6	1,160	
TOTAL		13.2	6.6	~	

FOR INFORMATION ONLY, INCLUDE IN THE COST OF RUMBLE STRIPS

TOPSOIL & SEEDING										
STATION		cu. yards	acres							REMARKS
		TOPSOIL SALVAGING & PLACING	SEED			FERTILIZER		CONDITION SEEDBED ①	MULCH - COMPOST	
			NO. 1	NO. 2	NO.3	NO. 1	NO. 2			
FROM	TO									
1781+70.40	1800+00.00	2,345	6.6		1.3	6.6		7.9		
1800+00.00	1825+00.00	3,964	11.1		1.7	11.1		12.8		
1825+00.00	1850+00.00	3,239	8.7		1.7	8.7		10.4		
1850+00.00	1875+00.00	2,914	6.9		1.7	6.9		8.6		
1875+00.00	1900+00.00	3,483	12.4		1.7	12.4		14.1		
1887+67.00	1890+85.00	595	1.1			1.1		1.1		BERM REMOVAL
1900+00.00	1925+00.00	3,344	10.9		1.7	10.9		12.6		
1925+00.00	1950+00.00	3,951	9.5		1.7	9.5		11.2		
1950+00.00	1975+00.00	3,820	7.7		1.7	7.7		9.4		
1975+00.00	2000+00.00	3,902	8.8		1.7	8.8		10.5		
2000+00.00	2025+00.00	4,004	10.3		1.7	10.3		12.0		
2025+00.00	2050+00.00	4,938	11.5		1.7	11.5		13.2		
2050+00.00	2075+00.00	4,622	9.9		1.7	9.9		11.6		
2075+00.00	2100+00.00	3,485	8.9		1.7	8.9		10.6		
2100+00.00	2125+00.00	3,314	9.5		1.7	9.5		11.2		
2125+00.00	2152+50.00	2,110	11.3		1.9	11.3		13.2		
1887+67.00	1890+85.00	450	0.8			0.8		0.8		TIMBER CREEK BERM REMOVAL
TOTAL		54,480	145.9	0.0	25.3	145.9	0.0	① 171.2	0.0	

① - FOR INFORMATION ONLY, INCLUDE IN THE COST OF SEEDING AREA 1 & 3

EMBANKMENT FOUNDATION TREATMENT*				
STATION		cu. yards	sq. yards	REMARKS
		SPECIAL EMBANK-MENT	STABILIZ-ATION GEOTEXTILE	
FROM	TO			
1886+00	1887+00	932	1,171	
TOTAL		932	1,171	

* SEE DETAIL

REMOVE STRUCTURE		
STATION	lump sum	REMARKS
	REMOVE STRUCTURE	
1810+75	0.2	TIMBER CREEK TRIBUTARY (NBI P00057247+03941, MDT ID#06030)
1886+30	0.3	TIMBER CREEK (NBI P00057248+08311, MDT ID#06031)
1935+11	0.3	SKULL CREEK (NBI P00057249+07481, MDT ID#06032)
2107+98	0.1	CEMETERY COULEE TRIBUTARY (NBI P00057253+00151, MDT ID#06033)
2124+67	0.1	CEMETERY COULEE (NBI P00057253+03311, MDT ID#06034)
TOTAL	1	