

Grant County Highway Department

Matthew Yavarow, P.E.
County Engineer
matthew.yavarow@co.grant.mn.us

P.O. Box 1005 224 3rd St. SE
Elbow Lake, MN 56531
Office 218-685-8301

Feb 13, 2025

To: Aggregate Supplier

RE: Request for Quotes
Aggregate Surfacing Class 5

Grant County is accepting quotes for approximately 14,000 tons of Aggregate Surfacing Class 5 to be used throughout the County.

The selected contractor will be required to produce and store a gravel stockpile within Grant County for County use as needed. This work is to be completed by June 30, 2025.

If providing a quote, please fill out the Quote sheet included and email to Highway@co.grant.mn.us by the end of the day March 31, 2025.

Please reach out to the Maintenance Supervisor – Pat McGrath at 218-685-8300 with questions.

Thanks,

Matthew Yavarow, P.E.
County Engineer

SPECIFICATIONS

GOVERNING SPECIFICATIONS

The Minnesota Department of Transportation Standard Specifications for Construction, 2020 Edition and SALT- Schedule of Materials Control - 2024, shall apply on this Contract except as modified or altered in the following special provisions.

SCOPE OF WORK

The Contractor is to provide all material, equipment, labor and land rights necessary to provide a Class 5 Aggregate stockpile located within Grant County for County use until exhausted.

(1717) AIR AND WATER POLLUTION

Pollution of natural resources of air, land and water by operations under this Contract shall be prevented, controlled and abated in accordance with the rules, regulations and standards adopted and established by the Minnesota Pollution Control Agency (MPCA), and in accordance with the provisions of 1717. The Contractor is responsible for any permits that may be needed to perform this work.

(1806) DETERMINATION AND EXTENSION OF CONTRACT TIME

The Contract time will be determined in accordance with the provisions of 1806 and the following:

Aggregate Surfacing Class 5 production shall be completed and available for County use by June 30, 2025.

(3138) AGGREGATE FOR SURFACE AND BASE COURSES

The contractor is responsible for removing any foreign material that is not suitable for Aggregate Surfacing Class 5, for example trees, branches, large rocks, metal, etc.

The Contractor shall store the County's material in a separate pile or piles designated for the County. The pile or piles shall be clearly identified as County property. The Contractor shall ensure that only the County removes material from the designated pile or piles.

The Contractor will use a Certified Belt Scale to weigh the Aggregate Surfacing Class 5 material.

The Contractor will provide weight tickets to the County. These tickets will be used to verify quantities produced.

The costs for all crushing, stockpiling, hauling, labor, easements, taxes or other expenses incurred with the processing of the stockpiled gravels shall be included in the unit price bid. Royalties for clay hauled to the pit will be paid by the county directly.

The Provisions of 1903 shall not apply.

The stockpiling method used shall be with a stacking conveyor. The stockpiles shall be uniform cone tops that are level to enable accurate measurements. Overlapping of circular Stockpiles will not be allowed. The aggregate shall be handled from production to stockpiling in such a manner to avoid segregation, contamination, and non-uniformity.

GRANT COUNTY
State of Minnesota

QUOTE SHEET FOR
Aggregate Surfacing Class 5

Total

Item I Stockpile 14,000 tons Aggregate Surfacing Class 5 @ \$_____/ton \$_____

Location of stockpile (Sec, Twp, Range) _____

Minnesota Counties are exempt from sales tax.

All bids shall be written in ink or typewritten on the forms furnished by the County.

QUOTE SUBMITTED BY:

Company_____

Name _____ Title _____

Signature _____ Date _____

Telephone _____

Complete quote sheet shall be emailed to highway@co.grant.mn.us with the
subject line: "Aggregate Surfacing Class 5 Quote".