

# PROPOSAL FOR THE PRODUCTION AND STOCKPIILING OF AGGREGATE

(Address)

(I) (WE) hereby certify that (I am) (we are) the only person (s) interested in this proposal as principal (s); that it is made and submitted without fraud or collusion with any other person, firm or corporation; that this is the sole proposal that (I am) (we are) submitting, or have an interest in. Further, examination has been made of this proposal and agreement form including the "Special Provisions" contained herein.

## SPECIAL PROVISIONS

1. The purpose and intent of this proposal is to furnish Wilkin County with all the equipment to crush and stockpile surface gravel at a specified gravel pit owned by Wilkin County.
2. The gravel shall be blended and produced as the Engineer or his representative directs. Blending of this material in the pit will be of prime concern in order to utilize all the materials available.
3. Aggregate shall meet the following gradation:

### **Wilkin County Class 5 Modified**

<u>Sieve Size</u>	<u>Total % Passing</u>
1 inch	100
3/4 inch	95 - 100
3/8 inch	65 - 95
No. 4	40 - 75
No. 10	25 - 70
No. 40	10 - 45
No. 200	6 - 12

Of the material passing the #200 sieve, it shall be a minimum of 50% clay. No strippings or black dirt allowed in material. If clay is necessary to add to the material, Wilkin County forces will haul it to the crushing site. Stripping procedures will be approved by Wilkin County before crushing operations begin.

4. Wilkin County forces plan to run gradation tests on a daily basis. If a test fails, the Contractor will be given 24 hours to correct the problem. If the problem continues after the 24 hour correction time, the processed material, during the failing test period, will be paid for at 50% of the bid price for crushing. Samples will be taken at the time of production, as directed by the County Engineer.
5. Aggregate shall be measured as indicated on the proposal, by volume of material deposited in the stockpile (stockpile measure), or by the use of a belt scale.

6. Sites from which material has been removed shall be left in a neat and presentable condition upon the completion of the work. Leveling of waste piles, trimming of slopes and pit bottoms, replacing the stripping and other cleanup work shall be done by and at the expense of the Contractor, unless otherwise arranged for to the satisfaction of the Engineer.
7. If any additional dozer or front end loader work is necessary at the pit sites, it shall be approved by the Engineer, and paid for at the prices quoted on the Proposal. Stripping and replacing topsoil is incidental to the bid price for each pit. There will be no stripping or topsoil replacement required.
8. Work Schedule:  
The Contractor shall indicate on the bid sheet the approximate date that he plans to begin work, and also the date that the work will be completed. The County has a definite, immediate, need for the processed material, and these dates will be a factor in the Contractor selection process.
9. No Bonds are required.
10. Wilkin County reserves the right to reject any or all bids, waive any irregularities and to award the bid in the best interest of Wilkin County.
11. As part of this quote, the Contractor supplying this quote will be required to supply Wilkin County with a list of 3 references of previous work as defined in this Proposal. If the Bidder cannot supply Wilkin County with this list, their quote will not be accepted. Please list references below.

Agency/Owner	Location	Phone #

## Wilkin County, Minnesota

Title
-------