

PIPESTONE COUNTY HIGHWAY DEPARTMENT
600 4TH STREET NW
P.O. BOX 276
PIPESTONE, MN. 56164

*******PROPOSAL*******

FOR HIGHWAY CONSTRUCTION AND MAINTENANCE PROJECTS WITH
BIDS RECEIVED UNTIL 10:30 O'CLOCK A.M. ON MAY 13, 2025
AT THE PIPESTONE COUNTY COURTHOUSE, 416 SOUTH HIAWATHA, PIPESTONE, MINNESOTA
BIDS WILL BE OPENED IMMEDIATELY FOLLOWING
AT THE PIPESTONE COUNTY COURTHOUSE, PIPESTONE, MINNESOTA

PROPOSAL OF _____

(NAME OF FIRM)

(ADDRESS)

(AREA CODE) TELEPHONE NUMBER

TO FURNISH AND DELIVER ALL MATERIALS AND TO PERFORM ALL WORK IN ACCORDANCE WITH THE CONTRACT, THE PLANS AND THE APPROVED DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION 2020 EDITION" (USING English UNITS), ON FILE IN THE OFFICE OF THE COMMISSIONER OF TRANSPORTATION, EXCEPT AS STATED OTHERWISE IN THE SPECIAL PROVISIONS WHICH ARE PART OF THIS PROPOSAL, FOR:

PIPESTONE COUNTY PROJECT: **SAP 059-647-001**

LOCATION: CSAH 47 (SEE ENCLOSED MAP)

TYPE OF WORK: BITUMINOUS SURFACING

LENGTH: 0.157 MILES

STARTING DATE: S.S. PROV.

COMPLETION DATE: September 1, 2025

NOTICE TO BIDDERS: In submitting a bid, **YOU MUST RETURN THIS COMPLETE PROPOSAL**. You must initial changes made in the Schedule of Prices in the Proposal and acknowledge addenda on the back cover sheet.

I hereby certify that this Proposal was prepared by me or under my direct supervision, and that I am a duly registered professional engineer under the laws of the State of Minnesota.



Registration No. 50636

Date: 4/7/2025

BID RIGGING IS A SERIOUS CRIME. IF YOU HAVE ANY INFORMATION CONCERNING COLLUSIVE BIDDING, EVEN A REQUEST TO SUBMIT A COMPLIMENTARY BID, PLEASE CALL THE MINNESOTA ATTORNEY GENERAL'S OFFICE AT TELE. NO. 651-296-1796

THIS PAGE INTENTIONALLY
LEFT BLANK


LEGEND

- BITUMINOUS - U.S.
- BITUMINOUS - STATE
- BITUMINOUS - C.S.A.H.
- BITUMINOUS - TOWNSHIP/COUNTY
- GRAVEL - TOWNSHIP/COUNTY
- GRAVEL - TOWNSHIP

PIPESTONE COUNTY

NICHOLAS G. BERGMAN
HIGHWAY ENGINEER
FEBRUARY 15, 2022

75 U.S. 23 STATE 16 C.S.A.H. 79 TWS.P./C.H.



SAP 059-647-001 OVERLAY LOCATION MAP


THIS PAGE INTENTIONALLY
LEFT BLANK

PIPESTONE COUNTY

WEIGHT POSTED ROADS & BRIDGES

NICHOLAS G. BERGMAN
HIGHWAY ENGINEER
NOVEMBER 15, 2024
(WEIGHT POSTED BRIDGES)
(6 BRIDGE STRUCTURES)

75 U.S. 23 STATE 16 C.S.A.H. 79 TWSP./CH.



THE PROSECUTOR GENERAL
STATE OF NEW YORK

To Pipestone County Board of Commissioners:

According to the advertisement of Pipestone County inviting proposals for the improvement of the section of highway hereinbefore named, and in conformity with the Contract, Plans, Specifications and Special Provisions pertaining thereto, all on file in the office of the Auditor of Pipestone County:

(I)(We) hereby certify that (I am)(we are) the only person(s) interested in this proposal as principal(s); that this proposal is made and submitted without fraud or collusion with any other person, firm or corporation at all; that an examination has been made of the site of the work and the Contract form, with the Plans, Specifications and Special Provisions for the improvement.

(I)(We) understand that the quantities of work shown herein are approximate only and are subject to increase or decrease; that all quantities of work, whether increased or decreased within the limits specified in MnDOT 1903 and 1402, are to be done at the unit prices shown on the attached schedule; that, at the time of opening bids, totals only will be read, but that comparison of bids will be based on the correct summation of item totals obtained from the unit prices bid, as provided in MnDOT 1301.

(I)(We) propose to furnish all necessary machinery, equipment, tools, labor and other means of construction and to furnish all materials specified, in the manner and at the time prescribed, all according to the terms of the Contract and Plans, Specifications, and the Special Provisions forming a part of this.

(I)(We) further propose to do all Extra Work that may be required to complete the contemplated improvement, at unit prices or lump sums to be agreed upon in writing before starting such work, or if such prices or sums cannot be agreed upon, to do such work on a Force Account basis, as provided in MnDOT 1904.

(I)(We) further propose to execute the form of Contract within 7 days after receiving written notice of award, as provided in MnDOT 1306.

(I)(We) further propose to furnish a Payment Bond and a Performance Bond each equal to the Contract Amount as required by MN Statute § 574.26, as security for the construction and completion of the improvement according to the Plans, Specifications and Special Provisions as provided in MnDOT 1305.

(I)(We) further propose to do all work according to the Plans, Specifications and Special Provisions, and to renew or repair any work that may be rejected due to defective materials or workmanship, before completion and acceptance of the Project by Pipestone County.

(I)(We) agree to all provisions of Minnesota Statutes, Section 181.59.

(I)(We) further propose to begin work and to prosecute and complete the same according to the time schedule set forth in the Special Provisions for the improvement.

(I)(We) assign to Pipestone County all claims for overcharges as to goods and materials purchased in connection with this Project resulting from antitrust violations that arise under the antitrust laws of the United States and the antitrust laws of the State of Minnesota. This clause also applies to subcontractors and first tier suppliers under this Contract.

THIS PAGE INTENTIONALLY
LEFT BLANK

NOTICE TO ALL BIDDERS

To report bid rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

THIS PAGE INTENTIONALLY
LEFT BLANK

**MINNESOTA DEPARTMENT OF TRANSPORTATION
NOTICE TO BIDDERS:
SUSPENSIONS/DEBARMENTS
THIS NOTICE APPLIES TO STATE-FUNDED AND FEDERALY-FUNDED PROJECTS**

Do not use suspended or debarred parties as subcontractors or material suppliers on this project!
Both the federal government and the State of Minnesota suspend and debar vendors. Review the list of suspended and debarred vendors before submitting a bid or a request to sublet. If your bid is based on using a suspended or debarred vendor, you will not be entitled to additional compensation for replacing the suspended or debarred vendor with a qualified vendor.

State Suspensions and Debarments

The State of Minnesota's list of suspended and debarred vendors is maintained by the Minnesota Department of Administration, Office of State Procurement, and can be found at this link: <https://mn.gov/admin/osp/government/suspended-debarred/index2.jsp> . This list includes parties suspended and debarred by the Minnesota Department of Transportation and the Minnesota Department of Administration.

Federal Suspensions and Debarments

The federal government maintains a searchable database of suspensions and debarments, called the System for Award Management (SAM), which is found at this link: <https://www.sam.gov/SAM/> . You can use the "Search Records" function without registering for an account.

September 29, 2023

RECEIVED
1983 MAR 10

**SPECIAL PROVISIONS
FOR
PIPESTONE COUNTY PROJECT
SAP 059-647-001**

INDEX TO SPECIAL PROVISIONS

Index of Sheets	Page 1
Index of Attachments	Page 2
Governing Specifications	Page 2

DIVISION A

I	Introduction	Page 1-A
II	Definitions	Page 1-A
III	Application & Understanding	Page 2-A
IV	Vendor Registration	Page 3-A
V	Labor Classifications.....	Page 3-A
VI	Wage Decision(s) & Wage Rate(s).....	Page 3-A
VII	Hours of Work.....	Page 5-A
VIII	Fringe Benefits.....	Page 5-A
IX	Overtime	Page 6-A
X	Payrolls and Statements.....	Page 7-A
XI	Apprentices, Trainees and Helpers	Page 8-A
XII	Independent Contractors, Owners, Supervisors, and Foreman	Page 9-A
XIII	Trucking	Page 9-A
XIV	Off-Site Facilities.....	Page 10-A
XV	Subcontracting Part of the Contract.....	Page 10-A
XVI	Site of Work Requirements.....	Page 11-A
XVII	Child Labor	Page 11-A
XVIII	Non-compliance and Enforcement	Page 11-A
Appendix A	Salaried Worker Wage Computation	Page 1-A
Appendix B	Fringe Benefit Credit.....	Page 1-A
Appendix C	Apprentice Rate of Pay.....	Page 1-A
Appendix D	Prevailing Wage Overtime Calculations	Page 2-A
	Notice to Bidders – Prompt Payment to Subcontractors	
	Minnesota Prevailing Wage Rates	
	Notice of Certification of Truck Rental Rates	

DIVISION S

S-1	Protection of Public Contracts	Page 1-S
S-2	(1203) Access to Proposal Package.....	Page 1-S
S-3	(1206) Preparation and Delivery of Proposal.....	Page 1-S
S-4	(1210) Revision of Proposal Package or Withdrawal of Proposals	Page 3-S
S-5	(1212) Opening of Proposals.....	Page 3-S
S-6	(1302) Award of Contract.....	Page 3-S
S-7	(1305) Requirement of Contract Bond.....	Page 4-S
S-8	(1404) Maintenance of Traffic, (1707) Public Safety, and (2563) Traffic Control.....	Page 4-S
S-9	(1505) Cooperation by Contractor	Page 5-S

S-10	(1506) Supervision by Contractor	Page 5-S
S-11	(1507) Utility Property and Service	Page 5-S
S-12	(1515) Control of Haul Roads	Page 6-S
S-13	(1602) Natural Material Sources	Page 6-S
S-14	(1603.2) Sampling and Testing	Page 6-S
S-15	(1701) Laws to be Observed	Page 6-S
S-16	(1803) Progress Schedules	Page 8-S
	(1806) Determination and Extension of Contract Time	Page 8-S
	(1807) Failure to Complete the Work on Time	Page 8-S
S-17	(1901) Measurement of Quantities	Page 9-S
S-18	(1903) Compensation for Altered Quantities	Page 10-S
S-19	(1906) Partial Payments	Page 10-S
S-20	(1908) Final Estimate and Payment – Conditions and Process	Page 10-S
S-21	(2051) Maintenance and Restoration of Haul Roads	Page 10-S
S-22	(2357) Bituminous Material for Tack Coat	Page 11-S
S-23	(2360) Plant Mixed Asphalt Pavement	Page 11-S
S-24	(2504) Adjust Valve Box – Water	Page 12-S
S-25	(2506) Adjust Frame and Ring Casting	Page 12-S

ATTACHMENTS

1. 2024 SALT "Schedule of Materials Control – Local Government Agency
2. Responsible Contractor Verification and Certification of Compliance
3. Non-Collusion Declaration
4. Schedule of Bid Prices

GOVERNING SPECIFICATIONS

The Minnesota Department of Transportation "Standard Specifications for Construction" 2020 Edition (Using English Units), shall apply on this contract except as modified or altered in the following special provisions.

STATE FUNDED ONLY CONSTRUCTION CONTRACTS

SPECIAL PROVISIONS DIVISION A - LABOR

I. INTRODUCTION

- A. **Policy Statement.** It is in the public interest that public buildings and other public works projects be constructed and maintained by the best means and the highest quality of labor reasonably available and that persons working on public works projects be compensated according to the real value of the services they perform.¹
- B. **State Regulations Govern.** This Contract is subject to the Minnesota Prevailing Wage Act², Minnesota Fair Labor Standards Act³, Minnesota Rules⁴, Minnesota Department of Labor and Industry (MnDLI) Wage Decision(s), and the MnDLI Truck Rental Rate Schedule.
- C. **Purpose.** These provisions: (1) outline your obligations under state and federal laws, rules and regulations; (2) explain the requirements necessary to demonstrate compliance; and (3) explain the processes that the Department will undertake to ensure compliance.
- D. **Questions or Resources.** Please visit the Minnesota Department of Transportation (MnDOT) Labor Compliance Unit (LCU) website at: www.dot.state.mn.us/const/labor.

II. DEFINITIONS

Many of the terms used in these provisions are defined in MnDOT's Standard Specifications for Construction,⁵ unless defined below.

- A. **Apprentice.** A Worker at least 16 years of age who is employed to learn an apprenticeable trade or occupation in a registered apprenticeship program.⁶
- B. **Bona Fide.** Made or carried out in good faith; authentic.⁷
- C. **Certified Payroll Report (CPR).** A report comprised of two components; (1) a payroll report, and (2) a statement of compliance report.⁸
- D. **Contractor.** An individual or business entity that is engaged in construction or construction service-related activities including trucking activities either directly or indirectly through a Contract, or by Subcontract with the Prime Contractor, or by a further Subcontract with any other person or business entity performing Work.⁹
- E. **Employer.** An individual, partnership, association, corporation, business trust, or other business entity that hires a Worker.¹⁰
- F. **Fringe Benefit.** An employment benefit given in addition to a Worker's wages or salary.¹¹
- G. **Independent Truck Owner/Operator (ITO).** An individual, partnership, or principal stockholder of a corporation who owns or holds a vehicle under lease and who contracts that vehicle and the owner's services to an entity which provides construction services to a public works project.¹²

¹ Minn. Stat. 177.41

² Minn. Stat. 177.41 to 177.44

³ Minn. Stat. 177.21 to 177.35

⁴ Minn. R. 5200.1000 to 5200.1120

⁵ MnDOT Standard Specifications for Construction, Section 1103

⁶ Minn. Stat. 178.011, Subdivision 2

⁷ The American Heritage College Dictionary, Third Edition, 2000

⁸ Minn. R. 5200.1106, Subpart 10

⁹ Minn. R. 5200.1106, Subpart 2(D)

¹⁰ Minn. Stat. 177.42, Subdivision 7

¹¹ The American Heritage College Dictionary, Third Edition, 2000

¹² Minn. R. 5200.1106, Subpart 7(A)

- H. **Journeyworker.** A person who has attained a level of skill, abilities, and competencies recognized within and industry as having mastered the skills and competencies required for the trade or occupation.¹³
- I. **Prime Contractor.** An individual or business entity that enters into a Contract with the Department.¹⁴
- J. **Subcontract.** A Contract that assigns some obligations of a prior Contract to another party.¹⁵
- K. **Substantially In Place.** Mineral aggregate is deposited on the project site directly or through spreaders where it can be spread from or compacted at the location where it was deposited.¹⁶
- L. **Total Prevailing Wage Rate.** The sum of the prevailing hourly “basic” and “fringe” rate that is established in a Wage Decision.
- M. **Trucking Broker (Broker).** An individual or business entity, the activities of which include, but are not limited to: contracting to provide trucking services in the construction industry to users of such services, contracting to obtain such services from providers of trucking services, dispatching the providers of the services to do Work as required by the users of the services, receiving payment from the users in consideration of the trucking services provided, and making payment to the providers for the services.¹⁷
- N. **Trucking Firm/Multiple Truck Owner (MTO).** Any legal business entity that owns more than one vehicle and hires the vehicles out for services to Trucking Brokers or Contractors on public works projects.¹⁸
- O. **Truck Rental Rate Schedule.** A document prepared by the MnDLI through a Contractor survey process that identifies the required hourly Total Prevailing Wage Rate and operating cost for various types of trucks that perform hauling activities (Work) under a Contract that is funded in whole or in part with state funds.¹⁹
- P. **Wage Decision.** A document prepared by the MnDLI through a Contractor survey process that identifies the required hourly basic rate of pay and hourly Fringe Benefits for various labor classifications that perform Work under a Contract that is funded in whole or in part with state funds.²⁰
- Q. **Work (Work).** All construction activities associated with a public works project, including any required hauling activities on-the-site-of or to-or-from a public works project and conducted pursuant to a Contract, regardless of whether the construction activity or Work is performed by the Prime Contractor, subcontractor, Trucking Broker, Trucking Firm (MTO), ITO, independent contractor, or employee or agent of any of the foregoing entities.²¹
- R. **Worker (Laborer or Mechanic).** A Worker in a construction industry labor class identified in or pursuant to Minnesota Rules 5200.1100, Master Job Classifications.²²

III. APPLICATION & UNDERSTANDING

- A. **Provisions & Prevailing Wage Rates Apply.** These provisions, along with the prevailing Wage Decision(s) that are incorporated into the Contract, apply to all Contractors contracting to do all or part of the Work.²³

¹³ Minn. Stat. 178.011, Subdivision 9

¹⁴ Minn. R. 5200.1106, Subpart 2(C)

¹⁵ The American Heritage College Dictionary, Third Edition, 2000

¹⁶ Minn. R. 5200.1106, Subpart 5(C)

¹⁷ Minn. R. 5200.1106, Subpart 7(C)

¹⁸ Minn. R. 5200.1106, Subpart 7(B)

¹⁹ Minn. R. 5200.1105

²⁰ Minn. R. 5200.1020 to 5200.1060

²¹ Minn. R. 5200.1106, Subpart 2(A)

²² Minn. R. 5200.1106, Subpart 5(A)

²³ Minn. Stat. 177.44, Subdivision 1

- B. **Truck Rental Rates Apply.** The Truck Rental Rate Schedule incorporated into the Contract applies to all hired trucking entities that perform covered hauling activities related to the project.²⁴
- C. **Prevailing Wage Terms Must Be Included in All Contracts.** The Prime Contractor is required to ensure that all subcontractors performing Work receive the Contract Wage Decision(s), Truck Rental Rate Schedule, and a copy of these provisions with their written Subcontracts, agreements and/or purchase orders.²⁵
- D. **Responsible for Understanding All Requirements.** Each Contractor is responsible for understanding all laws, rules, regulations, plans, and specifications that are incorporated physically, or by reference, into the Contract.²⁶
- E. **E-Verify.** For services valued in excess of \$50,000, the Contractor certifies that as of the date of services performed on behalf of State, the Contractor will have implemented or be in the process of implementing the federal E-Verify program for all newly hired employees in the United States who will perform work under the contract. The Prime Contractor is responsible to collect all subcontractor certifications and may do so utilizing the E-Verify Subcontractor Certification Form available at <http://www.mnd.admin.state.mn.us/doc/EverifySubCertForm.doc>. All subcontractor certifications must be kept on file with the Prime Contractor and made available to the State upon request.

IV. VENDOR REGISTRATION

Vendor Registration Required. A Contractor that performs Work, supplies material, or product must be registered with MnDOT. The Contractor must complete and submit a vendor form²⁷ to the MnDOT LCU²⁸, along with all applicable documentation that is required. This registration process is separate and distinct from other state agency requirements.

V. LABOR CLASSIFICATIONS

- A. **Labor Classification Assignment.** A Worker must be paid at least the Total Prevailing Wage Rate in the same or most similar trade or occupation.²⁹ To determine the appropriate labor classification for a Worker, a Contractor must refer to the Wage Decision(s) incorporated into the Contract, the labor classification descriptions for laborers and special crafts established in Minnesota Rules or the United States Department of Labor's Dictionary of Occupational Titles.³⁰
- B. **Labor Classification Clarification & Disputes.** A Contractor needing assistance in determining a labor classification must submit a Classification Clarification Request³¹ to the MnDOT LCU for a written decision. If the Contractor chooses to contest the classification assignment, it must provide written notice to the MnDOT LCU. The MnDOT LCU will forward the matter to the MnDLI for a final ruling.
- C. **Performing Work in Multiple Labor Classifications.** For Workers performing Work in multiple labor classifications, the Contractor must compensate at a minimum the Total Prevailing Wage Rate, and report the hours worked, in each applicable labor classification.³²

VI. WAGE DECISION(S) & WAGE RATE(S)

- A. **Applicability of a Highway and Heavy Wage Decision.** A highway and heavy Wage Decision applies to a Worker that is engaged in a construction activity or performing Work to construct or maintain a highway or other public works project, such as a road, street, airport runway, bridge,

²⁴ Minn. Stat. 177.44, Subdivision 3

²⁵ MnDOT Standard Specifications for Construction, Section 1801

²⁶ MnDOT Standard Specifications for Construction, Section 1701

²⁷ www.dot.state.mn.us/const/labor/documents/forms/contractorform2016.pdf for www.dot.state.mn.us/const/labor/documents/forms/truckvendorform2016.pdf

²⁸ lcusupport.dot@state.mn.us

²⁹ Minn. Stat. 177.44, Subdivision 1

³⁰ Minn. R. 5200.1101 and 1102 and USDOL Dictionary of Occupational Titles

³¹ <http://www.dot.state.mn.us/const/labor/documents/forms/classification-clarification-request.pdf>

³² Minn. Stat. 177.44, Subdivision 1

power plant, dam or utility³³ that is external to a sheltered enclosure (structure). This includes, but is not limited to, the following Work: site clearing; grading; excavating backfilling; paving; curbs; gutters; sidewalks; culverts; bridges; lighting systems; traffic management systems; installing of utilities out from an exterior meter; fuel islands; communication towers; or other activities similar to highway and/or heavy Work.

- B. **Applicability of a Commercial Wage Decision.** A commercial Wage Decision applies to a Worker that is engaged in a construction activity or performing Work to construct a sheltered enclosure (structure) with walk-in access for the purpose of housing persons, machinery, equipment or supplies.³⁴ This includes, but is not limited to, the following Work: constructing foundations, aprons, stoops; framing walls; installing windows, doors, tiling, plumbing, electrical, HVAC systems; roofing; installing utilities into the building from an exterior meter.
- C. **Pay According to Wage Decision(s).**
1. **Contract with One Wage Decision.** If the Contract contains one Wage Decision, the Contractor must examine the Wage Decision and compensate the Worker at a minimum the Total Prevailing Wage Rate for the appropriate labor classification(s).
 2. **Contract with Multiple Highway/Heavy Wage Decisions.** If the Contract contains multiple Highway/Heavy Wage Decisions, the Contractor must examine each Wage Decision and compensate the Worker, at a minimum, the Total Prevailing Wage Rate that is the greatest³⁵ for the appropriate labor classification(s).
 3. **Contract with Highway/Heavy and Commercial Wage Decision(s).** If the Contract contains a Highway/Heavy and Commercial Wage Decision(s), the Contractor must first determine which Wage Decision is applicable to the Worker. The Contractor must then compensate the Worker, at a minimum, the Total Prevailing Wage Rate for the appropriate labor classification(s).
- D. **Must Pay Total Prevailing Wage Rate.** A Contractor must compensate each Worker, at a minimum, the Total Prevailing Wage Rate(s) for all hours worked on the project for the appropriate labor classification(s).³⁶
- E. **Missing Wage Rate.** If a Wage Decision fails to include a wage rate for a labor classification(s) that will be utilized on a project, the Contractor must obtain a wage rate prior to furnishing an estimate, quote or bid.³⁷
1. **Wage Rate Request.** A Contractor must complete a Request for Rate Assignment form³⁸ and submit it to the MnDOT LCU³⁹ for processing.
 2. **No Contract Price Adjustment for Missing Wage Rate.** If MnDLI determines that a higher wage rate applies, the Department will not reimburse the Contractor.
- F. **Salaried Worker.** A salaried Worker is not exempt from these Provisions. A Contractor must convert the Worker's salary to an average hourly rate of pay by dividing the Worker's salary by the total number of hours Worked (government and non-government) during the pay period.⁴⁰ A salaried Worker must be included on a CPR.
- G. **Reduction in Standard (Private) Contractual Regular Rate of Pay Prohibited.** A Contractor must not reduce a Worker's standard, contractual regular rate of pay when the prevailing wage rate(s) certified by the MnDLI is less.⁴¹

³³ Minn. R. 5200.1010, Subdivision 3

³⁴ United States Department of Labor All Agency Memorandum #130

³⁵ Minn. Stat. 177.44, Subdivision 4

³⁶ Minn. Stat. 177.44, Subdivision 1

³⁷ Minn. R. 5200.1030, Subpart 2a(C)

³⁸ <http://www.dot.state.mn.us/const/labor/documents/forms/request-for-rate-assignment.doc>

³⁹ lcusupport.dot@state.mn.us

⁴⁰ Refer to Appendix A

⁴¹ Minn. Stat. 181.03, Subdivision 1(2)

- H. **Prohibited Payment Practices.** A Contractor is prohibited from taking (accepting) a rebate for the purpose of reducing or otherwise decreasing the value of the compensation paid.
- I. **Prohibited Deductions.** No deductions, direct or indirect, may be made for the items listed below which when subtracted from wages would reduce the wages below Minnesota's minimum wage rate as established in section 177.24⁴²
1. **Uniforms.** Purchased or rented uniforms or specifically designed clothing that is required by the Employer, by the nature of employment, or by statute, or as a condition of employment, which is not generally appropriate for use except in that employment.
 2. **Equipment.** Purchased or rented equipment used in employment, except tools of a trade, a motor vehicle, or any other equipment which may be used outside the employment. The cost of the Worker's use of equipment used outside of employment, such as tools, a motor vehicle, cell phone, may be deducted only if an agreement between the Employer and employee existed prior to the deduction.
 3. **Supplies.** Consumable supplies required in the course of employment.
 4. **Travel Expenses.** Travel expenses in the course of employment except those incurred in traveling to and from the employee's residence and place of employment.

VII. HOURS OF WORK

- A. **Work Performed Under the Contract.** A Worker performing Work is subject to prevailing wage for all hours associated with the Contract⁴³, unless the Worker is exempt under state law.⁴⁴
- B. **Wait Time Subject to Prevailing Wage.** A Worker who is required to remain on the project and is waiting to Work because of the fault of the Contractor is considered "engaged to wait" and subject to prevailing wage for the time spent, unless the Worker is completely relieved of duty and free to leave the project for a defined period of time.

VIII. FRINGE BENEFITS

- A. **Funded Fringe Benefit Plan Criteria.** In order for a funded Fringe Benefit (e.g., health/medical insurance, disability insurance, life insurance, pension, etc.) to be considered and creditable towards the Total Prevailing Wage Rate it must be:⁴⁵
1. a contribution irrevocably made by a Contractor on behalf of an Worker to a financially responsible trustee, third person, fund, plan, or program;
 2. carried out under a financially responsible plan or program;
 3. legally enforceable;
 4. communicated in writing to the Worker; and
 5. made available to the Worker once he/she has met all eligibility requirements.
- B. **Unfunded Fringe Benefit Plan Criteria.** In order for a unfunded Fringe Benefit (e.g., vacation, holiday, sick leave, etc.) to be considered and creditable towards the Total Prevailing Wage Rate it must be:⁴⁶
1. reasonably anticipated to provide a benefit;
 2. a commitment that can be legally enforced;

⁴² Minn. Stat. 177.24, Subdivision 4(1-4)

⁴³ Minn. Stat. 177.44, Subdivision 1

⁴⁴ Minn. Stat. 177.44, Subdivision 2 or Minn. R. 5200.1106, Subpart 4

⁴⁵ Minn. Stat. 177.42, Subdivision 6

⁴⁶ Minn. Stat. 177.42, Subdivision 6

3. carried out under a financially responsible plan or program;
 4. communicated in writing to the Worker; and
 5. made available to the Worker once he/she has met all eligibility requirements.
- C. **Fringe Benefit Contributions for Hours Worked.** A Contractor that provides Fringe Benefits to a Worker must make contributions, not less than quarterly⁴⁷, for all hours worked,⁴⁸ including overtime hours, unless it's a defined benefit or contribution plan that provides for immediate participation and immediate or essentially immediate vesting (see subpart D2 of this section).
- D. **Hourly Fringe Benefit Credit.** An hourly Fringe Benefit credit toward the Total Prevailing Wage Rate must be determined separately for each Worker based on one or more of the following methods:
1. **Monthly, Quarterly or Annual Computation Methods.** A Contractor must compute its monthly, quarterly or annual cost of a particular Fringe Benefit and divide that amount by the estimated total number of hours worked (government and non-government) during the time frame used.⁴⁹ Typical plans that require monthly, quarterly or annual computations include but are not limited to: health/medical insurance, disability insurance, life insurance, vacation, holiday, sick leave and defined benefit or contribution pension plans that do not provide for immediate participation and immediate or essentially immediate vesting.
 2. **Fringe Benefit Credit not Requiring Monthly, Quarterly or Annual Computation Methods.** A defined benefit or contribution pension plan that allows for a higher hourly rate of contribution for government work (prevailing wage) than non-government (non-prevailing wage) will be fully credited only if the plan provides for immediate participation and immediate or essentially immediate vesting.
- E. **Wages In Lieu of Fringe Benefits.** A Contractor that does not provide full Fringe Benefits must compensate a Worker the difference between the Total Prevailing Wage Rate and the rate actually paid for the appropriate labor classification(s). The compensation paid is considered wages and subject to tax liabilities.
1. **Overtime.** The cash equivalent (wages paid) made in lieu of Fringe Benefits is excluded from the overtime calculation requirement, unless the cash equivalent (wages paid) is part of the Worker's standard straight time wage.
- F. **Administrative Costs Not Creditable.** Administrative expenses incurred by a Contractor in connection with the administration of a Bona Fide Fringe Benefit plan are not creditable towards the Total Prevailing Wage Rate.
- G. **Federal, State & Local Fringe Benefit Credit Prohibited.** No credit is allowed for benefits required by federal, state or local law, such as: worker's compensation, unemployment compensation, and social security contributions.⁵⁰

IX. OVERTIME

- A. **Overtime after 8 Hours per Day or 40 Hours per Week.** A Contractor must not permit or require a Worker to work longer than the prevailing hours of labor unless the Worker is paid for all hours in excess of the prevailing hours at a rate of at least 1.5 times the hourly basic rate of pay.⁵¹ The prevailing hours of labor is defined as not more than 8 hours per day and more than 40 hours per week.⁵²

⁴⁷ 29 CFR, Part 5.5(a)(1)(i)

⁴⁸ Government and non-government Work

⁴⁹ Refer to Appendix B

⁵⁰ Minn. Stat. 177.42, Subdivision 6

⁵¹ Minn. Stat. 177.44, Subdivision 1 and Refer to Appendix D

⁵² Minn. Stat. 177.42, Subdivision 4

- B. **Wages in Lieu of Fringe Benefits Overtime.** Wages paid in Lieu of Fringe Benefits must be paid for all hours worked under the contract.
- C. **Multiple Labor Classifications and Overtime.** A Worker employed in multiple labor classifications throughout a workweek must be compensated at the applicable labor classification overtime rate in effect during the hours worked in excess of 8 hours per day or 40 hours per week.
- D. **Federal Fair Labor Standards Act (FLSA) and Overtime.** A Contractor subject to the FLSA may be subject to additional overtime compensation requirements.

X. PAYROLLS AND STATEMENTS

- A. **Reporting.** Each Contractor that is performing Work must submit a CPR(s) to the Department.
 - 1. **Payroll Report (Paper).** Each Contractor performing Work must submit a paper (written) payroll report to the Department. The payroll report is available on the MnDOT LCU website.⁵³
 - 2. **Statement of Compliance (Paper).** Each Contractor's paper (written) payroll report must include a paper (written) "Statement of Compliance Form". The "Statement of Compliance Form" must: (1) state whether or not Fringe Benefits are provided to a Worker; (2) provide a description of each benefit, the hourly contribution made on behalf of each Worker, along with fund/plan information; and (3) a signature attesting that the payroll and Fringe Benefit information provided is truthful and accurate.⁵⁴
 - 3. **Electronic Reporting.** If the Contract is subject to electronic reporting, each Contractor performing Work must submit a CPR(s) using the AASHTOWare, Civil Rights Labor (CRL) system. Refer to the **Special Provisions Division S – "Electronic Submission of Payrolls and Statements"** which is incorporated into and found elsewhere in the Contract for detailed requirements.
- B. **Biweekly Payroll Reporting and Payment of Wages.** A CPR(s) must be submitted no later than 14 calendar days after the end of each Contractor's pay period⁵⁵ to the Department. A Contractor must pay its employees at least once every 14 calendar days.⁵⁶
- C. **Payroll Report Data.** Each payroll report must include all Workers that performed Work and provide at a minimum the following information:⁵⁷
 - 1. Contractor's name, address, and telephone number.
 - 2. State project number.
 - 3. Contract number (if applicable).
 - 4. Project number.
 - 5. Payroll report number.
 - 6. Project location.
 - 7. Workweek end date.
 - 8. Each Worker's name, home address, and social security number.⁵⁸
 - 9. Labor classification(s) title(s) and optional three-digit code for each Worker.

⁵³ www.dot.state.mn.us/const/labor/certifiedpayroll.html

⁵⁴ Minn. R. 5200.1106, Subpart 10

⁵⁵ Minn. Stat. 177.43, Subdivision 3

⁵⁶ Minn. Stat. 177.30 (a)(4)

⁵⁷ Minn. Stat. 177.30 (a)(1-4) and Minn. R. 5200.1106, Subpart 10

⁵⁸ Minn. R. 5200.1106, Subpart 10A & Minn. Stat. 13.355, Subdivision 1

10. Hours worked daily and weekly in each labor classification, including overtime hours, for each Worker.
11. Wage rate paid to each Worker for straight time and overtime.
12. Authorized legal deductions for each Worker.
13. Project gross amount, weekly gross amount, and net wages paid to each Worker.

- D. **Prime Contractor to Ensure Compliance.** The Prime Contractor must review the CPR(s) submitted by each lower tier Contractor and sign the "Statement of Compliance Form".⁵⁹ The Prime Contractor must ensure that each lower tier Contractor's CPR(s) include all Workers that performed Work and accurately reflect labor classifications, hours worked, regular and overtime rates of pay, gross earnings for the project and Fringe Benefits.⁶⁰
- E. **Retention of CPR(s).** The Prime Contractor must keep its written CPR(s), including those of all lower tier Contractors, for three (3) years after the final payment is issued.⁶¹
- F. **Retention of Employment-Related Records.** Each Contractor must keep employee records, including, but not limited to: Fringe Benefit statements, time cards, payroll ledgers, check registers and canceled checks⁶² for at least three (3) years after the final payment is issued.⁶³ Other laws may have longer retention requirements.
- G. **Detailed Earning Statement.** At the end of each pay period, each Contractor must provide every Worker, in writing or by electronic means, an accurate, detailed earnings statement.⁶⁴
- H. **Reports and Records Request.** Upon a request from the Department, the Prime Contractor must promptly furnish copies of CPR(s) for its Workers and those of all lower tier Contractors, along with employment-related records, documents, and agreements that the Department considers necessary to determine compliance.⁶⁵

XI. APPRENTICES, TRAINEES AND HELPERS

- A. **Apprentice.** An Apprentice will be permitted to Work at less than the prevailing basic hourly rate only if the Apprentice is:
 1. Registered with the U.S. Department of Labor (DOL), Bureau of Apprenticeship and Training or MnDLI Division of Voluntary Apprenticeship.⁶⁶
 2. Performing Work of the trade, as described in the apprenticeship agreement.
 3. Compensated according to the rate specified in the program for the level of progress.⁶⁷
 4. Supervised by a Journeyworker from the same company, in accordance with the program ratio requirements.⁶⁸
- B. **Ratio Requirement.** If an approved apprenticeship program fails to define a ratio allowance, the first Apprentice must be supervised by a Journeyworker within the same trade or occupation. Any subsequent Apprentice must be supervised by an additional three Journeyworkers.⁶⁹

⁵⁹ MnDOT Standard Specifications for Construction, Section 1701

⁶⁰ MnDOT Standard Specifications for Construction, Section 1801

⁶¹ Minn. Stat. 177.30 (a)(5)

⁶² Minn. R. 5200.1106, Subpart 10

⁶³ Minn. Stat. 177.30 (a)(5)

⁶⁴ Minn. Stat. 181.032

⁶⁵ Minn. Stat. 177.44, Subdivision 7; Minn. Stat. 177.33(a)(5)

⁶⁶ Minn. R. 5200.1070, Subpart 1

⁶⁷ Minn. R. 5200.1070, Subpart 1 and Refer to Appendix C

⁶⁸ Minn. Stat. 178.036, Subdivision 5

⁶⁹ Minn. Stat. 178.036, Subdivision 5

- C. **Failure to Comply with Apprenticeship Requirements.** If a Contractor fails to demonstrate compliance with the terms established in this section, the Contractor must compensate the Apprentice not less than the applicable Total Prevailing Wage Rate for the actual classification of labor performed.⁷⁰
- D. **Trainee and Helper.** A trainee or helper is not exempt from prevailing wage under state law. The Contractor must assign the trainee or helper a labor classification that is the "same or most similar"⁷¹ and compensate the trainee or helper for the actual Work performed regardless of the trainee's or helper's skill level.

XII. INDEPENDENT CONTRACTORS, OWNERS, SUPERVISORS, AND FOREMAN

- A. **Independent Contractor.** An independent contractor (IC) that is not an Independent Truck Owner/Operator (ITO), who is performing Work must be properly classified and compensated.⁷² The IC must submit a CPR(s) to the Department. If the IC does not receive an hourly wage, but instead a weekly, biweekly, monthly or quarterly distribution for performance, the IC must calculate its hourly rate of pay by dividing the weekly, biweekly, monthly, or quarterly company distribution by all hours worked during that time frame and report the information on a CPR. If necessary, the Department may request documentation from the IC to determine how the hourly wage rate was calculated.⁷³
- B. **Owners, Supervisors and Foreman.** An owner, supervisor, or foreman performing Work is subject to prevailing wage and must be properly classified, compensated and reported.⁷⁴

XIII. TRUCKING

- A. **Covered Hauling Activities.** A Contractor must ensure that all Workers, including hired Trucking Brokers, MTOs and ITOs are paid the applicable Total Prevailing Wage Rate or truck rental rate for the following Work:
1. The hauling of any or all stockpiled or excavated materials on the project work site to other locations on the same project even if the truck leaves the work site at some point.⁷⁵
 2. The delivery of materials from a non-commercial establishment to the project and the return haul to the starting location either empty or loaded.⁷⁶
 3. The delivery of materials from another construction project site to the public works project and the return haul, either empty or loaded. Construction projects are not considered commercial establishments.⁷⁷
 4. The hauling required to remove any materials from the project to a location off the project site and the return haul, either empty or loaded from other than a commercial establishment.⁷⁸
 5. The delivery of materials or products by trucks hired by a Contractor, subcontractor, or agent thereof, from a commercial establishment.⁷⁹
 6. The delivery of sand, gravel, or rock, by or for a commercial establishment, which is deposited "substantially in place," either directly or through spreaders from the transporting vehicles is work under the contract. In addition, the return haul to the off-site facility empty or loaded is also considered work under the contract.⁸⁰

⁷⁰ Minn. R. 5200.1070, Subpart 3

⁷¹ Minn. Stat. 177.44, Subdivision 1

⁷² Minn. Stat. 177.44, Subdivision 1

⁷³ Minn. Stat. 177.30(a)(5); Minn. Stat. 181.723

⁷⁴ Minn. Stat. 177.44, Subdivision 1

⁷⁵ Minn. R. 5200.1106, Subpart 3B(1)

⁷⁶ Minn. R. 5200.1106, Subpart 3B(2)

⁷⁷ Minn. R. 5200.1106, Subpart 3B(3)

⁷⁸ Minn. R. 5200.1106, Subpart 3B(4)

⁷⁹ Minn. R. 5200.1106, Subpart 3B(5)

⁸⁰ Minn. R. 5200.1106, Subpart 3B(6)

- B. Hauling Activities Not Subject to Prevailing Wage or Truck Rental Rates.** A Contractor may exclude a Worker, including hired Trucking Brokers, MTOs and ITOs from prevailing wage or truck rental rates for the Work described in (1-2) of this section. However, this Work may be considered hours worked and subject to standard compensation pursuant to the Minnesota Fair Labor Standards Act.
1. The delivery of processed or manufactured goods to a public works project by the employees of a commercial establishment including truck owner-operators hired by and paid by the commercial establishment, unless it is the delivery of mineral aggregate that is incorporated into the work under the contract by depositing the material substantially in place.⁸¹
 2. The delivery of oil offsite, as an example, to a Prime Contractor's permanent (commercial) asphalt mixing facility that is not to, from, or on the project Work site.⁸²
- C. Repair, Maintenance & Waiting to Load Time.** An ITO and MTO must be paid the truck rental rate for time spent repairing or maintaining the truck owner-operator's equipment, and for waiting to load or unload if the repair, maintenance, or wait time is the fault of the Trucking Broker, Contractor, its agent or employees.⁸³
- D. Month End Trucking Report.** A Contractor that acquires the services of an ITO or MTO must submit a "MnDOT – MTO and/or ITO Month-End Trucking Report", and a "MnDOT – Month-End Trucking Statement of Compliance Form" to the Department for each month hauling activities are performed under the Contract.⁸⁴ The forms are available on the MnDOT LCU website.⁸⁵
- E. Broker Fee.** A truck broker contracting to provide trucking services directly to a prime contractor or subcontractor is allowed to assess a broker fee.

XIV. OFF-SITE FACILITIES

- A. Off-Site Facility Activities Subject to Prevailing Wage.** A Contractor must ensure that all Workers performing Work at a covered off-site facility are paid the applicable Total Prevailing Wage Rate for the following Work:
1. The processing or manufacturing of material at a Prime Contractor's off-site facility that is not a separately held commercial establishment.⁸⁶
 2. The processing or manufacturing of material at an off-site facility that is not considered a commercial establishment.⁸⁷
- B. Off-Site Facility Activities Not Subject to Prevailing Wage.** A Contractor may exclude a Worker from prevailing wage for the following work:
1. The processing or manufacturing of material or products by or for a commercial establishment.⁸⁸
 2. The work performed by Workers employed by the owner or lessee of a gravel or borrow pit that is a commercial establishment, even if the screening, washing or crushing machines are portable.⁸⁹

XV. SUBCONTRACTING PART OF THE CONTRACT

⁸¹ Minn. R. 5200.1106, Subpart 4(C)

⁸² J.D. Donovan, Inc. vs. Minnesota Department of Transportation, 878 N.W.2d 1 (2016)

⁸³ Minn. R. 5200.1106, Subpart 8(A)(1)

⁸⁴ Minn. R. 5200.1106, Subpart 10

⁸⁵ <http://www.dot.state.mn.us/const/labor/forms.html>

⁸⁶ ALJ Findings of Fact, Conclusions of Law, and Recommendation, Conclusions (7), Case #12-3000-11993-2

⁸⁷ Minn. R. 5200.1106, Subpart 3(A)

⁸⁸ Minn. R. 5200.1106, Subpart 4(A)

⁸⁹ Minn. R. 5200.1106, Subpart 4(B)

The Prime Contractor must include the Contract Special Provisions, Wage Decision(s) and Truck Rental Rate Schedule in all Subcontracts, agreements and purchase orders with lower tier Contractors.⁹⁰ This requirement also applies to all lower tier subcontractors.

XVI. SITE OF WORK REQUIREMENTS

- A. **Poster Board.** The Prime Contractor must construct and display a poster board containing all required posters. The poster board must be accurate, legible, and accessible to all project Workers from the first day of Work until the project is one hundred percent (100%) complete.⁹¹ A poster board at an off-site location, or inside a construction trailer, does not meet this requirement.
- B. **How to Obtain a Poster Board.** The Prime Contractor may obtain the required posters and the necessary contact information that is required to be inserted on each poster by visiting the MnDOT LCU website.⁹²
- C. **Employee Interviews.** The Contractor must permit representatives from the Department or other governmental entities⁹³ to interview Workers at any time during working hours on the project.⁹⁴

XVII. CHILD LABOR

- A. **No Worker under the Age of 18.** No Worker under the age of 18 is allowed to perform Work on a Project Site, except pursuant to Section XVII B below.⁹⁵
- B. **Parental Supervision.** A Worker under the age of 18 may perform Work on a Project Site if all of the following criteria are met:
 - 1. The Contractor (Employer) is not subject to FLSA.
 - 2. The Worker is employed in a corporation owned solely by one or both parents.
 - 3. The Worker is supervised by the parent(s).
 - 4. The Worker is not working in a hazardous occupation.⁹⁶
- C. **Removal of Minor from Project.** The Engineer or inspector may remove a Worker that appears to be under the age of 18 from the Project Site until the Contractor or Worker can demonstrate proof of age and compliance with all applicable federal and state regulations.⁹⁷

XVIII. NON-COMPLIANCE AND ENFORCEMENT

- A. **Case-by-Case Enforcement.** The Department has the authority to enforce the prevailing wage law on a case-by-case.⁹⁸
- B. **Prime Contractor Responsible for Unpaid Wages.** The Prime Contractor will be held liable for any unpaid wages to its Workers or those of any lower tier Contractor.⁹⁹
- C. **Enforcement Options.** If evidence shows that a Contractor has violated prevailing wage requirements, or these Special Provisions, the Department may, after written notice, implement one or more of the following:

⁹⁰ MnDOT Standard Specifications for Construction, Section 1801

⁹¹ Minn. Stat. 177.44, Subdivision 5

⁹² www.dot.state.mn.us/const/labor/posterboards

⁹³ MnDOT, U.S. DOL, U.S. Department of Transportation, Federal Highways Administration

⁹⁴ MnDOT Standard Specifications for Construction, Section 1511

⁹⁵ Minn. R. 5200.0910, Subpart F; 29 CFR Part 570.2(a)(ii)

⁹⁶ Minn. R. 5200.0930, Subpart 4

⁹⁷ Minn. Stat. 181A.06, Subdivision 4; MnDOT Standard Specifications for Construction, Section 1701

⁹⁸ See International Union of Operating Engineers, Local 49 v. MnDOT, No. C6-97-1582, 1998 WL 74281, at *2 (Minn. App. Feb. 24, 1998)

⁹⁹ MnDOT Standard Specifications for Construction, Section 1801

1. **Withholding Payment.** The Department may withhold from the Prime Contractor payments relating to prevailing wage underpayments.¹⁰⁰
2. **Non-Responsible Contractor.** The Department may reject a bid from a Prime Contractor that has received two (2) or more Determination Letters within a three (3) year period from the Department finding an underpayment by the Contractor to its own employees.¹⁰¹
3. **Default.** The Department may take the prosecution of the Work out of the hands of the Prime Contractor, place the Contractor in default, and terminate the Contract for failure to comply.¹⁰²
4. **Suspension or Debarment.** The Department may refer violations and matters of non-compliance by a Contractor to the Minnesota Department of Administration for suspension or debarment proceedings.¹⁰³
5. **County Attorney.** The Department may refer suspected criminal violations by Contractor to the appropriate local county attorney for prosecution.¹⁰⁴
6. **Financial Penalties.** Any Contractor who violates the state prevailing wage law is guilty of a misdemeanor and may be fined not more than \$300 or imprisoned not more than 90 days or both. Each day that the violation continues is a separate offense.¹⁰⁵ A Contractor may be fined up to \$1,000 for each failure to maintain records.¹⁰⁶
7. **False Claims Act Violation.** All required payroll and certification reports are legal documents; knowing falsification of the documents by a Contractor may result in civil action and/or criminal prosecution¹⁰⁷ and may be grounds for debarment proceedings.¹⁰⁸
8. **Compliance Order.** The Department may request that MnDLI issue a compliance order to a Contractor for violations of the state prevailing wage law. If the Contractor is found to have committed a violation, liquidated damages and other costs may be assessed against the Employer.¹⁰⁹
9. **Private Right of Action.** The Department may direct an employee to pursue a civil action in district court against its Employer for failure to comply with the proper payment of wages.¹¹⁰ If the Employer is found to have committed a violation, liquidated damages and other costs may be assessed against the Employer.¹¹¹
10. **Fringe Benefits; Misdemeanor.** A Contractor that is obligated to deposit Fringe Benefit contributions on behalf of a Worker into a financially responsible trustee, third person, fund, plan, or program and fails to make timely contributions is guilty of a gross misdemeanor or other violations under federal law.¹¹²

¹⁰⁰ MnDOT Standard Specifications for Construction, Section 1906

¹⁰¹ Minn. Stat. 16C.285

¹⁰² MnDOT Standard Specifications for Construction, Section 1808

¹⁰³ Minn. R. 1230.1150, Subpart 2(A)(4)

¹⁰⁴ Minn. Stat. 177.44, Subdivision 7

¹⁰⁵ Minn. Stat. 177.44, Subdivision 6

¹⁰⁶ Minn. Stat. 177.30(b)

¹⁰⁷ Minn. Stat. 15C.02; , Minn. Stat. 161.315; Minn. Stat. 177.32; Minn. Stat. 177.43, Subdivision 5, Minn. Stat. 609.63

¹⁰⁸ Minn. Stat. 161.315 and Minn. Stat. 609.63

¹⁰⁹ Minn. Stat. 177.43, Subdivision 6a

¹¹⁰ Minn. Stat. 177.27, Subdivision 8

¹¹¹ Minn. Stat. 177.27, Subdivision 10

¹¹² Minn. Stat. 181.74, Subdivision 1

**THE FOLLOWING APPENDICES ARE FOR
EXPLANATORY PURPOSES ONLY.
FOR SPECIFIC QUESTIONS, PLEASE CONTACT LCU.¹¹³**

APPENDIX A**SALARIED WORKER WAGE COMPUTATION**

Salaried Workers. In order to convert the Worker's salary into an hourly rate of pay, divide the employee's weekly, bi-weekly or monthly earnings by the total number of hours Worked (government and non-government), including overtime hours for the time period used.¹¹⁴

$$\text{\$800.00 (weekly salary) / 40 (total weekly hours) = \$20.00}$$

$$\text{\$1,600.00 (bi-weekly salary) / 80 (total bi-weekly hours) = \$20.00}$$

$$\text{\$3,200.00 (monthly salary) / 160 (total monthly hours) = \$20.00}$$

APPENDIX B**FRINGE BENEFIT CREDIT**

Fringe Benefit Credit Calculation. The Employer contributes monthly (\\$600.00) for medical insurance on behalf of a Worker. In order to calculate the projected hourly credit that the Employer can take, the Employer should: (1) add the monthly contributions for each Worker, (2) multiply by twelve (12) months, and (3) divide the total cost of the benefit by the total hours worked (government and non-government)¹¹⁵ (see annual example below). Quarterly and monthly examples are also provided.

Annual: $(\$600.00) \times (12 \text{ months}) = \$7,200.00$
 $(\$7,200.00) / (2080 \text{ hours}) = \underline{\text{\$3.46 per hour credit}}$

Quarterly: $(\$600.00) \times (3 \text{ months}) = \$1,800.00$
 $(\$1,800.00) / (520 \text{ hours}) = \underline{\text{\$3.46 per hour credit}}$

Monthly: $(\$600.00) \times (1 \text{ month}) = \600.00
 $(\$600.00) / (173 \text{ hours}) = \underline{\text{\$3.47 per hour credit}}$

End of Year Self-Audit. At the end of the calendar year, the Contractor must conduct an audit to determine if the hourly fringe benefit credit taken for each Worker was accurate. The Contractor must calculate the total annual fringe benefits paid on behalf of each Worker and divide that amount by the total number of hours worked (government and non-government) by that Worker. If the hourly fringe benefit credit was less than what was reported on a CPR, the contractor must compensate the Worker the hourly difference, multiplied by the total hours worked under the Contract.

APPENDIX C**APPRENTICE RATE OF PAY**

State Requirements. The Apprentice must be compensated according his/her level of progress, which is expressed as a percentage of the Journeyworker wage that is established in the program.

$$\text{Journeyworker Wage Established in Program} = \text{\$25.00}$$

$$\underline{\text{Apprentice Level of Progress} = 60\%}$$

$$(\text{\$25.00}) \times (.60) = \text{\$15.00}$$

¹¹³ lcu.support.dot@state.mn.us or (651) 366-4238

¹¹⁴ United States Department of Labor Field Operation Handbook, Section 15f08

¹¹⁵ United States Department of Labor Field Operation Handbook, Section 15f12

APPENDIX D**PREVAILING WAGE OVERTIME CALCULATION**

Overtime Hourly Rate of Pay. Here is the formula to calculate the required minimum overtime.¹¹⁶

$$OT = (PW * .5) + (HW) + (RF) + (F)$$

Definition of OT Acronyms

OT: overtime.

PW: the basic hourly prevailing wage rate established in a federal and/or state prevailing Wage Decision.

HW: hourly wage rate paid to a Worker.

RF: remaining fringe, which means the difference between the Contract hourly Fringe Benefit rate and the actual hourly Fringe Benefit rate paid by the Contractor to a third party on behalf of a Worker.

F: Fringe Benefit contributions that are bona-fide and contributed by an Employer to a third party on behalf of a Worker.

The Total Prevailing Wage Rate for a Worker is \$30.00, which is comprised of an hourly basic rate of \$20.00 and an hourly fringe rate of \$10.00. The table below includes various hourly basic and Fringe Benefit payments that a Contractor could potentially make to a Worker.

OT CALCULATION FORMULA AND EXAMPLES				
OT = (PW * .5) + (HW) + (RF) + (F)				
Hourly Wage Paid	Fringe Benefits Paid	Payment To Employee (PW * .5) + (HW) + (RF)	Fringe Payment + (F)	Total Payment = OT
\$ 20.00	\$ 10.00	(\$ 20.00 * .5) + (\$ 20.00) + (\$ 0.00) = \$ 30.00	+ \$ 10.00	= \$ 40.00
\$ 18.00	\$ 12.00	(\$ 20.00 * .5) + (\$ 18.00) + (\$ 0.00) = \$ 28.00	+ \$ 12.00	= \$ 40.00
\$ 22.00	\$ 8.00	(\$ 20.00 * .5) + (\$ 22.00) + (\$ 0.00) = \$ 32.00	+ \$ 8.00	= \$ 40.00
\$ 30.00	\$ 0.00	(\$ 20.00 * .5) + (\$ 30.00) + (\$ 0.00) = \$ 40.00	+ \$ 0.00	= \$ 40.00
\$ 24.00	\$ 4.00	(\$ 20.00 * .5) + (\$ 24.00) + (\$ 2.00) = \$ 36.00	+ \$ 4.00	= \$ 40.00

Regarding the last example the Contractor would be required to pay an additional \$2.00 to the Worker, which is wages in lieu of fringe for a straight time hourly rate of \$26.00 not \$24.00.

A Contractor subject to the Fair Labor Standards Act (FLSA) may be subject to additional overtime compensation requirements.

¹¹⁶ United States Department of Labor Field Operation Handbook, Section 15k

NOTICE TO BIDDERS

Minnesota Statutes require prompt payment to subcontractors:

Minn. Stat. § 471.425 PROMPT PAYMENT OF LOCAL GOVERNMENT BILLS.

Subdivision 1. **Definitions.** For the purposes of this section, the following terms have the meanings here given them.

. . . (d) "Municipality" means any home rule charter or statutory city, county, town, school district, political subdivision or agency of local government. "Municipality" means the Metropolitan Council or any board or agency created under chapter 473.

. . . Subd. 4a. **Prompt payment to subcontractors.** Each contract of a municipality must require the prime contractor to pay any subcontractor within ten days of the prime contractor's receipt of payment from the municipality for undisputed services provided by the subcontractor. The contract must require the prime contractor to pay interest of 1-1/2 percent per month or any part of a month to the subcontractor on any undisputed amount not paid on time to the subcontractor. The minimum monthly interest penalty payment for an unpaid balance of \$100 or more is \$10. For an unpaid balance of less than \$100, the prime contractor shall pay the actual penalty due to the subcontractor. A subcontractor who prevails in a civil action to collect interest penalties from a prime contractor must be awarded its costs and disbursements, including attorney's fees, incurred in bringing the action.

Minn. Stat. § 15.72 PROGRESS PAYMENTS ON PUBLIC CONTRACTS; RETAINAGE.

. . . Subd. 2. **Retainage.** . . . (c) A contractor on a public contract for a public improvement must pay all remaining retainage to its subcontractors no later than ten days after receiving payment of retainage from the public contracting agency, unless there is a dispute about the work under a subcontract. If there is a dispute about the work under a subcontract, the contractor must pay out retainage to any subcontractor whose work is not involved in the dispute, and must provide a written statement detailing the amount and reason for the withholding to the affected subcontractor.

THIS PAGE INTENTIONALLY

LEFT BLANK

MINNESOTA DEPARTMENT OF LABOR AND INDUSTRY PREVAILING WAGES FOR STATE FUNDED CONSTRUCTION PROJECTS



THIS NOTICE MUST BE POSTED ON THE JOBSITE IN A CONSPICUOUS PLACE

Construction Type: Highway and Heavy

Region Number: 08

Counties within region:

- CHIPPEWA-12
- KANDIYOHI-34
- LAC QUI PARLE-37
- LINCOLN-41
- LYON-42
- MCLEOD-46
- MEEKER-47
- MURRAY-51
- PIPESTONE-59
- REDWOOD-64
- RENVILLE-65
- YELLOW MEDICINE-87

Effective: 2024-11-18 Revised: 2025-03-24

This project is covered by Minnesota prevailing wage statutes. Wage rates listed below are the minimum hourly rates to be paid on this project.

All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at a rate of one and one half (1 1/2) times the basic hourly rate. *Note: Overtime pay after eight (8) hours on the project must be paid even if the worker does not exceed forty (40) hours in the work week.*

Violations on MnDOT highways and road projects should be reported to:

Department of Transportation
Office of Construction
Transportation Building MS650
John Ireland Blvd
St. Paul, MN 55155
(651) 366-4209

All other prevailing wage violations and questions should be sent to:

Department of Labor and Industry
Prevailing Wage Section
443 Lafayette Road N
St Paul, MN 55155
(651) 284-5091
DLI.PrevWage@state.mn.us

LABOR CODE AND CLASS	EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
LABORERS (101 - 112) (SPECIAL CRAFTS 701 - 730)				
101	LABORER, COMMON (GENERAL LABOR WORK)		36.64	24.68
			24.68	61.32
		2024-11-18		
		2025-05-01	39.01	26.01
				65.02

LABOR CODE AND CLASS		EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
102	LABORER, SKILLED (ASSISTING SKILLED CRAFT JOURNEYMAN)	2024-11-18	36.64	24.68	61.32
		2025-05-01	39.01	26.01	65.02
103	LABORER, LANDSCAPING (GARDENER, SOD LAYER AND NURSERY OPERATOR)	2024-11-18	30.04	21.53	51.57
		2025-05-01	31.66	22.78	54.44
104	FLAG PERSON	2024-11-18	36.64	24.68	61.32
		2025-05-01	39.01	26.01	65.02
105	WATCH PERSON	2024-11-18	16.25	12.94	29.19
106	BLASTER	2024-11-18	39.64	24.24	63.88
107	PIPELAYER (WATER, SEWER AND GAS)	2024-11-18	40.14	24.68	64.82
		2025-05-01	42.51	26.01	68.52
108	TUNNEL MINER	2024-11-18	38.14	24.24	62.38
109	UNDERGROUND AND OPEN DITCH LABORER (EIGHT FEET BELOW STARTING GRADE LEVEL)	2024-11-18	38.14	24.68	62.82
		2025-05-01	40.51	26.01	66.52
110	SURVEY FIELD TECHNICIAN (OPERATE TOTAL STATION, GPS RECEIVER, LEVEL, ROD OR RANGE POLES, STEEL TAPE MEASUREMENT; MARK AND DRIVE STAKES; HAND OR POWER DIGGING FOR AND IDENTIFICATION OF MARKERS OR MONUMENTS; PERFORM AND CHECK CALCULATIONS; REVIEW AND UNDERSTAND CONSTRUCTION PLANS AND LAND SURVEY MATERIALS). THIS CLASSIFICATION DOES NOT APPLY TO THE WORK PERFORMED ON A PREVAILING WAGE PROJECT BY A LAND SURVEYOR WHO IS LICENSED PURSUANT TO MINNESOTA STATUTES, SECTIONS 326.02 TO 326.15.	2024-11-18	35.00	11.50	46.50
111	TRAFFIC CONTROL PERSON (TEMPORARY SIGNAGE)	2024-11-18	21.49	14.80	36.29

LABOR CODE AND CLASS		EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
112	QUALITY CONTROL TESTER (FIELD AND COVERED OFF-SITE FACILITIES; TESTING OF AGGREGATE, ASPHALT, AND CONCRETE MATERIALS); LIMITED TO MN DOT HIGHWAY AND HEAVY CONSTRUCTION PROJECTS WHERE THE MN DOT HAS RETAINED QUALITY ASSURANCE PROFESSIONALS TO REVIEW AND INTERPRET THE RESULTS OF QUALITY CONTROL TESTERS. SERVICES PROVIDED BY THE CONTRACTOR.	2024-11-18	16.04	0.00	16.04
SPECIAL EQUIPMENT (201 - 204)					
201	ARTICULATED HAULER	2024-11-18	42.49	25.00	67.49
202	BOOM TRUCK	2024-11-18	31.16	23.45	54.61
203	LANDSCAPING EQUIPMENT, INCLUDES HYDRO SEEDER OR MULCHER, SOD ROLLER, FARM TRACTOR WITH ATTACHMENT SPECIFICALLY SEEDING, SODDING, OR PLANT, AND TWO-FRAMED FORKLIFT (EXCLUDING FRONT, POSIT-TRACK, AND SKID STEER LOADERS), NO EARTHWORK OR GRADING FOR ELEVATIONS	2024-11-18	30.04	21.53	51.57
		2025-05-01	31.66	22.78	54.44
204	OFF-ROAD TRUCK	2024-11-18	41.29	23.45	64.74
205	PAVEMENT MARKING OR MARKING REMOVAL EQUIPMENT (ONE OR TWO PERSON OPERATORS); SELF-PROPELLED TRUCK OR TRAILER MOUNTED UNITS.	2024-11-18	33.91	23.49	57.40
HIGHWAY/HEAVY POWER EQUIPMENT OPERATOR					
GROUP 2		2024-11-18	45.61	26.90	72.51
		2025-05-05	47.24	29.40	76.64
302	HELICOPTER PILOT (HIGHWAY AND HEAVY ONLY)				
303	CONCRETE PUMP (HIGHWAY AND HEAVY ONLY)				
304	ALL CRANES WITH OVER 135-FOOT BOOM, EXCLUDING JIB (HIGHWAY AND HEAVY ONLY)				

LABOR CODE AND CLASS	EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
305				
306				
307				
308				
GROUP 3	2024-11-18	45.01	26.90	71.91
	2025-05-05	46.61	29.40	76.01
309				
310				
311				
312				
313				
314				
315				
316				
317				
318				
319				
320				
321				
322				
GROUP 4	2024-11-18	44.67	26.90	71.57
	2025-05-05	46.25	29.40	75.65
323				
324				
325				
326				
327				
328				
329				
330				
331				
332				

LABOR CODE AND CLASS	EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
333	CONCRETE MIXER ON JOBSITE (HIGHWAY AND HEAVY ONLY)			
334	CONCRETE MOBIL (HIGHWAY AND HEAVY ONLY)			
335	CRUSHING PLANT (GRAVEL AND STONE) OR GRAVEL WASHING, CRUSHING AND SCREENING PLANT			
336	CURB MACHINE			
337	DIRECTIONAL BORING MACHINE			
338	DOPE MACHINE (PIPELINE)			
339	DRILL RIGS, HEAVY ROTARY OR CHURN OR CABLE DRILL (HIGHWAY AND HEAVY ONLY)			
340	DUAL TRACTOR			
341	ELEVATING GRADER			
342	FORK LIFT OR STRADDLE CARRIER (HIGHWAY AND HEAVY ONLY)			
343	FORK LIFT OR LUMBER STACKER (HIGHWAY AND HEAVY ONLY)			
344	FRONT END, SKID STEER OVER 1 TO 5 C YD			
345	GPS REMOTE OPERATING OF EQUIPMENT			
346	HOIST ENGINEER (POWER) (HIGHWAY AND HEAVY ONLY)			
347	HYDRAULIC TREE PLANTER			
348	LAUNCHER PERSON (TANKER PERSON OR PILOT LICENSE)			
349	LOCOMOTIVE (HIGHWAY AND HEAVY ONLY)			
350	MILLING, GRINDING, PLANNING, FINE GRADE, OR TRIMMER MACHINE			
351	MULTIPLE MACHINES, SUCH AS AIR COMPRESSORS, WELDING MACHINES, GENERATORS, PUMPS (HIGHWAY AND HEAVY ONLY)			
352	PAVEMENT BREAKER OR TAMPING MACHINE (POWER DRIVEN) MIGHTY MITE OR SIMILAR TYPE			
353	PICKUP SWEEPER, ONE CUBIC YARD AND OVER HOPPER CAPACITY(HIGHWAY AND HEAVY ONLY)			
354	PIPELINE WRAPPING, CLEANING OR BENDING MACHINE			
355	POWER PLANT ENGINEER, 100 KWH AND OVER (HIGHWAY AND HEAVY ONLY)			
356	POWER ACTUATED HORIZONTAL BORING MACHINE, OVER SIX INCHES			
357	PUGMILL			
358	PUMPCRETE (HIGHWAY AND HEAVY ONLY)			
359	RUBBER-TIRED FARM TRACTOR WITH BACKHOE INCLUDING ATTACHMENTS (HIGHWAY AND HEAVY ONLY)			
360	SCRAPER			
361	SELF-PROPELLED SOIL STABILIZER			
362	SLIP FORM (POWER DRIVEN) (PAVING)			
363	TIE TAMPER AND BALLAST MACHINE			
364	TRACTOR, BULLDOZER (HIGHWAY AND HEAVY ONLY)			
365	TRACTOR, WHEEL TYPE, OVER 50 H.P. WITH PTO UNRELATED TO LANDSCAPING (HIGHWAY AND HEAVY ONLY)			
366	TRENCHING MACHINE (SEWER, WATER, GAS) EXCLUDES WALK BEHIND TRENCHER (HIGHWAY AND HEAVY ONLY)			
367	TUB GRINDER, MORBARK, OR SIMILAR TYPE			
368	WELL POINT DISMANTLING OR INSTALLATION (HIGHWAY AND HEAVY ONLY)			
GROUP 5	2024-11-18	41.36	26.90	68.26

LABOR CODE AND CLASS		EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
		2025-05-05	42.77	29.40	72.17
369	AIR COMPRESSOR, 600 CFM OR OVER (HIGHWAY AND HEAVY ONLY)				
370	BITUMINOUS ROLLER (UNDER EIGHT TONS)				
371	CONCRETE SAW (MULTIPLE BLADE) (POWER OPERATED)				
372	FORM TRENCH DIGGER (POWER)				
373	FRONT END, SKID STEER UP TO 10 YD				
374	GUNITE GUNALL (HIGHWAY AND HEAVY ONLY)				
375	HYDRAULIC LOG SPLITTER				
376	LOADER (BARBER GREENE OR SIMILAR TYPE)				
377	POST HOLE DRIVING MACHINE/POST HOLE AUGER				
378	POWER ACTUATED AUGER AND BORING MACHINE				
379	POWER ACTUATED JACK				
380	PUMP (HIGHWAY AND HEAVY ONLY)				
381	SELF-PROPELLED CHIP SPREADER (FLAHERTY OR SIMILAR)				
382	SHEEP FOOT COMPACTOR WITH BLADE . 200 H.P. AND OVER				
383	SHOULDERING MACHINE (POWER) APSCO OR SIMILAR TYPE INCLUDING SELF-PROPELLED SAND AND CHIP SPREADER				
384	STUMP CHIPPER AND TREE CHIPPER				
385	TREE FARMER (MACHINE)				
GROUP 6		2024-11-18	38.06	25.00	63.06
387	CAT, CHALLENGER, OR SIMILAR TYPE OF TRACTORS, WHEN PULLING DISK OR ROLLER				
388	CONVEYOR (HIGHWAY AND HEAVY ONLY)				
389	DREDGE DECK HAND				
390	FIRE PERSON OR TANK CAR HEATER (HIGHWAY AND HEAVY ONLY)				
391	GRAVEL SCREENING PLANT (PORTABLE NOT CRUSHING OR WASHING)				
392	GREASER (TRACTOR) (HIGHWAY AND HEAVY ONLY)				
393	LEVER PERSON				
394	OILER (POWER SHOVEL, CRANE, TRUCK CRANE, DRAGLINE, CRUSHERS, AND MILLING MACHINES, OR OTHER SIMILAR HEAVY EQUIPMENT) (HIGHWAY AND HEAVY ONLY)				
395	POWER SWEEPER				
396	SHEEP FOOT ROLLER AND ROLLERS ON GRAVEL COMPACTION, INCLUDING VIBRATING ROLLERS				
397	TRACTOR, WHEEL TYPE, OVER 50 H.P., UNRELATED TO LANDSCAPING				
TRUCK DRIVERS					
GROUP 1		2024-11-18	36.00	11.50	47.50
601	MECHANIC . WELDER				
602	TRACTOR TRAILER DRIVER				
603	TRUCK DRIVER (HAULING MACHINERY INCLUDING OPERATION OF HAND AND POWER OPERATED WINCHES)				

LABOR CODE AND CLASS		EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
GROUP 2		2024-11-18	33.00	11.50	44.50
604	FOUR OR MORE AXLE UNIT, STRAIGHT BODY TRUCK				
GROUP 3		2024-11-18	31.00	11.50	42.50
605	BITUMINOUS DISTRIBUTOR DRIVER				
606	BITUMINOUS DISTRIBUTOR (ONE PERSON OPERATION)				
607	THREE AXLE UNITS				
GROUP 4		2024-11-18	23.70	6.91	30.61
608	BITUMINOUS DISTRIBUTOR SPRAY OPERATOR (REAR AND OILER)				
609	DUMP PERSON				
610	GREASER				
611	PILOT CAR DRIVER				
612	RUBBER-TIRED, SELF-PROPELLED PACKER UNDER 8 TONS				
613	TWO AXLE UNIT				
614	SLURRY OPERATOR				
615	TANK TRUCK HELPER (GAS, OIL, ROAD OIL, AND WATER)				
616	TRACTOR OPERATOR, UNDER 50 H.P.				
SPECIAL CRAFTS					
701	HEATING AND FROST INSULATORS	2024-11-18	17.50	2.79	20.29
702	BOILERMAKERS	2024-11-18	46.00	31.93	77.93
		2025-01-01	48.35	31.93	80.28
703	BRICKLAYERS	FOR RATE CALL 651-284-5091 OR EMAIL <u>DLI.PREVVAGE@STATE.MN.US</u>			
704	CARPENTERS	2024-11-18	37.65	27.08	64.73
		2025-01-01	37.65	27.08	64.73
		2025-05-01	42.85	27.08	69.93
705	CARPET LAYERS (LINOLEUM)	FOR RATE CALL 651-284-5091 OR EMAIL <u>DLI.PREVVAGE@STATE.MN.US</u>			
706	CEMENT MASONS	2024-11-18	43.00	23.72	66.72
707	ELECTRICIANS	2024-11-18	41.00	23.10	64.10

LABOR CODE AND CLASS		EFFECT DATE	BASIC RATE	FRINGE RATE	TOTAL RATE
711	GROUND PERSON	2024-11-18	16.63	6.38	23.01
712	IRONWORKERS	2024-11-18	46.00	34.11	80.11
713	LINEMAN	2024-11-18	50.86	23.06	73.92
714	MILLWRIGHT	2024-11-18	38.23	29.18	67.41
715	PAINTERS (INCLUDING HAND BRUSHED, HAND SPRAYED, AND THE TAPING OF PAVEMENT MARKINGS)	2024-11-18	33.91	23.49	57.40
716	PILEDRIIVER (INCLUDING VIBRATORY DRIVER OR EXTRACTOR FOR PILING AND SHEETING OPERATIONS)	2024-11-18	45.71	29.73	75.44
		2025-01-01	45.71	29.73	75.44
		2025-05-01	49.46	30.23	79.69
717	PIPEFITTERS , STEAMFITTERS	2024-11-18	41.97	25.92	67.89
719	PLUMBERS	2024-11-18	51.04	30.58	81.62
		2025-05-01	54.79	30.58	85.37
721	SHEET METAL WORKERS	2024-11-18	40.88	25.10	65.98
723	TERRAZZO WORKERS	FOR RATE CALL 651-284-5091 OR EMAIL DLL.PREVIEWWAGE@STATE.MN.US			
724	TILE SETTERS	FOR RATE CALL 651-284-5091 OR EMAIL DLL.PREVIEWWAGE@STATE.MN.US			
725	TILE FINISHERS	FOR RATE CALL 651-284-5091 OR EMAIL DLL.PREVIEWWAGE@STATE.MN.US			
727	WIRING SYSTEM TECHNICIAN	2024-11-18	41.42	18.16	59.58
728	WIRING SYSTEMS INSTALLER	2024-11-18	29.02	16.46	45.48
729	ASBESTOS ABATEMENT WORKER	2024-11-18	39.86	24.61	64.47
		2025-01-01	41.23	25.49	66.72
		2025-05-01	41.23	25.99	67.22

LABOR CODE AND CLASS

EFFECT DATE BASIC RATE FRINGE RATE TOTAL RATE

730

SIGN ERECTOR

FOR RATE CALL 651-284-5091 OR EMAIL
DLI.PREVWAGE@STATE.MN.US

THIS PAGE INTENTIONALLY
LEFT BLANK

Jan. 6, 2025

Notice of truck rental rate certification and effective date

The Department of Labor and Industry (DLI) commissioner has certified the minimum truck rental rates for state-funded highway projects effective Jan. 6, 2025. This certification follows the publication of the Notice of Truck Rental Rate Determination in the State Register on Dec. 16, 2024, and the informal conference held pursuant to Minnesota Rules, part 5200.1105 on Dec. 27, 2024.

According to Minnesota Rules, part 5200.1105, the purpose of the informal conference was for DLI to obtain further input regarding the determined rates prior to the certification. No written input regarding the determination was received by DLI prior to the informal conference.

The truck rental rate is determined for each equipment type by adding the average hourly cost of operating the vehicle to the certified prevailing-wage rate for the driver. The average hourly operating costs are determined by voluntary survey of truck owner operators, trucking contractors and trucking firms. Cost data used in DLI's analysis must be representative of five trucking firms of various size and five independent truck owner operators for each type of truck.

The determination of the minimum truck rental rates by region are as follows.

Three-axle units

Region	Effective date	607 driver rate	Operating cost	Truck rental rate
Region 1	Certification date	\$61.54	\$37.35	\$98.89
	Increase April 28, 2025	\$64.83	\$37.35	\$102.18
Region 2	Certification date	\$54.57	\$37.35	\$91.92
	Increase April 28, 2025	\$57.49	\$37.35	\$94.84
Region 3	Certification date	\$54.57	\$37.35	\$91.92
	Increase April 28, 2025	\$57.49	\$37.35	\$94.84

Region	Effective date	607 driver rate	Operating cost	Truck rental rate
Region 4	Certification date	\$56.93	\$37.35	\$94.28
Region 5	Certification date	\$39.50	\$37.35	\$76.85
Region 6	Certification date	\$45.00	\$37.35	\$82.35
Region 7	Certification date	\$46.65	\$37.35	\$84.00
Region 8	Certification date	\$42.50	\$37.35	\$79.85
Region 9	Certification date	\$56.36	\$37.35	\$93.71
Region 10	Certification date	\$42.50	\$37.35	\$79.85

Four or more axle units

Region	Effective date	604 driver rate	Operating cost	Truck rental rate
Region 1	Certification date	\$61.65	\$51.50	\$113.15
	Increase April 28, 2025	\$64.95	\$51.50	\$116.45
Region 2	Certification date	\$54.72	\$51.50	\$106.22
	Increase April 28, 2025	\$57.65	\$51.50	\$109.15
Region 3	Certification date	\$ 39.60	\$51.50	\$91.10
Region 4	Certification date	\$53.73	\$51.50	\$105.23
Region 5	Certification date	\$26.00	\$51.50	\$77.50
Region 6	Certification date	\$54.25	\$51.50	\$105.75

Region 7	Certification date	\$46.15	\$51.50	\$97.65
Region 8	Certification date	\$44.50	\$51.50	\$96.00
Region 9	Certification date	\$56.45	\$51.50	\$107.95
Region 10	Certification date	\$53.70	\$51.50	\$105.20

Tractor

Region	Effective date	602 driver rate	Operating cost	Tractor-only truck rental rate	Plus trailer operating cost	Tractor trailer rental rate
Region 1	Certification date	\$62.25	\$54.96	\$117.21	\$11.46	\$128.67
	Increase April 28, 2025	\$65.58	\$54.96	\$120.54	\$11.46	\$132.00
Region 2	Certification date	\$55.29	\$54.96	\$110.25	\$11.46	\$121.71
	Increase April 28, 2025	\$58.25	\$54.96	\$113.21	\$11.46	\$124.67
Region 3	Certification date	\$55.29	\$54.96	\$110.25	\$11.46	\$121.71
	Increase April 28, 2025	\$58.25	\$54.96	\$113.21	\$11.46	\$124.67
Region 4	Certification date	\$50.27	\$54.96	\$105.23	\$11.46	\$116.69
Region 5	Certification date	\$28.84	\$54.96	\$83.80	\$11.46	\$95.26
Region 6	Certification date	\$47.40	\$54.96	\$102.36	\$11.46	\$113.82
Region 7	Certification date	\$46.15	\$54.96	\$101.11	\$11.46	\$112.57
Region 8	Certification date	\$47.50	\$54.96	\$102.46	\$11.46	\$113.92

Region 9	Certification date	\$62.70	\$54.96	\$117.66	\$11.46	\$129.12
	Increase April 28, 2025	\$66.05	\$54.96	\$121.01	\$11.46	\$132.47
Region 10	Certification date	\$47.50	\$54.96	\$102.46	\$11.46	\$113.92

The current operating costs and truck rental rates may be reviewed by accessing DLI's website at <https://dli.mn.gov/business/employment-practices/prevaling-wage-minimum-truck-rental-rates>. Questions about the truck rental rates or the informal conference notice below can be answered by calling 651-284-5192.

The minimum truck rental rate for these four types of trucks in the State's 10 highway and heavy construction areas will be effective for all highway and heavy construction projects financed in whole or part with state funds advertised for bid on or after the day the notice of certification is published in the *State Register*.

Sincerely,

Nicole Blissenbach

DLI commissioner

SAP 059-647-001
SPECIAL PROVISIONS
DIVISION S
SPECIAL REQUIREMENTS

S-1 PROTECTION OF PUBLIC CONTRACTS

- S-1.1 Bidders are hereby given notice of and must abide by the provisions of M.S. 161.315 in performing contracts with Pipestone County.
- S-1.2 Out-of-state bidders are hereby given notice of the provisions of M.S. 290.9705, pertaining to withholding on payments by government entities to out-of-state Contractors.

S-2 (1203) ACCESS TO PROPOSAL PACKAGE

MnDOT 1203 is hereby deleted from the MnDOT Standard Specifications

S-3 (1206) PREPARATION AND DELIVERY OF PROPOSAL

The provisions of MnDOT 1206 are supplemented and/or modified with the following:

- S-3.1 MnDOT 1206.1 is hereby deleted from the MnDOT Standard and Supplemental Specifications.
- S-3.2 MnDOT 1206.2 is hereby deleted from the MnDOT Standard Specifications and replaced with the following:

1206.2 ALLOWABLE SUBSTITUTIONS

For all Proposals the Bidder shall use the following method:

- (1) Submit a Proposal on the Bid Schedule forms provided by the Department.
 The Bidder shall:
 - (1.1) Submit a Unit Price in numeric figures for each Pay Item for which a quantity is shown. Assume a numeric quantity of "1" for each "Lump Sum" Pay Item, except as not required in the case of alternate Pay Items,
 - (1.2) Show the extensions resulting from Unit Prices multiplied by the shown quantities in the specified column, and
 - (1.3) Add the extended Pay Item amounts to show the total amount of the Proposal.

The Bidder shall write the figures in ink or provide typed or computer printed figures. In the case of a discrepancy between a Unit Price and extension in a Proposal, the Unit Price will govern.

If a Bidder fails to provide a Unit Price for any Pay Item on the Bid Schedule, except for "Lump Sum" Pay Items, the Department will reject the Proposal.

If a Pay Item in the Proposal requires the Bidder to choose an alternate Pay Item, the Bidder shall indicate its choice in accordance with the Specifications for that Pay Item.

An authorized representative of the Bidder must sign the Proposal.

The Bidder shall deliver the Proposal and the Proposal Guaranty in a sealed envelope. The Bidder shall mark the sealed envelope with the name of the Bidder, the Project number, and the letting date. The Bidder shall deliver the sealed envelope to the Department as specified in the Advertisement for Bids as follows:

- (1) To the address specified,
- (2) In care of the official receiving the Proposals, and
- (3) By the date and time for opening Proposals.

PROPOSALS SHALL BE SUBMITTED IN THEIR ENTIRETY TO BE CONSIDERED AS AN ACCEPTABLE BID.

If the Department receives a Proposal after the date and time for opening Proposals, the Department will return the Proposal to the Bidder unopened.

1206.3 RESPONSIBLE CONTRACTOR

The Department cannot award a construction contract in excess of \$50,000 unless the Bidder is a "responsible contractor" as defined in Minnesota Statutes §16C.285, subdivision 3.

A Bidder submitting a Proposal for this Project must verify that it meets the minimum criteria specified in that statute by submitting the "Responsible Contractor Verification and Certification of Compliance" form. A company owner or officer must sign the "Responsible Contractor Verification and Certification of Compliance" form under oath verifying compliance with each of the minimum criteria. **THE COMPLETED FORMS MUST BE SUBMITTED WITH THE BID PROPOSAL.**

A bidder must obtain a verification from each subcontractor it will have a direct contractual relationship with. At the Department's request, a bidder must submit signed subcontractor verifications. A contractor or subcontractor must obtain an annual verification from each motor carrier it has a direct contractual relationship with. A motor carrier must give immediate written notice if it no longer meets the minimum responsible contractor criteria. The requirement for subcontractor verifications does not apply to:

- Design professionals licensed under Minnesota Statutes §326.06; and
- A business or person that supplies materials, equipment, or supplies to a subcontractor on the Project, including performing delivering and unloading services in connection with the supply of materials, equipment, and supplies. But, a business or person must submit a verification if it delivers mineral aggregate such as sand, gravel, or stone that will be incorporated into the Work by depositing the material substantially in place, directly or through spreaders, from the transporting vehicle.

A bidder or subcontractor who does not meet the minimum criteria specified in the statute, or who fails to verify compliance with the criteria, is not a "responsible contractor" and is ineligible to be awarded the Contract for this Project or to work on this Project. Submitting a false verification makes the bidder or subcontractor ineligible to be awarded a construction contract for this Project. Additionally, submitting a false

statement may lead to contract termination. If only one bidder submits a bid, the Department may, but is not required to, award a contract even if that bidder does not meet the minimum criteria.

S-4 (1210) REVISION OF PROPOSAL PACKAGE OR WITHDRAWAL OF PROPOSALS

The provisions of MnDOT 1210 are deleted and replaced with the following:

When submitting a Proposal in accordance with 1206.2, "Allowable Substitutions," of these Special Provisions, the Bidder may revise or withdraw its Proposal after delivery to the Department if the Department receives the Bidder's written request for withdrawal or revision before the date and time for opening Proposals.

The Department reserves the right to revise the Proposal Package at any time before the date and time for opening Proposals. The Department will issue a numbered and dated Addendum for any revision of the Proposal Package. The Department will post each Addendum as announced in an e-mail or other method of notification to each Bidder on the Department's list of Bidders.

The Department will include each Addendum with all Proposal Forms issued to the Bidder after the date of the Addendum.

If revisions made by an Addendum require change to Proposals or reconsideration by the Bidder, the Department may postpone opening Proposals. If the Department postpones opening Proposals, the Department will specify the new date and time for opening Proposals in the Addendum.

The Bidder shall acknowledge receipt of each Addendum in the proposal.

S-5 (1212) OPENING OF PROPOSALS

The provisions of MnDOT 1212 are modified with the following:

MnDOT 1212 is hereby deleted from the MnDOT Standard Specifications and replaced with the following:

1212 OPENING OF PROPOSALS

The Department will open Proposals at the time, date, and place defined in the Proposal Package and the Advertisement for Bids.

S-6 (1302) AWARD OF CONTRACT

S-6.1 The first paragraph of MnDOT 1302 is hereby changed to read as follows:

The right is reserved to send to the successful bidder the necessary Contract and bond forms and notice that the Contract has been awarded to him/her at any time within 30 calendar days after the date on which proposals are received.

S-6.2 The provisions of MnDOT 1302 are supplemented by the following:

As a condition precedent to the approval of the Contract, the bidder shall furnish proof that he/she is in compliance with Minnesota Statutes Section 363, as amended, implementing the rules and regulations of the Minnesota Department of Human Rights.

If the low bidder for SAP 059-647-001 is not also the low bidder of project SP 059-618-040, the bidder will be allowed to withdraw (without penalty) their bid within 24 hours of the bid opening by notifying the Pipestone County Engineer in writing.

S-7

(1305) REQUIREMENT OF CONTRACT BOND

The provisions of MnDOT 1305 are hereby deleted and replaced with the following:

The contracting authority shall require for all contracts less than or equal to five million dollars (\$5,000,000.00), that the aggregate liability of the payment and performance bonds shall be twice the amount of the contract. All contracts in excess of five million dollars (\$5,000,000.00) shall have an aggregate liability equal to the amount of the contract.

S-8

(1404) MAINTENANCE OF TRAFFIC, (1707) PUBLIC SAFETY, AND (2563) TRAFFIC CONTROL

The provisions of 1404 are supplemented as follows:

The Contractor shall furnish, install, maintain, and remove all traffic control devices required to provide safe movement of vehicular and/or pedestrian traffic passing through the work zone during the life of the Contract from the start of Contract operations to the final completion thereof. The Engineer will have the right to modify the requirements for traffic control as deemed necessary due to existing field conditions.

The Contractor shall be responsible for any and all necessary traffic control (ie. No parking signs) to ensure vehicles are not parked on the street for milling and overlay operations. This signing shall NOT be placed any earlier than 18 hours prior to and shall be removed immediately following each construction operation.

Traffic control devices include, but are not limited to, barricades, warning signs, trailers, flashers, cones, drums, pavement markings and flaggers as required and sufficient barricade weights to maintain barricade stability.

The Contractor shall furnish name, address, and phone number of an individual responsible for the placement and maintenance of traffic control devices. This individual shall be "on call" 24 hours per day, seven days per week during the times any traffic control devices, furnished and installed by the Contractor, are in place. The required information shall be submitted to the Engineer at the Pre-Construction Conference.

The Contractor shall, at the pre-construction conference, designate a Work Zone Safety Coordinator who shall be responsible for safety and traffic control management in the Project work zone. The Work Zone Safety Coordinator shall be either an employee of the Contractor such as a superintendent or a foreman, or an employee of a firm which has a subcontract for overall work zone safety and traffic control management for the Project. The responsibilities of the Work Zone Safety Coordinator shall include, but not be limited to:

- Coordinating all work zone traffic control operations of the Project, including those of the Contractor, subcontractors and suppliers.

- Establishing contact with local school district, government, law enforcement, and emergency response agencies affected by construction before work begins.
- Maintaining a record of all known crashes within a work zone. This record should include all available information, such as: time of day, probable cause, location, pictures, sketches, weather conditions, interferences to traffic, etc. These records shall be made available to the Engineer upon request.

The Contractor shall inspect, on a daily basis, all traffic control devices, which the Contractor has furnished and installed, and verify that the devices are placed in accordance with the Traffic Control Layouts, these Special Provisions, and/or the MN MUTCD. Any discrepancy between the placement and the required placement shall be immediately corrected. The Contractor shall protect all manholes, water valve boxes, and etc. with a minimum of a type 2 barricade with flasher.

S-8.1

Measurement and Payment:

All traffic control under this Contract shall be performed as incidental work for which no direct payment will be made

S-9

(1505) COOPERATION BY CONTRACTORS

The Contractor is hereby made aware of and shall coordinate work with the following:

- Dutch Festival in Edgerton – July 10 – 12
- NOTE this is part of the parade route

S-10

(1506) SUPERVISION BY CONTRACTOR

The provisions of MnDOT 1506 are supplemented as follows:

At the Preconstruction Conference the Contractor and Subcontractor shall designate in writing who the competent superintendent and competent individual (if different) will be for this Project. These persons can only be changed throughout the duration of the Project by submission of written authorization to the Engineer by the Contractor. The submittal of these persons shall be done before any work is performed on this Project.

The Contractor will be subject to an hourly charge for failure to comply with the requirements of MnDOT 1506. Non-Compliance charges, for each incident, will be assessed at a rate of \$100 per hour, for each hour or portion thereof, during which the Engineer determines that the Contractor has not complied. No charge will be made if the deficiency is corrected within one (1) hour of notification.

An incident of Non-Compliance will be defined as the receipt of a written work order by the Contractor with instructions to correct a deficiency.

S-11

(1507) UTILITY PROPERTY AND SERVICE

All utilities that relate to this Project are classified as "Level D", unless the Plans specifically state otherwise. This quality level was determined according to the guidelines of CI/ASCE 38-22, entitled "Standard Guidelines for Investigating and Documenting Existing Utilities."

The Contractor shall assume full responsibility for damage to any utilities, underground or otherwise, and any subsurface drainage to be left in place. **As part of this Contract, the Contractor shall be solely responsible to coordinate with the utility companies to insure timely relocation of utilities.**

S-12 (1515) CONTROL OF HAUL ROADS

The Contractor shall apply calcium chloride for dust control at all farm sites and intersections. It shall be placed at a minimum of 500 feet per location as directed by the County Engineer, at a rate of 0.25 gallons per square yard and shall be a minimum 38% solution. The Contractor is also responsible for dust control that may be needed in other areas outside of those described above for the safety of the traveling public as determined by the Engineer. When needed, the Contractor shall propose a method of dust control for these areas to be approved by the Engineer. All costs shall be included in the unit price bid for the item being hauled.

S-13 (1602) NATURAL MATERIAL SOURCES

Aggregates shall be furnished in accordance with the provisions of MnDOT 1602, 3138, 3149, 3601 and the following:

- S-13.1 Aggregates for the purpose of this Contract shall be furnished by the Contractor from sources selected by him/her. The Contractor shall make his/her own arrangements with the pit owners for gravel in any pit from which he/she elects to obtain the material and any payment that is required of the Contractor shall be made directly to the pit owners.
- S-13.2 Contractors are advised to check with local zoning regulations which apply to the taking of pit materials from new sources. The Contractor will be required to notify the Pipestone County Zoning Officer of all new pit sources to be used on the Contract before any aggregates are produced.

S-14 (1603.2) SAMPLING AND TESTING

Sampling and Testing of material shall be in accordance with the provisions of MnDOT 1603.2 Sampling and Testing and the following:

The first paragraph of MnDOT 1603.2 Sampling and Testing is hereby deleted and replaced with the following:

Sampling and testing of materials for this project will be in accordance with the State Aid for Local Transportation (SALT) "Schedule of Materials Control – Local Government Agency" (SMC-LGA). The SMC-LGA establishes the size of samples and the minimum rate of testing. The SMC-LGA references the 2020 MnDOT Standard Specifications for Construction and does not set contract requirements for the material.

If material is deemed unacceptable by these tests and additional tests are needed, Pipestone County shall charge the Contractor the cost incurred to do so plus \$100.00 per additional sample that is tested.

S-15 (1701) LAWS TO BE OBSERVED

The provisions of MnDOT 1701 are modified and/or supplemented with the following:

The Contractor is advised of the requirement to comply with the provisions of Minnesota Statutes Chapter 103G.271 pertaining to permit requirements for use of surface or underground waters. Related information may be obtained from the Department of Natural Resources.

The Labor Compliance information shall be posted in a conspicuous place on the project where all employees will be able to see it.

The County shall deduct from payments due, an amount equivalent to any/all fines, penalties, bills, etc. assessed to the County due to the Contractor's actions or inactions as it relates to non-compliance with permits and specifications on this project.

1701.7 COMPLIANCE WITH TAX LAW REQUIREMENTS

The Department cannot make final payment to the Contractor until the Contractor demonstrates that it and all its Subcontractors have complied with the Income Tax withholding requirements of Minnesota Statutes, section 290.92 and section 270C.66 for wages paid for Work performed under the Contract. To establish compliance, the Contractor must submit a "Contractor Affidavit" either online or in paper form (IC134) to the Minnesota Department of Revenue. The Contractor will receive a written certification of compliance when the Department of Revenue determines that all withholding tax returns have been filed and all withholding taxes attributable to the Work performed on the Contract have been paid. The Contractor must then provide this written certification to the Department to receive final payment.

Every Subcontractor working on the Project must submit an approved "Contractor Affidavit" from the Minnesota Department of Revenue to the Contractor before the Contractor can file its own Contractor Affidavit. The Contractor is advised to obtain the certification from each Subcontractor as soon as the Subcontractor completes Work on the Project. Experience has shown that waiting until the Project is complete to obtain the forms from all Subcontractors is likely to result in significant additional Work for the Contractor as it will be difficult or impossible to collect all forms.

The Department of Revenue, in association with the Department of Employment and Economic Development, offers a free seminar to help Contractors understand tax law requirements. The Department strongly urges the Contractor and all Subcontractors to attend the "Employment Taxes & Employer Responsibilities Seminar" or similarly offered classes. You can find a schedule and more information on the Department of Revenue website (www.revenue.state.mn.us).

Complying with this requirement is considered part of the Work under this Contract. The Department will enforce this requirement equally with all other Contract requirements. The Contractor delay in complying with this requirement will cause the Department to delay final payment and Contract Acceptance. The Department may also report non-compliance to the Department of Revenue, which may result in enforcement action by the Department of Revenue.

Contractor Affidavit requirements and Form IC134 can be found on the Department of Revenue website (www.revenue.state.mn.us).

S-16 (1803) PROGRESS SCHEDULES, (1806) DETERMINATION AND EXTENSION OF CONTRACT TIME AND, (1807) FAILURE TO COMPLETE THE WORK ON TIME

MnDOT 1803 is hereby modified as follows:

S-16.1 The second paragraph of MnDOT 1803.1A is revised to read:

The Contractor shall give the Engineer definite notice of his/her intention to start work at least 7 calendar days in advance of beginning construction and at least 48 hours in advance of beginning each subsequent major construction operation.

S-16.2 The provisions of MnDOT 1803.2 and 1803.3 (Pertaining to bar chart and critical path diagram requirements) are hereby deleted.

S-16.3 The Contract Time shall be determined in accordance with the provisions of MnDOT 1806 and the following:

Construction operations shall be started any time after Contract approval and the removal of spring load postings.

All work shall be completed no later than September 1, 2025. However, the following stipulations also apply:

- Production of aggregates may be started any time after Contract and Bond approval.

S-16.4 The Contractor must not perform work that will restrict or interfere with traffic between 2:00 P.M. on the day before and 6:00 A.M. on the day after any consecutive combination of a Saturday, Sunday and legal holiday. The Contractor may request exceptions to this requirement. Exceptions must be approved in writing by the Engineer.

S-16.5 The Contractor shall not operate any trucks on any city side streets of Edgerton (except while performing work on those streets).

S-16.6 The following shall be deleted from the second paragraph of MnDOT 1806.3:

- (3) During the inclusive period from November 15 through April 15, except as specified in 1806.1, "Determination and Extension of Contract Time, General."

S-16.7 The Contractor shall set up the Preconstruction meeting to be held at least two weeks in advance of the start of construction. **THE CONTRACTOR SHALL MAKE ALL CONTACTS CONCERNING THE MEETING**, and will hold the meeting at the Pipestone County Highway Department, Pipestone Minnesota.

S-16.8 Liquidated damages will be assessed in accordance with the provisions of MnDOT 1807, as modified herein, and the amount(s) deducted from any monies due or coming due to the Contractor in an amount(s) equal to the following:
If, at any time, the Contractor fails to, in a timely manner, properly furnish, install, maintain or remove any of the required traffic control devices as set forth in Section S-8 (MAINTENANCE OF TRAFFIC) of these Special Provisions, Pipestone County reserves the right to properly correct the deficiency. Each time Pipestone County takes such corrective action, the costs thereof, including mobilization, plus \$250.00 will be

deducted from monies due or coming due the Contractor.

The Contractor will be subject to an hourly charge for failure to maintain the traffic control devices as set forth in Section S-8 (MAINTENANCE OF TRAFFIC) of these Special Provisions. Non-compliance charges, for each incident, will be assessed at a rate of \$250.00 per hour for each hour or any portion thereof with which the Engineer determines that the Contractor has not complied.

S-16.9 The liquidated damages for failure to complete this work on time shall be in accordance with the provisions of MnDOT 1807 and the following:

Upon completion of all major items of the Contract the County will furnish the Contractor with a "Punch List". The "Punch List" shall be completed within 5 working days. The Liquidated Damages for failure to complete the "Punch List" work in the 5 days shall be a per diem deduction of \$100.00 per calendar day.

S-17 (1901) MEASUREMENT OF QUANTITIES

The following shall be added to MnDOT 1901:

S-17.1 For pay items to be paid on a tonnage basis, the Contractor shall:

- 1) Have automated weighing equipment.
- 2) **All trucks used to haul material onto a project shall have a tare weight from a certified scale that is to be given to the project inspector prior to that truck hauling any material onto the project.** Any material hauled without a tare weight from a certified scale will be subject to a 10% pay reduction of materials hauled. All loads hauled prior to receiving a tare weight shall receive a 10% deduct.
- 3) For each truckload, give the truck driver a legible copy of an automatically printed ticket that is to be given to the project inspector on the project site. The S.A.P. No., truck no., truck tare, and net mass shall be on the ticket. In lieu of printing the truck tare on the ticket, the Contractor shall furnish the Engineer with a complete listing of truck tares. All trucks used on the Project shall be listed. The Contractor shall update the list as trucks are added to the Project.
- 4) Interlock scales to eliminate load manipulation.

All material hauled onto the project **SHALL** have a printed weight ticket. Each weight ticket shall include the project number, **TRUCK NUMBER**, type of material, and the date and time of delivery (loaded). **ALL WEIGHTS SHALL BE IN ENGLISH UNITS.**

Any weight tickets not given to the inspector on site during delivery shall be supplied to Pipestone County by noon the following business day following delivery of the material. A deduct for failure to provide the weight tickets as specified shall be a per diem deduction of ten percent (10%) of the contract price for the respective delivered item.

ALLOWABLE LEGAL GROSS WEIGHT

The allowable legal gross weight is defined as the vehicle licenses gross weight plus the tolerance provided in Minnesota Statutes 168.013 or the gross vehicle weight provided by Minnesota Statutes 169.825, whichever is less. In no case will the allowable legal

gross weight exceed 80,000 pounds. No payment will be made for any material in excess of the allowable legal gross weight.

S-18 (1903) COMPENSATION FOR ALTERED QUANTITIES

The provisions of MnDOT 1903 shall not apply on this Contract.

S-19 (1906) PARTIAL PAYMENTS

The Contractor's attention is directed to DIVISION "A" NOTICE TO BIDDERS regarding prompt payment to subcontractors.

If the Contractor fails to make payment within the specified time, the applicable payment may be canceled on the next partial payment.

Partial payments will be subject to a five percent (5%) retainage for in-state contractors and an eight percent (8%) retainage for out of state contractors until all work is substantially completed and accepted. After substantial completion, retainage will be reduced to one percent (1%).

S-20 (1908) FINAL ESTIMATE AND PAYMENT – CONDITIONS AND PROCESS

Prior to the final contract payment, the Contractor shall furnish an Affidavit of Withholding and certification that payment to pit owners and other suppliers have been made or that satisfactory arrangements for payment have been made therefore.

S-21 (2051) MAINTENANCE AND RESTORATION OF HAUL ROADS

Maintenance and restoration of haul roads shall be performed in accordance with MnDOT 2051 and the following:

The Contractor shall be responsible for dust control on all haul roads.

S-21.1 All haul roads used for the delivery of materials to the project shall be approved by the County Engineer. The Contractor shall apply calcium chloride for dust control on all haul roads at all farm sites and intersections. It shall be placed at a minimum of 500 feet per location as directed by the County Engineer, at a rate of 0.25 gallons per square yard and shall be a minimum 38% solution. The Contractor is also responsible for dust control that may be needed in other areas outside of those described above for the safety of the traveling public as determined by the Engineer. The Contractor shall propose a method of dust control for these areas to be approved by the Engineer. All costs incurred for furnishing, placing, and maintaining the calcium chloride solution or other dust control method shall be included in the unit price bid for the item being hauled.

Maintenance on all haul roads shall also be done by the Contractor and will be included in the unit price bid for the item being hauled with no additional compensation therefore. The speed limit at all farm places along all gravel haul roads shall be reduced to 40 mph.

S-22 (2357) BITUMINOUS MATERIAL FOR TACK COAT

Bituminous tack coat shall be constructed in accordance with the provisions of Specification 2357, except as modified below:

S-22.1 The bituminous material for tack coat shall be CSS-1 or CSS-1H.

S-23 (2360) PLANT MIXED ASPHALT PAVEMENT

S-23.1 Mix Designation Numbers for the bituminous mixtures on this Project are as follows:

Type SP 12.5 Wearing Course Mixture (2,B) SPWEB240B

S-23.2 The compaction method for all mainline bituminous mixtures on this project shall be by the Maximum Density Method.

S-23.3 If the Contractor performs efficient compaction, to the satisfaction of the Engineer, the Engineer may eliminate coring from this project.

S-23.4 The Contractor shall mill all joints where new bituminous matches in to existing hard surfaces to a vertical face (depth shall match the depth of the proposed overlay), including along the driveways on the city streets of Edgerton. The cost of this milling shall be included in the unit price bid for 2360.509 Wearing Course Mixture (2,B) and no direct compensation will be made thereto.

S-23.5 The Plant Mixed Asphalt Pavement shall be constructed in accordance with the provisions of specification 2360 Plant Mixed Asphalt Pavement, except as modified below.

The (2360) PLANT MIXED ASPHALT PAVEMENT Specification is hereby modified with the following:

(1) See Special Provision (1901) Measurement of Quantities as it pertains to this work.

(2) Provision 2360.2G.1.a of the 2360 specifications is revised to include the following:

Certification of the plant shall be at the Contractor's cost and said cost shall be included in the unit price bid for 2360 Plant Mixed Asphalt Pavement.

(3) All Aggregates will be split according to G&B Manual 5-692.141, "Quartering Method of Sample Size Reduction". All asphalt mixtures will be split using AASHTO Standard Practice for Reducing Samples of Hot Mix Asphalt (HMA) to Testing Size (R-47) using the Mechanical Splitter Method, Type A (Quartermaster or equivalent).

(4) Delete the first paragraph of MnDOT 2360.3.D.1 and replaced with the following:

Compact the pavement to at least the minimum required maximum density values in accordance with Table 2360.3-1,

- (5) Delete MnDOT Table 2360.3-2.
- (6) Delete MnDOT 2360.3.D.1.j and replace with the following:

The Department will select at least one of the two companion cores per lot to test for verification.
- (7) Delete MnDOT 2360.3.D.1.n Longitudinal Joint Density.
- (8) Delete MnDOT 2360.3.D.1.p Shoulders.
- (9) Delete MnDOT Table 2360.5-6 Incentive and Disincentive Schedule for Longitudinal Joint Density, 4 percent Design Void.
- (10) Delete MnDOT Table 2360.5-7 Incentive and Disincentive Schedule for Longitudinal Joint Density, 3 percent Design Void.

S-24 (2504) ADJUST VALVE BOX - WATER

Adjustment of Valve Boxes shall be in accordance with the provisions of 2504 and the following:

- S-24.1 This work shall consist of adjusting water gate valve boxes to the final surface without changing the elevation of the gate valve. All water valve boxes shall be adjusted prior to the placement of the roadway surface. The top of the valve box shall be adjusted 1/4" to 1/2" below the finished roadway surface as measured from a 10 foot straight edge laid longitudinally along the roadway. In the event this requirement is found to be out of compliance upon final inspection, the Contractor shall re-adjust the valve box by means of cutting around the valve box in a diamond shape with a straight, clean saw cut and raising or lowering the valve box as needed. This re-adjustment, if needed, will be at the sole expense of the Contractor. When the adjustment cannot be made by using the existing materials in place, the Contractor shall furnish at his/her expense, such materials as may be necessary to accomplish the required adjustment. . (See also special provision 1803 Prosecution of Work, 1806 Determination and Extension of Contract Time, 1807 Failure to Complete the Work on Time as it pertains to this work).
- S-24.2 Adjusting the valve boxes will be paid for as one unit under Item No. 2504.602 (Adjust Valve Box – Water) at the Contract unit price per each, which price shall be compensation in full for all costs incidental thereto including, but not limited to, furnishing extensions and replacing any materials damaged by the Contractor's operations.
- S-24.3 The Contractor shall protect all valve boxes with a minimum of a type II barricade with flasher until the final paving operation is completed.

S-25 (2506) ADJUST FRAME AND RING CASTING

Adjustment of frame and ring castings shall be in accordance with the provisions of 2506 and the following:

- S-25.1 Adjusting frame and ring castings on existing manholes will be measured by the number of castings actually adjusted and will be paid for under Item No. 2506.502 at the contract

unit price for each Adjust Frame and Ring Casting, which price shall be full compensation for all costs included thereto.

- S-25.2 The Contractor shall recompact all disturbed soils and materials around the adjusted frame and casting in maximum lifts of 3" to achieve densities equal to adjacent materials.
- S-25.3 All frame and ring castings shall be adjusted prior to the placement of the bituminous wear course. If any new frame and ring castings are required on existing manholes, they will be furnished by Pipestone County and installed and adjusted by the Contractor. The Contractor, at his/her expense, may use approved adjusting rings if they allow for the 1/4" to 1/2" tolerance. The top of the castings shall be adjusted 1/4" to 1/2" below, the finished bituminous surface as measured from a 10 foot straight edge laid longitudinally along the roadway. In the event this requirement is found to be out of compliance upon final inspection, the Contractor shall re-adjust the frame and casting by means of cutting around the manhole casting in a diamond shape with a straight, clean saw cut and raising or lowering the manhole casting as needed. This re-adjustment, if needed, will be at the sole expense of the Contractor. (See also special provision 1803 Prosecution Of Work, 1806 Determination And Extension Of Contract Time, and 1807 Failure To Complete The Work On Time as it pertains to this work).
- S-25.4 The Contractor shall protect all manholes with a minimum of a type II barricade with flasher until the final paving operation is completed.

TEST PAGE 01 10/10/10
10/10/10

2024

SALT Schedule of Materials Control



Contents

Introduction	3
Material Acceptance Summary Instructions	4
Material Acceptance Summary	5
Bituminous Quality Management	6-7
Bituminous Specialty Items	8
Cold Inplace Recycling (CIR), Stabilized Full Depth Reclamation (SFDR)	9
Grading and Base Construction Items	10-13
Certified Ready-Mix Concrete	14-16
Concrete Plant and Field Materials	17
Concrete Pavement – Agency	18-19
Concrete Pavement – Producer/Contractor	20-21
Concrete Wearing Course for Bridges	22
Concrete Pavement Repair – CPR for 3U18	23
Dowel Bar Retrofit – (DBR)	24
Landscaping and Erosion Control Items	25
Chemical Items	26
Metals	27-28
Geosynthetics, Pipe, Tile, Precast/ Prestressed Concrete	29
Electrical and Signal Equipment Items	30-31
Brick, Stone and Masonry Units	32
Miscellaneous Materials	33
Approved/Qualified Products & Resources	34
Contacts	35-37
Sample Sizes	38

Introduction

This Schedule of Materials Control (SMC) outlines the MINIMUM testing requirements for State Aid Funded and/or Federal Aid Projects **OFF** the National Highway and Trunk Highway System. Optional to this SMC is the MnDOT Materials Control Schedule. Usage of either schedule must be defined in the project proposal.

The SMC – LGA serves as a guide for material testing with allowable acceptance “as directed by the Engineer” detailed in Specification 1501.1(1) – Authority of the Engineer. These testing rates are a minimum and additional test may be taken at the Engineer’s discretion. A minimal testing rate does not always ensure a quality product; field observations and attention to detail is crucial. Materials not listed on an approved products list may be sampled and tested as directed by the Engineer. Materials listed on a Qualified Products list may be accepted or tested at the discretion of the Engineer.

Federal Aid projects require Independent Assurance Inspection. Contact the MnDOT District IA Inspector when the job starts to provide the proper servicing of your project.

*****Agencies using MnDOT Metro Inspection Services will be sampled at the current MnDOT Schedule of Materials Control rates and will be billed accordingly.**

*****Contact the MnDOT District IA Inspector to provide servicing for your federal aid project.**

Definitions

Schedule of Materials Control

Schedule of Materials Control (SMC) are inserted into project proposals to direct how materials are to be sampled and tested. The SMC is updated yearly. Each SMC is project specific. Therefore, one needs to refer to their specific proposal.

Approved/ Qualified Products List

Products are “approved” when they have been found to routinely meet all applicable standards and specifications. The product is placed on the list based upon established successful manufacturer’s quality control and warranties, but the listing may expire or require periodic renewal to verify the product has not changed over time. The approval process for the individual product should specify any expiration requirement. Testing may still be on at the Engineers discretion.

Certified Sources

Certified Sources must comply with each individual product’s defined “certification procedure”. Acceptance of products from certified sources follows the same sampling and testing as “approved/ qualified” products.

Quality control (QC): The activities performed by the **Contractor/Producer** that have to do with making sure the quality of a product or process meets the relevant contract requirements. All testing shall be performed by a certified tester.

Quality assurance (QA): The activities performed by the **Department/Agency** that have to do with making sure the quality of a product or process meets the relevant contract requirements. All testing shall be performed by a certified tester.

Verification Testing: Sampling and testing performed as called out herein to validate the quality of the product(s). **Part of QA.**

Rev. February 2019

SP/SAP(s)

[illegible]

Approved by Project Engineer: _____ Date: _____
Print Name: _____

Material Acceptance Summary



STATE AID FOR LOCAL TRANSPORTATION MATERIAL ACCEPTANCE SUMMARY

Rev. February 2019

SP/SAP(s)

[illegible]

* This Item is hereby accepted by the Engineer as materially compliant for use on this project per the terms of specification 1501.1, subset (1).

Approved by Project Engineer: _____ Date: _____
Print Name: _____ Phone: _____

For an electronic Word version of this form, please visit the State Aid Construction webpage at:
https://edocs-public.dot.state.mn.us/edocs_public/DMResultSet/download?docId=19623193

Bituminous Quality Management

The Contractor shall provide and maintain a quality control program as detailed in Specification 2360.2.G. The Engineer shall review the quality control program for compliance. This shall be provided at the precon.

	Type of Test	Spec Section (1)	Contractor / Producer – QC Testing Rates	Agency – QA Testing Rates
Start-Up Testing Rates for the 1 st 2000 tons (2)	Bulk Specific Gravity	2360.2.G.7.b	1 test per 500 tons 55 lb. sample 3 full cylinder molds (7)	(3) (10) 1 Verification Mixture Sample test per day, all Verification samples are from a split (QC/QA) sample.
	Maximum Specific Gravity	2360.2.G.7.c		
	Air Voids (calculated)	2360.2.G.7.d		
	Asphalt Content	2360.2.G.7.a		
	Adj. Asphalt Film Thickness (AFT)	2360.2.E.7.e		
	Gradation	2360.2.G.7.f		
	Fines to Effective Asphalt Ratio (calculated)	2360.2.G.7.a/f	1 test per 1000 tons (4) (5) (6) (7)	
	Coarse Aggregate Angularity (CAA)	2360.2.G.7.g		
	Fine Aggregate Angularity (FAA)	2360.2.G.7.h		
	Added AC/Total AC Ratio (calculated)	2360.2.G.7.a		
Production Testing Rates	Bulk Specific Gravity	2360.2.G.7.b	1 test per 1000 tons 55 lb. sample 3 full cylinder molds (7)	(3) (10) Verification Mixture Sample test per day/ mix type, submit companion to the QC – CAA & FAA test results.
	Maximum Specific Gravity	2360.2.G.7.c		
	Air Voids (calculated)	2360.2.G.7.d		
	Asphalt Content	2360.2.G.7.a		
	Adj. Asphalt Film Thickness (AFT)	2360.2.E.7.e		
	Gradation (minimum of 1 per day)	2360.2.G.7.f		
	Added AC/Total AC Ratio (calculated)	2360.2.G.7.a		
	Coarse Aggregate Angularity (CAA)	2360.2.G.7.g		
	Fine Aggregate Angularity (FAA)	2360.2.G.7.h	(4) (5) (7)	
			(4) (6) (7)	
	TSR	2360.2.G.7.i	When directed by the Engineer	
	Aggregate Specific Gravity	2360.2.G.7.j		
	Mixture Moisture Content	2360.2.G.7.k	As directed by the Engineer	
	Asphalt Binder (QA ONLY)	2360	(8) 1 qt. steel container for asphalt binder	
	Asphalt Emulsion (QA ONLY)	2357	(9) ½ gal plastic container for asphalt emulsion. (Tack)	
	Compaction / Density Requirements	2360.3.D	Review special provisions	
	Small Quantity Requirements	< 500 tons per project may be accepted by the Engineer without testing.		

NOTES: Testing rates are minimum rates; additional testing is encouraged to ensure a quality product.

- (1) Review Special Provisions & 2360.2G Mixture Quality Management.
- (2) The testing rates apply only to mixtures that have not been tested on previous projects in the current year.
- (3) The Agency shall witness a minimum of 1 (one) complete QC mixture sampling, splitting and test per day. The Agency shall take possession of all split QA samples immediately. The Agency shall randomly submit one QA split sample to the District Lab for Verification testing and inform with contractor the following day of test number. Additional verification samples can be taken at any time or location. When additional verification samples are taken, the contractor must test the Verification Companion split of this sample and include the results in the QC program.
- (4) The Contractor will retain the extracted gradation samples in containers with field identification numbers for a period of 10 calendar days. The Engineer will identify which extracted gradation sample is the Verification Companion Sample and whether it is to be tested for coarse and fine aggregate angularity.

- (5) **At start-up or new Mix Design:** 2 tests/ day for a minimum of 2 days, then 1/day if CAA is met. If CAA > 8% of requirement, 1 sample/ day but test 1/ week. No testing required for Class A and B Aggregates.
- (6) **At start-up or new Mix Design:** 2 tests per day for a minimum of 2 days, then 1/day if FAA is met. If FAA > 5% of requirement, 1 sample/ day but test 1/week.
- (7) Random number generation and determination of random sample location shall be consistent with Section 5 of ASTM D3665. The Engineer may approve alternate methods of random number generation.
- (8) **During Asphalt Mixture Production (Field Verification):** Shall be from a certified supplier. Obtain asphalt binder samples from a sampling valve located between the pump and the drum. Contractor personnel shall obtain samples, under the observation of a department representative, by random selection from shipments of material at the project site. The samples shall be taken from the first load and subsequently 1 per 1000 tons of liquid asphalt binder for each supplier and grade of asphalt binder per contract. For contracts with less than approximately 25 tons (one truck transport) of asphalt binder, sampling may be waived. A minimum of 1 gallon of binder must be drawn and wasted from the sampling valve before the actual sample is drawn. Sample shall be sent in for verification testing.
- (9) **During Mixture Production (Field Verification):** Shall be from a certified supplier. The Contractor shall sample first shipment, then submit 1 per 50,000 gallons. Sample emulsified asphalt in clean ½ gallon plastic container with wide screw top and send to MnDOT Chemical Lab within 7 days of sampling. Sample all emulsified asphalt from the distributor. Sample shall be sent in for verification testing. No Samples required unless directed by the Engineer.
- (10) Conduct random belt samples and test for aggregate quality as directed by the Engineer.

Bituminous Specialty Items

Type of Test	Spec	Contractor/Producer – QC Testing Rates	Agency- QA Testing Rates
Gradation	2363	1 per 1,000 Ton with a minimum 1 per day.	1 per day. 35 lbs.
PASSRC & PASB	3139.3		
Micro-Surfacing	2354 3139.5	Stockpile: 1/1,500 Tons (min 1/day) Machine Hopper: 1/500 Ton (min 1/day)	Machine Hopper: 1/day, 30 lbs.
Seal Coat, Underseal & Otta Seal	2356 3137.2B	Stockpile: 1/1,500 Tons (min 1/day) Chip Spreader Hopper: 1/day	1/day from Hopper. 30 lbs.
% Crushing – CAA	2363	1 per 1,000 Ton with a minimum 1 per day.	1 per day from gradation test. 35 lbs.
PASSRC & PASB	3139.3		
Moisture / Aggregate	2354	Machine Hopper: 1/500 Tons (min 3/day)	1/day 2lbs
Micro-Surfacing	3139.5		
Sand Equivalence	2354	1/day	Test at Engineer discretion, 25 lbs.
Micro-Surfacing			
Flakiness Index	2356	Sample taken from first load on first day, submit to Agency: 30 lbs.	Agency will test at their discretion, see Lab Manual 1223
Bituminous Seal Coat & Bituminous Underseal			
Bituminous Mixture	2353	1/500 Tons, min 1/day. %AC, Gradation, Max SpG, Adj.AFT	1/day, 20 lbs. 1 cylinder from truck box.
UTBWC	3151.2G		
PASSRC & PASB	3151 2363	Asphalt spot check: min 1/day	-
Stone Matrix Asphalt – SMA Lab Manual 1203, 1204, 1205, 1211, 1214, 1806, 1807, 1808, 1813, 1853, 1854, 1855, AI SP-2 AASHTO T305	2365	Tests, %AC, gradation, Gmm, Gmb, Voids, VMA, CAA, Draindown, VCA, fines/effective asphalt. Rate, (1/1000 tons, min.1/day) Agg SpG, mix moisture, TSR to be tested as directed by Engineer. Submit companion 1 per day to agency: 3 full 6" by 12" cylinders	Tests: %AC, Gradation, Gmm, Gmb, Voids, VMA, CAA, VCA, fines/effective asphalt. Agency is not required to do drain down. Copy MDR to Project Engineer and Grading & Base Engineer.
Asphalt Binder Tests		Asphalt Emulsion List	Asphalt Binder List
UTBWC	2353 3151	Asphalt Binder: Sample first load, then 1/250,000 gallons. Sample size of 1 quart metal container. Emulsified Asphalt: Sample first load, then 1/50,000 gallons. Sample size of ½ gallon wide screw top plastic container.	
Micro-Surfacing	2354		
Seal Coat, Underseal & Otta Seal	2356		
Tack Coat	2357		
PASSRC & PASB	3151		
Asphalt Binder Rate	2354	Verify Application Rate 3/day	Verify Application Rate 1/day
Micro-Surfacing			
Fog Seal	2355	Verify Application Rate 1/day	Verify Application Rate 1/day
Seal Coat, Underseal & Otta Seal	2356		
Bit Tack Coat	2357		

Specification 2215 – Cold Inplace Recycling (CIR), Stabilized Full Depth Reclamation (SFDR) and Cold Central Plant Recycling Bituminous (CCPR)

Test Type	Contractor/Producer QC Testing Rates	Agency QA Testing Rates	<u>Grading & Base Manual/Form</u>
Gradation SFDR (Simple) Pre-ground un-stabilized material	1 per mile – report sieves 2" & 3"	Run gradation at the discretion of the Engineer	.215 / 101 report sieve 2" & 3"
Gradation (Entire) (Material to be stabilized)	One per day, give split sample to the Engineer	Run gradation at the discretion of the Engineer	.215 / 101 report sieve 2", 1.5", 1.25", 1", ¾", 3/8", #4, #10, #30.
Gradation (Simple) (Material to be stabilized)	1 per mile for SFDR & CIR. 1 per 2,000 ton for CCPR.	Run gradation at the discretion of the Engineer	.215 & .293 / 101 report sieve 2" & 1.5" for SFDR, 1.5" and 1.25" for CIR
CIR & SFDR Depth Check – Unstabilized and Stabilized	None	1 per day	.284 / 401
SFDR & CCPR Moisture – before injecting with bituminous.	1 per mile of anticipated daily production and after rain. 1 per mile for SFDR after mechanical drying.	Run moisture at the discretion of the Engineer	.245 Speedy tester not allowed.
Penetration Index (DCP) – SFDR only Unstabilized.	2 per mile	1 per mile	.255 / 205
Calibrate: mineral stabilizing agent application rate.	Once using design rate per vane feeder.	Observe contractor calibration	.286 or .287
Moisture: before injecting liquid bituminous material	1 per mile of daily anticipated SFDR & one after rain or mechanical drying out (disking, etc.).	none	.281 / 105
Yield: Mineral Stabilizing Agent and/or Liquid Bituminous Material	1 per transport load each type	1 per day each type	.286 & .287 / 402 & 403
Compaction: Nuclear density for SFDR stabilized and CIR	10 per lane mile, (see note below).	Observe the Contractor.	.282
Control Strip: SFDR Stabilized and CIR	Minimum of once per project	Observe the Contractor.	
Bituminous Material Samples		. 1 per 50,000 gallons; sample first load	1 quart each sample
Mineral Stabilizing Agent Samples	None	1 sample	none
Foaming asphalt checks expansion ratio & half life	1 per load	Observe the Contractor.	.285
Moisture (stabilized) – before placement of next layer during curing.	2 per day until moisture stabilizes & placement of HMA.	None	Grading & Base Manual

Note: The Engineer may require a Contractor to perform additional nuclear density tests in areas that the Engineer believes are failing density requirements.

Grading and Base Construction Items (1 of 4)

		Material Type	Spec.	Contractor / Producer QC Testing Rates	Minimum Required Agency QA Testing Rates	Verification Testing Sample
Gradation Testing (2) (3)		Aggregate Surfacing	3138	1 / 1,000 CY (CV) stockpile gradation only required for material on hand.	> 250 yd ³ (CV) or 500 Tons and < 2000 yd ³ (CV) or 4000 tons. Material is a minimum of one lot (5). Test two random samples from each lot and average. > 2000 yd ³ (CV) or 4000 Tons. Divide into lots with lot size (5) no greater than 2000 yd ³ (CV) or 4000 Tons. Test two random samples from each lot and average.	1/source 30 lb.
		Aggregate Base	3138			
		Shoulder Base Aggregate	3138			
		Drainable Aggregate Base (OGAB & DSB)	3136			
		Granular and Select Granular Material (borrow/embankment)	3149.2B	1/10,000 CY (CV) only required for material on hand.	1/40,000 yd ³ (CV)	1/source 30 lb.
		Stabilizing Aggregate	3149.2C			
		Reclamation FDR	3135.2B	None	Test at Engineer's discretion. Inspect for oversize chunks (+3"), after the motor grader has overturned the material	None
		Granular Filter	3601.2B	1/source – before delivery on the project. Only required for materials on hand. Spec 1906.2	1/ source	1/source 30 lb.
		Backfill Materials	3149.2D			
		Granular Bedding	3149.2F			
		Aggregate Bedding	3149.2G			
		Coarse Filter Agg.	3149.2H			
		Filter Aggregate	3149.2J			
		Sand Cover	3149.2K			
Proctor	Specified Density *	Non-Granular Material Used to determine optimum moisture & maximum density.	2106 3149	None	1 per major soil, subgrade prep specified density requires 100% of proctor density.	1 sample 25 lb.
Sand Cone, Nuclear Density or LWD		Non-Granular Material For non-granular material, i.e., material that does not meet 3149.2B.1		<p>AGENCY TESTING: Roadway Embankment: One test per 4,000 yd³ (CV) <u>or</u> <u>if</u> test rolled, One test per 10,000 yd³ (CV)</p> <p>Transverse culverts & abutments: 1 test per every 2 feet of fill.</p> <p>Structures and Longitudinal Trenches: One test per 300 feet of each structure per 2 feet per fill.</p> <p>Sidewalks and Trails: 1 per 500 feet.</p> <p>Subgrade Preparation: One per 25 road stations.</p>		

Grading and Base Construction Items (2 of 4)

Material Type		Spec.	Contractor / Producer QC Testing Rates	Minimum Required Agency QA Testing Rates	Verification Testing Sample
Penetration Index Method (DCP) or LWD *	Aggregate Base	3138 2211.3C	None	1 DCP tests per 500 yd ³ (CV) or 1 per 1000 Tons. If test rolled, 1 test / 1,500 yd ³ (CV) or 3000 Tons.	None
	Shoulder Base Aggregate				
	Reclamation FDR	3135.2B 2215.2C		1 DCP test per 3,000 yd ² . If test rolled, 1 test / 10,000 yd ²	
	Walks & Trails	2521		1 per 500 feet of Sidewalk or Trail	
	Granular Materials Subgrade Preparation (for materials meeting 3149.2B1)	3149.2B	AGENCY TESTING: Roadway Embankment: One test per 2,000 yd ³ (CV) <u>or if test rolled, One test per 6,000 yd³ (CV)</u> Transverse culverts & abutments: 1 test per every 2 feet of fill. Structures and Longitudinal Trenches: One test per 300 feet of each structure per 2 feet per fill. Sidewalks and Trails: 1 per 500 feet. Subgrade Preparation: One per 25 road stations.		
Moisture Content Test During All Compaction Methods (4)	Aggregate Base, Shoulder, Surfacing & Walks	3138	None	For 2118, 2211,2221, and 2521: 1 / 1,000 yd ³ up to 10 Maximum For 2451: 1 per structure, for multiple adjacent structures, may test once, use judgement For Quality Compaction: Test as directed by Engineer.	None
	Drainable Aggregate Base (OGAB & DSB)				
	Reclamation FDR	3135.2B	None	1 / 20,000 yd ²	
	All Embankment Materials	2106 3149	None	1/10,000 yd ³ up to 10 Maximum For Quality Compaction: Test as directed by Engineer.	
	Subgrade Preparation	2106 3149		1 per 25 road stations For Quality Compaction: Test as directed by Engineer.	
Percent Crushing	Particle Count (1)	1906.2	1 required for Material on hand	1/source unless directed by Engineer, (required for 3138.2B & C, 3149.2C & G1, 3136.2B).	1 / source
Quality	Aggregate Quality Tests	3138 3149 3601	1 required for material on hand, Spec 1906.2	1/ source unless directed by Engineer	1 / source 30lb
Depth Check	Reclamation FDR	3135.2B	1/Mile.	1 per day unless directed by Engineer	

Material Type		Spec.	Contractor / Producer QC Testing Rates	Minimum Required Agency QA Testing Rates	Verification Testing Sample
Test Rolling	Test Rolling (as directed in the special provisions)	2111	As directed by the Engineer the contractor will perform test rolling at the top of all <ul style="list-style-type: none"> • Subgrade • Base layers (2211) • Non-Stabilized FDR (2215) • Granular layers not meeting the requirements of 3149.2B2 (2106) • Minimum 12' width and 300' length. Agency to observe test rolling. 		

Verification Testing Samples are companion split samples to the QA sample:

- Companion gradation, proctor, QA crushing, aggregate quality samples not required 1,000 tons or less.
- Include the laboratory companion with the first field sample.
- Include the field sample results with the laboratory sample.
- Laboratories with AMRL Accreditation are not required to submit laboratory companion samples.
- Carbonate aggregate materials require 50 lb. samples for the laboratory testing.

NOTES:

(1) Percent crushing test is not required when the material is crushed from a quarry or contains 25% or greater recycled materials.

(2) Submit a laboratory companion to the first Acceptance Gradation sample for a bituminous extraction, see 3138.2C. Full Depth Reclamation samples are not required.

(3) The Certification of Aggregates and Granular Materials procedure and documentation of testing locations is at the discretion of the Engineer.

(4) For quality compaction per spec 2106.3G.2, test at Engineer's discretion.

(5) Lot sizes may be adjusted by the Engineer. This may be good practice if parts of the project are taking place in separate areas or at separate times, such as many turn lane or excavation areas or separate project stages.

* Review the Special Provisions. The Grading and Base Manual allows the nuclear density gauge, see pages 60 and 65.

NOTES:

Conversions: 1 ton = 0.55 yd³ (CV), 1 ton = 0.7 yd³ (LV), 1 yd³ (CV) = 1.8 tons.

Contact the MnDOT District IA Inspector to provide servicing of your Federal Aid Project.

Less than 500 tons (250 CY) may be accepted by the Engineer without testing.

Grading and Base Construction Items (4 of 4)

Guidelines for Required Crushing & Aggregate Quality Tests

	3149 Granular Materials	3138 Aggregate for Surface and Base	3136 Drainable Bases
Crushing	Yes, for Stabilizing Aggregate, Fine Aggregate Bedding and Medium Filter Aggregate. Test waived if material contains recycled at twice the minimum crushing requirement. Not required for quarried sources.	Yes, for Class 5, 5Q & 6. Test waived if material contains recycled at twice the minimum crushing requirement. Not required for quarried sources. Class 2 must contain 100% crushed quarry rock.	Yes. Not required for quarried sources.
Bitumen Content	At the discretion of the Engineer	At the discretion of the Engineer	Not applicable
LAR	Not applicable	Yes, if source is carbonate quarry and does not contain bitumen.	Yes
Insoluble Residue	Yes, if source is carbonate quarry and does not contain bitumen.	Yes, if source is carbonate quarry and does not contain bitumen.	Yes, if source is carbonate quarry.
Litho Exam & Shale Float Test	Yes, for Medium Filter Aggregate	Yes, for Class 3, 4, 5, 5Q & 6, when not from quarried rock, and does not contain bitumen.	Yes, when not from a quarried source.

Testing procedures in the Grading & Base Manual.

Forms and worksheets at the Grading & Base website.

Gradation worksheets at the SALT Construction website.

****MAKE SURE TO FILL OUT THE REQUIRED PRELIMINARY AND FINAL GRADING AND BASE REPORTS AND SUBMIT TO PROJECT ENGINEER.****

http://www.dot.state.mn.us/materials/gradingandbasedocs/Forms/form001_08_043019.xlsx

Certified Ready-Mix Concrete (1 of 3)

The Prime Contractor is responsible to assure that all ready-mix concrete used is produced by an annually Certified Ready-Mix plant as detailed in Specification 2461.3F.

Material Spec.	Test Type (Concrete Manual)	Contractor / Producer QC Testing Rates				Form
bridge 2406.2 2411.2 2461.2 2461.3 general 2301** 2452.2 2461.2 2461.3 2506.2 2511.2 2514.2 2520.2 2521.2 2531.2 2533.2 2545.2 2554.2 2557.2 2564.2 2565.2	Gradation (5-694.145) (5-694.148) 3126, 3131, 3137	For all JMF's & Bridge Deck Mix Designs Daily Concrete Quantity: 1 per fraction per source per day between 20 – 400 yd³. If over 400 yd³ per day, take a second gradation after the DAILY total exceeds 400 yd³. Bridge Deck Concrete must have passing gradations prior to mixing.				Concrete Agg. Work sheet, Agg. Grad. Control Charts, R-M Plant QC workbook. R-M Plant QA Workbook
		For all other mix designs, Weekly Concrete Quantity: 1 per fraction per source per week between 20 – 400 yd³. If over 400 yd³ produced per week, take a second gradation after the WEEKLY total exceeds 400yd³.				
		Department Plant Monitor Testing Rates: Verification only Verification Sample: When weekly concrete quantity is ≥ 20 yd³: 1 per fraction per source per week, split and tested by both Agency and Contractor				
	Moisture Content (5-694.142)	QC rates:	1 every 4 hours When Daily Concrete Quantity ≥ 20 yd³	QA rates:	None	
	Test Type	Agency QA Testing Rates (1)				
	Aggregate Quality (5-694.146)	Minimum of 1 per each fraction - use of MnDOT test results for the same 30-day time period is acceptable. <u>For all bridge deck concrete poured during the month</u> : Test monthly quality to 3137.2D2 for each coarse aggregate fraction. Designate 3137.2D2 on the sample card. Gradation results will be included with the monthly quality tests.				
	Coarse Aggregate (% Passing 200) (5-694.146)					
	Minimum Aggregate Sample Size All Aggregate Gradation and Quality samples require companions, double sample size					
	Aggregate Size	Gradation	Quality	Moisture	% -200 Course.Agg.	
	3/4" Plus, #4	30 lb.	50 lb.	2000 g	5000 g	
	3/4" Minus, #67	10 lb.	30 lb.	2000 g	2500 g	
	#7, CA-70	6 lb.	20 lb.	2000 g	2500 g	
	CIA to meet #67	6 lb.	20 lb.	500 g	500 g	
	CIA to meet JMF, FIA, CS, FS	500 g	20 lb.	500 g	500 g	
	CA-80, #89	1.1 lb. (500 g)	20 lb.	500 g	500 g	
Fine Aggregate	1.1 lb. (500 g)	20 lb.	500 g	-		

Certified Ready-Mix Concrete (2 of 3)

Spec.		Test Type	Agency QA Testing Rates (1)	Form
bridge 2406.2 2411.2 2461.2 2461.3	Concrete Field-Testing Rates	<u>Sampling Locations for Air, Slump (when required), Temperature and Cylinder Testing</u> First load each day per mix - Take sample after discharging approximately 1/4 yd ³ , stop further discharge until both slump and air content test are completed. The first load of concrete <u>must have passing air content and slump prior to placement</u> . Cast strength specimens from the same load as the air content and slump test. Test whenever adjustments are made to the mix. Take all tests at the point of placement. Subsequent tests - Sample from the middle portion of the load.		
		Air Content - Type 3 Concrete (5-694.541)	1 test per 100 yd ³ . Test first load each day per mix. Test when adjustments are made to the mix.	
		Slump (5-694.531)	Test first load each day per mix, then as necessary to verify passing slump. For Bridge Concrete: 1 test per 100 yd ³ . No testing required for slip form placement.	
		Air and Concrete Temperature (5-694.550)	Record temperature each time air content, slump or compressive strength specimen is performed/fabricated.	
general 2301** 2452.2 2461.2 2461.3 2506.2 2511.2 2514.2 2520.2 2521.2 2531.2 2533.2 2545.2 2554.2 2557.2 2564.2 2565.2		Compressive Strength (5-694.511) Standard cylinder size is 4 x 8, use 6 x 12 with aggregate greater than 1 1/4". Review 2461.3G.5 Test Methods and Specimens.	<u>General Concrete Grades F, G, M, P, and R:</u> 1 set of 3 cylinders per 300 yd ³ per mix per day.	2409 Concrete Cylinder ID Card
			<u>Bridge Concrete Grades B, S, and Y:</u> 1 set of 3 cylinders per 100 yd ³ , then 1 set of 3 cylinders per 300 yd ³ per mix per day	
			Agency will break 1 set of 3 cylinders at 28 days. Agency will cast up to 3 control cylinders, any additional control cylinders are the responsibility of the Contractor.	
			Cellular Concrete: 1 set of 4 cylinders (28 days) per day, fill in 2 equal lifts, <u>do not rod</u> , lightly tap the sides, cover and move to area with no vibration. Do not disturb for 24 hours.	

NOTES:

(1) Review the requirements of 2461.3F Certified Ready-Mix Concrete, 2461.3G Concrete Placement and 5-694.010 Inspector's Checklist in the Concrete Manual.

*Small Quantity Requirements are for less than 20 yd³ per day, Plant Monitoring is not required but Concrete Field Testing is required.

**Concrete Pavement: Use Certified Ready-Mix Concrete testing rates when: a) The entire concrete paving project is less than 3,500 cu. yd. b) When a secondary plant is used to provide minor work.

Certified Ready-Mix Concrete (3 of 3)

The Prime Contractor is responsible to assure that all ready-mix concrete used is produced by an annually Certified Ready-Mix plant as detailed in Specification 2461.3F.

Guidelines

- The testing rates shown in this Schedule of Materials Control are minimums. Take as many tests as necessary to ensure quality concrete. Should circumstances arise on a project which makes the testing rate impractical, contact the Concrete Engineering Unit.
- All samples shall be taken in a random manner using an appropriate number generator.
- The first load of concrete for any pour must have passing air content and slump results, prior to placing.
- If batching or field adjustments are made, test the adjusted load for air content and if suspect, slump, before it gets into the work. The Engineer will determine if additional testing is required after each water adjustment made during slip form placement. Continue to test for air content and slump, if suspect, when test results are inconsistent or marginal.
- If any field test fails, reject the concrete or if the Producer adjusts the load to meet requirements, record the adjustments on the Certificate of Compliance. Retest the air content of the load, slump if required, and record the adjusted test results. Test the next load for air content and slump, if required, before it gets into the work.
- Material not meeting requirements shall not knowingly be placed in the work. If failing concrete inadvertently gets placed in the work, review either the MnDOT Standard Specifications for Construction or contact the Concrete Engineering Unit for monetary deduction recommendations.

Best practices

- It is recommended that the Agency Plant Monitor be present during critical pours, such as superstructure or paving concrete (i.e., 3A21, S mixes, JMF mixes).
- It is recommended that the Agency representative continually monitor the progress of all concrete pours in the field and review Certificate of Compliances. It is not a recommended practice to only perform minimum testing requirements and leave the pour.
- It is recommended to make standard strength cylinders after the first load of concrete unless that is the only load of concrete for that mix that day.
- The Agency is responsible for verification sampling. For safety and consistency in sampling and splitting of the sample, it is recommended that the agency and the producer/contractor obtain the verification sample in tandem. This will allow the producer/contractor to witness the sampling process and take possession of the verification companion.

Concrete Plant and Field Materials

All materials must come from certified or qualified sources. All certified sources must state so on the delivery invoices. The most current list of certified/approved sources can be found at MnDOT Material website. Materials listed on the Approved/Certified Products List are not required to be sampled but need to be listed on the Material Acceptance Summary detailed in the SALT SMC. Samples can be submitted as directed by the Engineer.

Concrete Plant Batching Materials	Material	Spec. No.	Agency QA Field Sampling Rate	Form No.
	Portland Cement	3101	Shall be a Certified Supplier - For certified ready-mix and concrete paving sample rates: 1 sample when the plant is certified. Take additional samples if the plant changes sources or as the contract requires. The producer obtains a 5 lb. sample and stores the sample in a sealed container provided by the Agency and includes the supplier's delivery invoice from which the sample is obtained.	24300 ID Card Cement Samples
	Slag	3102		
	Blended Cement	3103		
	Fly Ash	3115		24308 Fly Ash
	Admixtures (Acceleration, Retarding, Water-Reducing, Air-Entraining, etc.)	3113	For all concrete: 1 sample of Air Entrainment and Type A Water Reducer in a 1/2-pint plastic container provided by the Agency when the plant is certified. Take additional samples if the plant changes sources or as the contract requires. The Producer should agitate the admixture tank prior to obtaining samples from dispensing tubes and store the samples in sealed plastic containers provided by the Agency.	2410 Sample ID Card
Water	3906	1 Non-Potable Water sample in a 1-gallon clean glass or plastic container from a questionable source. Clarified Water: 1 per month during Department production		
Concrete Field Materials	Preformed Joint Filler	3702	Visual Inspection	2410 Sample ID Card
	Preformed Elastomeric Type	3721	1 per lot. Only materials from a qualified source. <u>Link to Approved Products List.</u>	
	Silicone Joint Sealer	3722		
	Hot Poured Elastomeric Type	3723 3725		
	Burlap	3751	Visual Inspection	
	Colored Concrete Membrane Curing Compound	3752	Visual Inspection - Use only from qualified source.	
	Membrane Curing Compound	3753 3754 3755	Visual Inspection - Use only pre-approved curing compounds.	
	Plastic	3756	Visual Inspection - Must be white opaque and free from holes.	
	Refer to the "Metals" schedule for sampling requirements for concrete reinforcement.			

Concrete Pavement – Agency (1 of 2)

Test Type (concrete manual)	Spec.	Concrete Paving Batch Plant Agency QA Testing	Certified Ready-Mix Plant Agency QA Testing	Form
Gradation (1) (5-694.145) (5-694.148)	3126 3131 3137	Daily Concrete Quantity ≥ 500 Agency QA Testing Rates: Verification only Verification Sample: -, *1 per fraction per source per day, split and tested by both Agency and Contractor	Daily Concrete Quantity ≥ 100 yd3 Agency QA Testing Rates: Verification only Verification Sample: -, *1 per fraction per source per week, split and tested by both Agency and Contractor	JMF Concrete Aggregate Workbook
Aggregate Moisture - QC Verification (2) (5-694.142)	2301	If w/c incentives apply: 1 per 1000 yd3 or every 4 hours, whichever is greater. Take initial sample within the first 250 yd3.	If w/c incentives apply: 1 per 200 yd3 or every 4 hours, whichever is greater. Take initial sample within the first 100 yd3.	Concrete W/C Ratio Work sheet
Water Content, Microwave Oven Verification (3) (5-694.532)	<u>2301</u>	Take initial sample within the first 250 yd3. At least one additional verification test should be taken if more than 1000 yd3 is produced in a day.	Take initial sample within the first 100 yd3. At least one additional verification test should be taken if more than 400 yd3 is produced in a day.	
Coarse Aggregate, -200 sieve (5-694.146)	3131 3137	Test Verification sample on the first day of production and each time the Contractor mobilizes the plant, changes the aggregate sources, or the cleanliness of the coarse aggregate is in question, then 1 per week randomly thereafter. -200 test may be performed at the lab instead at the plant at the discretion of the Engineer.		JMF Concrete Aggregate Workbook
Coarse and Fine Aggregate Quality (4)	3126 3131 3137	During concrete production: 1 randomly selected test each fraction every 20,000 yd3 of production. Split the Quality sample 4 ways: 1) Provide 2 quarters of the sample to the producer/contractor. 2) Submit the remaining sample to the lab for quality testing including testing the -200 sieve on the coarse aggregate.		2410 Sample ID Card
Alkali Silica Reactivity (ASR) Testing	2301	1 per paving project per sand source. Provide one 5 lb. sample of: cement, supplementary cementitious material (fly ash or slag), and sand. Write "Project Specific ASR Testing" on all 3 sample cards. ASR Testing is not required if the entire project is less than 3,500 cubic yards.		2410 24300 24308
Coarse Aggregate Quality Testing of Incentive / Disincentive	3137	If coarse aggregate quality incentives apply: Test the Class B aggregates for % absorption and Class C aggregates for % carbonate including any other test necessary to make those determinations. Sample the 2 largest fractions in accordance with the following table and 2301:		Coarse Agg Quality Incentive / Disincentive Work sheet 2410 Sample ID Card
		Coarse Aggregate Quality Incentive/Disincentive Sampling Rates		
		Plan Concrete Cubic Yards	Samples per fraction	
		3,500 - 7,500	3	
		7,501 - 10,000	5	
		10,001 - 25,000	10	
		25,001 - 50,000	15	
50,001 +	20			

*Use Certified Ready-Mix Concrete testing rates when: a) The entire concrete paving project is less than 3,500 cu. yd. b) When a secondary plant is used to provide minor work.

Concrete Pavement – Agency (2 of 2)

Test Type	Spec.	Concrete Field Testing - Agency QA Testing	Form
Air Content before consolidation	Review Concrete Manual Website	1 correlation air test per day	2162 Test Beam Data
Concrete Temperature		Record temperature each time air content, slump or strength test specimen is performed/fabricated by the Agency.	
Flexural Strength		Supply beam boxes or cylinder molds. Cure and test beams and cylinders MnDOT standard beam box size is 6" x 6" x 20" unless others are approved by the Concrete Engineer.	
Opening to Traffic Strength		Supply beam boxes or cylinder molds for field control testing. Cure and test beams and cylinders.	
Concrete Pavement Texture		Determine texture testing locations using random numbers. Observe Contractor Testing when possible.	Probing, Coring, Texture and MIT-Scan T2 Report
Thickness		Determine probing and coring locations using random numbers. Initial pavement at core locations and re-initial the sides of specimens after coring to clearly verify their authenticity. Field measure cores to the nearest 1/8". Transport to the MnDOT Office of Materials and Road Research for final thickness determination	
Surface Smoothness/ Dowel and Tie Bar Steel Location		Observe Contractor Testing when possible	

NOTES:

(1) All gradation samples shall be taken in the presence of the Agency, unless otherwise authorized by the Engineer. All samples shall be taken off the belt leading to the weigh hopper unless otherwise approved by the Engineer. All gradations and quality tests require companion samples. If Coarse Aggregate Quality Incentive / Disincentives apply: The Agency may also use the QA samples for incentive / disincentive testing. Notify the Contractor/Producer to double the QC/QA sample size. If well-graded aggregate incentives apply: Use the Contractor's gradation results for well-graded aggregate incentive calculations as verified by Agency testing. Use the Well-graded Concrete Agg. Worksheet.

(2) If w/c incentives apply: Use aggregate moisture results for determining the water content to calculate the w/c incentive/disincentive. Use the Concrete W/C Ratio Calculation Worksheet and do not leave sample unattended. Microwave oven verification testing to verify the w/c ratio is completed in conjunction with Agency aggregate moisture testing. Do not leave samples unattended.

(3) If w/c incentives apply: Microwave oven verification testing to verify the w/c ratio is completed in conjunction with Agency aggregate moisture testing. Do not leave samples unattended.

(4) Prior to concrete production: Obtain pre-production samples for quality testing at least 16 hours prior to concrete production. Samples may be taken from the stockpile and -200 test may be performed at the lab instead at the plant at the discretion of the Engineer. If the entire project is <3,500 yd³, pre-production sampling is not required.

Minimum Aggregate Sample Size				
*companion required, double sample				
Aggregate Size	Gradation*	Quality*	Moisture	% -200 C.Agg
3/4" Plus, #4	30 lb.	50 lb.	2000 g	5000 g
3/4" Minus, #67	10 lb.	30 lb.	2000 g	2500 g
#7, CA-70	6 lb.	20 lb.	2000 g	2500 g
CIA to meet #67	6 lb.	20 lb.	500 g	500 g
CIA to meet JMF	500 g	20 lb.	500 g	500 g
FIA, CS, FS	500 g	20 lb.	500 g	-
CA-80, #89	500 g	20 lb.	500 g	500 g
Fine Aggregate	500 g	20 lb.	500 g	-

Concrete Pavement – Producer/Contractor (1 of 2)

Test Type (concrete manual)	Spec.	Concrete Paving Batch Plant Contractor/Producer QC Testing	Certified Ready-Mix Plant Contractor/Producer QC Testing
Gradation (1) (5-694.145) (5-694.148)	3126 3131 3137	When > 250 yd ³ produced/ day: 1 per 2500 yd ³ per fraction per source. Take initial samples for aggregate gradation testing within the first 500 yd ³ . Test the verification companion sample on the day the sample was taken.	When 20-400yd ³ produced/ day: 1 per fraction per source. If over 400 yd ³ per day, take a second gradation after the total exceeds 400 yd ³ . Test the verification companion sample on the day the sample was taken.
Coarse Aggregate -200 sieve (5-694.146)	3131 3137	Test the verification companion sample. Test these samples at the plant.	
Aggregate Moisture QC Verification (2) (5-694.142)	2301	If w/c incentives do not apply: 1 per 1000 yd ³ , or 1 completed every 4 hours, whichever is the higher sampling rate.	If w/c incentives do not apply: 1 completed every 4 hours.
Water Content, Microwave Oven Verification	<u>Review Concrete Manual 2301</u>	If w/c incentives apply: Obtain the plastic concrete sample at the plant. See Concrete Manual (5-694.532)	
Unit Weight QC		Test one load of concrete per day at the plant. See Concrete Manual (5-694.542)	
Air Content QC (5-694.541)		Test the first load of concrete at the plant	
Coarse Aggregate Quality	3126 3131 3137	Test at Producer/Contractor Discretion	
Unit Weight		Test 1 load of concrete per day at the plant.	
Air Content for Type 3 Concrete (QC)		Test the first load of concrete at the plant.	
Coarse Aggregate Quality Testing for Incentive / Disincentive	3137	Test at the Contractor's discretion.	

* Use Certified Ready-Mix Concrete testing rates when: a) The entire concrete paving project is less than 3,500 cu. yd. b) When a secondary plant is used to provide minor work.

Concrete Pavement – Producer/Contractor (2 of 2)

NOTES:

(1) Performing testing on representative material at the end of the most recent day of production is allowed. If well-graded aggregate incentives apply: Use the Contractor's gradation results for well-graded aggregate incentive calculations as verified by Agency testing. Washing the fine aggregate gradation (QC) sample is not required when the result on the -#200 sieve of the unwashed sample is less than 1.0%. Wash all fine aggregate Verification Companion samples.

(2) Complete the initial moisture content and adjust the batch water prior to the start of concrete production each day. If weather conditions allow, performing moisture testing on representative material at the end of production the prior evening is allowed. Enter results into the batching system in real time.

Test Type	Spec.	Concrete Field Testing - Contractor QC Testing
Air Content before consolidation for Type 3 concrete	<u>Review Concrete Manual Website</u>	1 per 300 yd ³ or 1 per hour, whichever is less. Test first load each day per mix.
Slump		Test slump if concrete is suspected to be outside of required slump range as directed by the Engineer.
Concrete Temperature		Record temperature each time air content, slump or strength test specimen is performed/fabricated by the Contractor.
Flexural Strength		For information only: 1 beam (28-day) per week per mix. 1 cylinder (28-day) per week per mix may be substituted at the discretion of the Engineer. Provide moist curing environments, fabricate beams or cylinders, deliver to curing site, and clean beam boxes
Opening to Traffic		For opening to traffic: Make field control beams within the last hour of concrete poured each day. Substitute field control cylinders for field control beams at the discretion of the Engineer. Maturity testing is allowed in lieu of field control cylinders or beams. Fabricate beams or cylinders, deliver to curing site, and clean beam boxes.
Concrete Pavement Texture		Perform texture testing at locations determined by the Engineer in accordance with the Contract
Thickness		Probe, scan and core at locations determined by the Engineer in accordance with the Contract
Surface Smoothness		Measure smoothness of the final concrete as required by the Contract. Perform all profiling in the presence of the Engineer unless otherwise approved by the Engineer.
Dowel Bar and Tie Bar Steel Location		For Concrete projects greater than 3500 yd ³ . On the first day and each day of slip form pavement: (1) Verify the adequacy of the dowel bar anchoring by scanning seven random doweled contraction joints in each subplot. (2) Verify the presence and alignment of tie bar steel by scanning 75 lin. ft. in each subplot. If the Engineer determines the first day's dowel bar anchoring and tie bar placement processes are acceptable, the Engineer may allow a reduction in scanned joints in each subplot as follows: (1) Verify the adequacy of the dowel bar anchoring by scanning four random doweled contraction joints per subplot. (2) Verify the presence and alignment of tie bar steel by scanning 25 lin. ft. out of every subplot.

Concrete Wearing Course for Bridges

Test Type (Concrete Manual)	Spec.	Contractor/Producer QC Testing	Agency QA Testing	Form
Gradation, Quality, Coarse Agg -200 QC/Verification (5-694.145) (5-694.146) (5-694.148)	3126 3137	<p>Prior to production: The Contractor shall provide the Agency with: Aggregate pit numbers, 1 passing gradation result per fraction per source. Test Agency companion samples are Contractor's discretion.</p> <p>No quality tests are required.</p>	<p>Prior to production and each time aggregate is delivered to site: 1 gradation and quality per fraction prior to concrete production and each time aggregate is delivered to the site.</p> <p>Identify quality samples with a "Q" on the Sample ID Card and the Quality companion sample.</p>	2410 Sample ID Card
Air Content - Type 3 Concrete (Verification) (5-694.541)	2431	None	1 per 15 yd ³ , Test at beginning of pour each day.	Weekly Report of Low Slump Concrete
Slump (Verification) (5-694.531)		None	1 per 15 yd ³ Test at beginning of pour each day. For concrete from a concrete mobil, allow mix to hydrate 5 minutes before slump test to assure all cement is saturated.	
Compressive Strength (5-694.511)		None	1 cylinder (28 day) per 30 yd ³ , standard cylinder mold size is 4 x 8 inch.	2409 Cyl. ID Card
Cement	3101	None	Each time cement is delivered to site. Obtain a 5 lb. sample. Store sample in a sealed container and include the supplier's delivery invoice from which the sample is obtained.	2430 Sample ID Card
Admixtures	3113	None	Each time new lot/batch admixture is delivered to site: Obtain a ½ pint sample. Store the sample in a sealed plastic container.	2410 Sample ID Card
Test	<p style="text-align: center;">Minimum Sample Size All gradation and aggregate quality tests require companion samples, double sample size. Samples taken at location identified on Contact Report located at plant.</p>			
Gradation	6 lb. for # 7, 500 g for CA-80		500 g for Sand	
Quality	30 lb. for Coarse Aggregate		20 lb. Fine Aggregate	

Concrete Pavement Repair – CPR for 3U18

Test Type	Spec.	Contractor/Producer QC Testing	Agency QA Testing For volumetric batching only.	Forms
Gradation, Quality, Coarse Agg -200	3126 3137	<p>Prior to production: The Contractor shall provide the Agency with: Aggregate pit numbers, 1 passing gradation result per fraction per source.</p> <p>No quality test results are required. Test companion samples at Contractor's discretion.</p>	<p>Gradation: Prior to concrete production and each time aggregate is delivered to the site. 1 per aggregate fraction prior to production and each time aggregate is delivered to the site.</p> <p>Quality Testing & Coarse Agg -200: 1 test per aggregate fraction per source. The Agency may use the gradation results for the Quality Samples as a substitute for 1 required field gradation. Identify quality samples with a "Q" on the Sample ID Card and the Quality companion sample.</p>	2410 Sample ID Card
Air Content - Type 3 Concrete (Verification)	Review Concrete Manual Website	None	1 per 15 yd ³ or 1 per 4 hours whichever results in the highest sampling rate. Test at beginning of pour each day.	21412 Weekly Report of Low Slump Concrete
Slump (Verification)		None	1 per 15 yd ³ , Test at beginning of pour each day. Allow mix to hydrate 5 minutes before slump test to assure all cement is saturated. Test slump if concrete is suspected to be outside of required slump range.	
Compressive Strength		None	1 set of 3 cylinders (28 day) per 30 yd ³ . The Agency will cast up to three (3) field control cylinders, standard cylinder mold size is 4 x 8 inch.	2409 Cyl. ID Card
Type 1 Cement	3101	None	For Volumetric batching only: Each time cement is delivered to site. Obtain a 5 lb. sample. Store sample in a sealed container and include the supplier's delivery invoice from which the sample is obtained.	2430 Sample ID Card
Admixtures	3113	None	Each time new lot/batch admixture is delivered to site: Obtain a ½ pint sample. Store the sample in a sealed plastic container.	2430 Sample ID Card
Test	Minimum Sample Size All gradation and aggregate quality tests require companion samples, double sample size. Samples taken at location identified on Contact Report located at plant.			
Gradation	6 lb. for # 7, 500 g for CA-80		500 g for Sand	
Quality	30 lb. for Coarse Aggregate		20 lb. Fine Aggregate	

Dowel Bar Retrofit – (DBR)

Test Type	Spec.	Contractor/Producer QC Testing	Agency QA Testing	Form
Gradation Testing (Verification), Quality Testing including, Coarse Agg -200	3137	<p>Prior to production: The Contractor shall provide the Agency with: Aggregate pit numbers, 1 passing gradation result per fraction per source.</p> <p>No quality test results are required. Test companion samples are Contractor's discretion.</p>	<p>Gradation: Prior to concrete production and each time aggregate is delivered to the site.</p> <p>1 per aggregate fraction prior to production and each time aggregate is delivered to the site.</p> <p>Quality Testing & Coarse Agg -200: 1 test per aggregate fraction per source. The Agency may use the gradation results for the Quality Samples as a substitute for 1 required field gradation. Identify quality samples with a "Q" on the Sample ID Card and the Quality companion sample.</p>	2410 Sample ID Card
Test Type	Spec.	Agency QA Testing		Form
DBR Material Compressive Strength	<u>Review Concrete Manual</u>	Contractor Testing: Any additional field control cylinders are the responsibility of the Contractor.		2409 Cylinder ID Card
		<p>Agency Testing: 1 set of 3 cylinders (28 day) The Agency will cast up to three (3) field control cylinders, standard cylinder mold size is 4 x 8 inch.</p>		
Test	Minimum Sample Size			
	All gradation and quality tests require companion samples, double sample size. Samples taken at location identified on Contact Report locates at plant.			
Gradation	500 g for # 89 & Sand			
Quality	30 lb. Coarse Aggregate		20 lb. Fine Aggregate	

Landscaping and Erosion Control Items

Kind of Material	Spec. #	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Manufactured Topsoil Borrow, Salvaged Topsoil (stockpiled)	3877.2	As directed by the Engineer
<u>Plant Stock & Landscape Materials</u>	3861 and 2571.2A1	Materials must be in accordance with the Inspection and Contract Administration Guidelines for MnDOT Landscape Projects of which determines the minimum and maximum criteria thresholds. Certificate of Compliance, Nursery stock certificate registered with MN Dept. of Agriculture. Out of state products subject to pest quarantines must accompanied by documentation certifying all products are free of regulated pests.
<u>Erosion Control Blanket</u>	3885	Visual Inspection and Check approved products or approved vendors list - As directed by the Engineer.
<u>Erosion Control Netting</u>	3885	
<u>Silt Fence</u>	3886	
<u>Erosion Stabilization Mat</u>	3885	
Flotation Silt Curtain	3887	
Filter Logs	3897	Accepted, based on manufacturers certification of compliance. Check weight of fabric.
Flocculants	3898	Visual Inspection
Fertilizer	3898	Obtain copy of Certificate of Compliance and MSDS
Fertilizer	3881	Obtain copy of invoice of blended material stating analysis.
Agricultural Lime	3879	Contractor must supply amount of ENP (Equivalent Neutralizing Power) for each shipment.
<u>Mulch - Type 3</u>	3882	Certified Weed Free (Certified sources only) Check for Certified Vendor tag from Minnesota Crop Improvement Association (MCIA).
Mulch - Type 6 - Woodchips		All wood chips supplied by a supplier outside the Emerald Ash Borer quarantine area or have an Emerald Ash Borer Compliance Agreement with the MDA
Seeds	3876	(Certified Vendors Only) (Mixes 100-299) Check for Certified Vendor tag from Minnesota Crop Improvement Association (MCIA).
Native Seed		(Mixes 300-399) certified seed only. Check for Certified Vendor tag from Minnesota Crop Improvement Association (MCIA).
<u>Sod</u>	3878	Visual Inspection - Check approved products list - As directed by the Engineer. Check for Certified Vendor tag from Minnesota Crop Improvement Association (MCIA) for salt tolerant sod.
<u>Compost (from Certified Source)</u>	3890	
Compost (from Non-Certified Source)		Visual Inspection - As directed by the Engineer.
<u>Hydraulic Soil Stabilizer</u>	3884	Check Approved/Qualified Products List - As directed by the Engineer.

Chemical Items

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Asphalt Plank	3204	Visual Inspection - As directed by the Engineer.
Calcium Chloride	3911	Review the percentage required as per specification. Check for listing on Qualified Products website.
Magnesium Chloride	3912	
Hot-Pour Crack Sealant (for Crack Sealing/Filling)	3719 3723 3725	Retain Certification of Compliance. Check for listing on Qualified Products website.
Pavement Joint Adhesive	Special Provisions	Retain Certification of Compliance
Waterproofing Materials		
<u>Membrane Waterproofing System</u>	3757	Visual Inspection - Check qualified products list.
Waterproofing Materials - Three Ply System		
Asphalt Primer	3165	Verify supplied material meets ASTM D 41
Waterproofing Asphalt	3166	Verify supplied material meets ASTM D 449
Fabric	3201	Verify supplied material meets ASTM D 41
Paints		
<u>Waterborne Latex - Traffic Paint</u>	3591	Visual Inspection - Check qualified products list - retain Certificate of Compliance.
<u>Epoxy Traffic Paint</u>	3590	
<u>Traffic Marking Paint</u>	Special Provisions	
<u>Non-Traffic Striping Paints</u>	3500 Series	Retain Certification of Compliance
<u>Bridge Structural Steel Paint</u>	3520	Visual Inspection - Check approved products list - retain Certificate of Compliance.
<u>Exterior Masonry Paint</u>	3584	
<u>Noise Wall Stain</u>	Special Provisions	
<u>Drop-on Glass Beads</u>	3592	Visual Inspection - Check qualified products list. Retain Certificate of Compliance.
<u>Pavement Marking Tape</u>	3354	Visual Inspection - Check qualified products list. Retain Certificate of Compliance.
	3355	
	Special Provisions	
<u>Signs and Markers</u>	3352	Visual Inspection - Check qualified products list.

Metals (1 of 2)

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate) *
Guard Rail		
Fittings - Splicers, Bolts, Posts etc.	3381	Visual Inspection - Materials shall be approved before use. Call MnDOT inspector at 218-846-3613 to see if material has been approved.
Structural Plate Beam	3382	
Non-High Tension Guard Rail Cable	3381	
High Tension Guard Rail Cable	Special Provisions	
Steel Posts		
Steel Signposts	3401	Visual Inspection - As directed by the Engineer. Retain Certificate of Compliance in Project file.
Fence Posts, Brace Bars, Rails and others	3403	Visual Inspection - As directed by the Engineer. Retain Certificate of Compliance and certified mill analysis in project file.
	3406	
	3379	
Fence		
Barbed Wire	3376	Visual Inspection Retain Certification of Compliance, As directed by the Engineer.
Woven Wire		
Chain Link Fabric		
Components: cup, cap, nut, bolt, end clamp, tension band, truss rod tightener, hog ring, tie wire, tension stretcher bar, truss rod, clamp & tension wire		
Gates	3379	
Pipe		
Water Pipe and other Piping Materials	3364, 3365, 3366 & Special Provisions	Visual Inspection - As directed by the Engineer.
Reinforcing Steel - Inspected by MnDOT & will be charged back to the Local Agency.		
Uncoated Bars	3301	Retain Certificate of Compliance & Certified Mill Analysis
Epoxy Coated Bars	3301	For Epoxy-Coated bars, steel will be tagged "Inspected" when it has been sampled and tested by Mn/DOT prior to shipment, & it will be tagged "Sampled" when testing has not been completed prior to shipment. If the Epoxy-Coated bars are not tagged "Sampled" or "Inspected", submit samples (1 bar 3ft long for each size for each day's coating production), Certificate of Compliance, & Certified Mill Analysis for testing. Maintain original Cert. of Compliance & Certified Mill Analysis in project file.
Spirals	3305	
Stainless Steel Bars	Special Provisions	Visual Inspection Testing as directed by the Engineer (2 bars 3 ft. long per heat per bar size). Certified Mill Test Reports to be filed.

Metals (2 of 2)

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate) *	
Reinforcing Steel - Inspected by MnDOT & will be charged back to the Local Agency.			
Steel Fabric	3303	2 sq. ft. if epoxy coated.	Visual Inspection - Retain Certificate of Compliance.
Dowel Bars	3302	One dowel bar and basket from each shipment.	
Prestress/Post Tension Strands	3348 Spec Prov	One sample of 2 strands by 6 ft. from each heat/production lot.	
Castings			
Drainage Castings	3321	Visual Inspection - Check approved / qualified list.	
	2471		
Electrical	2565		
Anchor Rods (Cast in Place) and Structural Fasteners	3385 3391	Visual Inspection - Check approved / qualified list. Testing as directed by the Engineer (see notes below)	
Notes: Manufacturer must have one yearly passing test from the Department for each anchor rod or bolt type. Prior to installation, obtain copy of MnDOT passing test report from supplier. Specs 3385.2 A, B, & C require anchor rod markings per ASTM F 1554 S3. The end of each anchor bolt intended to project from the concrete must be die stamped with the grade identification as follows: Grade 36 = AB36, Grade 55 = AB55, Grade 105 = AB105.			
Anchorage (Drilled In)	Special Provisions	Visual Inspection - Check qualified products list.	
Structural Steel	Inspected by MnDOT & will be charged back to the Local Agency.		
Steel Bridge - Beams, Girders, Diaphragms, etc.	2471	Structural Metals Inspection Tag and field inspection for damage/defects, check dimensions for contract compliance. Review approved products list as directed by the Engineer. Note: Structural metals products will be inspected at the plant and will be shipped with a Structural Metals Inspection Tag. An inspection confirmation report will be completed by Structural Metals Inspection staff and sent to the field personnel. Only approved suppliers are allowed to supply Structural Metals products. A list of approved suppliers can be found on the Bridge Office website .	
Concrete Girders-Diaphragms and sole plates			
Expansion Joints			
Steel Bearings			
Railing-Structural tube and ornamental			
Drainage Systems			
Protection Angles			
Overhead Sign structures	2564 2471		
High Mast Lighting Structures	2545 2471		
Monotube Signal Structures	2565 2471		

*Check domestic steel requirement under 1601 Special Provision.

Geosynthetics, Pipe, Tile, Precast/ Prestressed Concrete

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Corrugated Metal Products		
Culvert Pipe Under Drains Erosion Control Structures	3225 thru 3229, 3351, 3399	Make certain pipe is Certified on Invoice, retain certificate of compliance and certified mill analysis in project file.
Structural Plate	3231	
Aluminum Structural Plate	3233	Retain the Certificate of Compliance and mill analysis in project file.
Pipe		
Clay Pipe	3251	Visual Inspection
Reinforced Concrete Pipe and Arches, Precast Cattle Pass Units, Sectional Manhole Units	3236	Field Inspection: Check for damage and defects. Check dimensions and class as required.
Non-Reinforced Concrete Pipe	3253	
Drain Tile (Clay or Concrete)	3276	Visual Inspection - Acceptance as directed by the Engineer.
Thermoplastic (TP) Pipe ABS and PVC	3245	Obtain Certificate of compliance. Check for approved marking printed on pipe. Field Inspect for damage or defects.
Corrugated Polyethylene Pipe	3278	Check for markings (AASHTO M 252) Certificate of Compliance. Field Inspect for damage or defects.
<u>Corrugated Polyethylene Pipe - Dual Wall 12"-48"</u>	3247	Visual Inspection - Check approved products list. Obtain Certificate of Compliance.
Precast/Prestressed Concrete Structures - Inspected by MnDOT & will be charged back to the Local Agency.		
Reinforced Precast Box Culvert	3238	Field Inspection: Check for damage and defects. Check dimensions as required. Check for the "MnDOT" stamp and signature on the certification document.
Precast/Prestressed Concrete Structure (beams, posts, etc.)	2405	
Manholes and Catch Basins	2506 3622	
Sewer Joint Sealing Compound	3724	Visual Inspection - Acceptance as directed by the Engineer.
Preformed Plastic Sealer for Pipe	3726 Type b	Visual Inspection - Acceptance as directed by the Engineer.
Bituminous Mastic Joint Sealer for Pipe	3728	
EPS Geofoam	Special Provisions	Visual Inspection - Acceptance as directed by the Engineer. Check for yellow aged material, uniformity and dimensions.
Geotextile Fabric and Geogrid Reinforcement	3733 and Special Provisions	Obtain Certificate of Compliance stating minimum average roll values (MARV). MARV must meet Project requirements. Fabric must be listed on <u>Geotextile Small Quantity Acceptance List</u> .
<u>Geotextile Small Quantity Acceptance List</u>		
<u>Silt Fence</u>	3886	Visual Inspection - Check approved products list.

Electrical and Signal Equipment Items (1 of 2)

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Lighting Standards (Aluminum or Steel)	3811	Visual Inspection - Obtain Certificate of Compliance. The Fabricator will submit "Certificate of Compliance," on a per project basis, to the Project Engineer.
<u>Hand Holes (Precast, PVC, and LLDPE)</u>	2545	Visual Inspection - Check approved/qualified products list. Traffic signal and street lighting projects require hand holes to be listed on the MnDOT Signals Approved Products List (APL). For cast iron frame and cover: see Metals - Drainage and Electrical Castings
	2550	
	2565	
Foundation	2545	Slump as needed, 1 cylinder per 25 cu. yds. Rebar is required in concrete foundations as specified in the Contract documents for all traffic control signals and roadway lighting projects.
Steel Screw In Foundations	2545 2565	See Approved/Qualified Products List for Roadway Lighting and Signals.
Conduit and Fittings		
Metallic	3801	Visual Inspection - Conduit shall be labeled as being listed by a National Recognized Testing Laboratory (NRTL). For traffic signal and street lighting projects, specific requirements are contained in the Special Provisions for each project.
	3802	
Non-Metallic (Rigid and HDPE)	3803	
	Special Provisions	
Anchor Rods and Bolts (Cast in Place)	3385	Visual Inspection - Manufacturer must have one yearly passing test from the Department for each anchor rod or bolt type. Prior to installation, obtain copy of Mn/DOT passing test report from supplier. Specs 3385.2 A, B, & C require anchor rod markings per ASTM F 1554 S3. The end of each anchor bolt intended to project from the concrete must be die stamped with the grade identification as follows: Grade 36 = AB36, Grade 55 = AB55, Grade 105 = AB105.
<u>Anchorage (Drilled In)</u>	Special Provision	Visual Inspection - Check qualified products list.
<u>Miscellaneous Hardware</u>	2545 2565	Visual Inspection - Check approved products list. Will carry "Inspected" tag if sampled and tested prior to shipment. No sample necessary if "Inspected". Do not use if not tested. Field sample at sampling rate for laboratory testing. For traffic signal and street light lighting projects, various miscellaneous hardware is required to be listed on the MnDOT Signals and Lighting Approved Products Lists (APL). The Contract documents indicate, which items must be on the Signals and/or Lighting APL.

Electrical and Signal Equipment Items (2 of 2)

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Cable and Conductors		
Power Conductors	3815.2B1	Visual Inspection - Make certain the conductors are the type specified. Submit Field Inspection report showing type and quantities used. Shall be labeled as being listed by a National Recognized Testing Laboratory (NRTL) and type where applicable.
Loop Detector Conductors (No Tubing)	3815.2B2 (a)	
Electrical Cables and Single Conductors with Jacket	3815.2B2(b) 3815.2B3	Visual Inspection - Usually inspected at the distributor. Documentation showing project number, reel number(s), & MnDOT test number(s) will be included with each project shipment. If such documentation is not received from Contractor, submit sample for testing along with material certification from manufacturer. Do not use if not tested. Pre-inspected materials will not be tagged; an inspection report will be sent by the MnDOT inspector for each shipment. Project inspectors should verify that the shipping documents agree with this inspection report. Call Steve Grover at 651-366-5540 or Cindy Schellack at 651-366-5543 with questions. For traffic signal and street lighting projects, the Special Provisions for each project contain electrical cable and conductor specifications.
	3815.2B5	
	3815.2C1 thru .2C8	
	3815.2C14	
	Special Provisions	
Fiber Optic Cables	3815.2C13	Visual Inspection - Check approved products list for Traffic Management Systems.
Ground Rods	2545	Visual Inspection - Check approved products list. Shall be labeled as being listed by a National Recognized Testing Laboratory (NRTL). Detail materials on Materials Acceptance Summary.
	2565	
Luminaires and Lamps	3810	Visual Inspection - Check approved products list. Traffic signal and street lighting projects require luminaires and lamps to be listed on the MnDOT Lighting Approved/Qualified Products List (APL). The conductors shall be labeled as being listed by a National Recognized Testing Laboratory (NRTL) and type, where applicable.
Electrical Systems	2565	Electrical Systems are to be reported as a "System" using the LIGHTING, SIGNAL AND TRAFFIC RECORDER INSPECTION REPORT. To be certified by the Project Engineer.
Traffic Signal Systems	2565	Traffic Signal Systems are to be reported as a "System" using the LIGHTING, SIGNAL AND TRAFFIC RECORDER INSPECTION REPORT. To be certified by the Project Engineer.

Brick, Stone, and Masonry Units

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Brick		
Sewer (clay) and Building	3612 to 3615	Visual Inspection - Acceptance as directed by the Engineer.
Sewer (Concrete)	3616	Visual Inspection - Acceptance as directed by the Engineer. Air entrainment required. Obtain air content statement from supplier.
Concrete Masonry Units		
Sewer Construction	3621	Visual Inspection - Acceptance as directed by the Engineer. Air entrainment required. Obtain air content statement from supplier.
<u>Modular Block Retaining Walls</u>	Review Current Special Provisions	Visual Inspection - Note: All lots of blocks upon delivery shall have Manufacturer or Independent laboratory test results to verify passing both compression and freeze-thaw requirements. * Wall units and cap units are considered separate block types.
Reinforced Concrete Cribbing	3661	Visual Inspection - Acceptance as directed by the Engineer. Will be stamped when inspected prior to shipment.
Stone for Masonry or Rip-Rap	2511, 3601 and Special Provisions	Visual Inspection - Acceptance as directed by the Engineer.

Remarks: each source shall be approved by Project Engineer or supervisor for quality, prior to use. For questions on quality, contact District Materials or Geology Unit.

Miscellaneous Materials

Kind of Material	Spec. No.	Minimum Required Agency QA Acceptance Testing (Field Testing Rate)
Timber, Lumber Piling & Posts	3412 to 3471 & 3491	Visual Inspection - Acceptance as directed by the Engineer. Untreated materials shall be inspected in the field. Treated materials shall be Certified on the Invoice or Shipping Ticket. Material is inspected and stamped by an Independent Agency as per Specification 3491. Contact Laboratory for additional information.
Miscellaneous pieces and Hardware (Galvanized)	3392 3394	Visual Inspection - Acceptance as directed by the Engineer.
Insulation Board	3760	
Elastomeric Bearing Pads - Plain or Laminated	3741 and Special Provisions	Check dimensions. Check repair of tested pad. Obtain copy of Certificate of Compliance. DO NOT USE ANY PADS THAT ARE NOT CERTIFIED.
Cotton Duck Bearing Pads		

Approved/Qualified Products & Resources

Approved/Qualified Products

- [Asphalt Products](#)
- [Bridge Products](#)
- [Concrete Products](#)
- [Crack and Joint Material Products](#)
- [Drainage](#)
- [Erosion Control and Landscaping Products](#)
- [Geosynthetic](#)
- [Maintenance Shop Supplies](#)
- [Paint/Stain/Coating Systems \(Non-Pavement\)](#)
- [Pavement Markings](#)
- [Precast Concrete](#)
- [Roadside Barriers](#)
- [Roadway Lighting Products](#)
- [Signals Products](#)
- [Signing Products](#)
- [Snow and Ice Chemical Products](#)
- [Temporary Traffic Control Devices](#)
- [Traffic Management Systems/ITS](#)
- [Truncated Domes](#)
- [Vehicle Safety Lighting](#)
- [Walls \(Retaining/Noise\)](#)

Additional Resources

- [SALT Construction webpage](#)
- [Bituminous Engineering](#)
 - [Asphalt Binder Certified Supplier](#)
 - [Asphalt Emulsion Certified Supplier](#)
- [Concrete Engineering](#)
 - [MnDOT Concrete Manual](#)
 - [QC & QA RM Plant Workbooks](#)
 - [MnDOT Certified Ready-Mix Program](#)
- [Grading & Base Engineering](#)
 - Testing procedures in the [Grading & Base Manual](#)
 - Forms and worksheets at the [Grading & Base website](#)
 - Gradation worksheets on the [SALT Construction website](#)

Contacts

MnDOT Construction and Materials State Aid Contacts

Districts 1, 2, 3, 4

Ross Hendrickson, State Aid Construction Specialist

ross.hendrickson@state.mn.us

218-766-3745

Districts 6, 7, 8

Rollin Larson, State Aid Construction Specialist

rollin.larson@state.mn.us

507-205-6403

Metro

Michael Pretel, State Aid Construction Engineer

michael.pretel@state.mn.us

651-755-3346

MnDOT Specialty Offices Contacts

Grading & Base

Terry Beaudry terry.beaudry@state.mn.us	Grading & Base Engineer	651-366-5456
John Bormann john.bormann@state.mn.us	Grading & Base Specialist	651-366-5596

Bituminous*

John Garrity john.garrity@state.mn.us	Bituminous Engineer	651-366-5577
Greg Johnson Greg.johnson@state.mn.us	Asst. Bituminous Engineer	651-366-5464
Chelsea Bennett chelsea.bennett@state.mn.us	Asst. Bituminous Engineer	651-366-5482
Joel Ulring joel.ulring@state.mn.us	Pavement Preservation	651-366-5432
Mike Skurdalsvold	Bituminous Mix Design Specialist	612-499-2998
Ray Betts ray.betts@state.mn.us	Bituminous Trial Mix Lab Tech	651-366-5469
Rich Kane richard.kane@state.mn.us	Bituminous Plant & Lab Testing	612-437-3005

*See website for the contact list by topic

Concrete*

Maria Masten maria.masten@state.mn.us	Concrete Engineer	651-334-4015
Jacob Gave jacob.gave@state.mn.us	Asst. Concrete Engineer	612-554-9289
Rob Golish robert.golish@sate.mn.us	Asst. Concrete Engineer	651-216-0516
Matt Herbst	Concrete Engineering Specialist	651-283-7127

2024 SALT Schedule of Materials Control – Local Government Agency

Matt.herbst@state.mn.us		
Brad Swenson brad.swenson@state.mn.us	Concrete Engineering Specialist	218-232-1012
Gordy Bruhn gordon.bruhn@state.mn.us	Concrete Field Engineering Specialist	651-398-9597
Mike Daniels michael.daniels@state.mn.us	Concrete Engineering Specialist	320-293-9421

*See website for the contact list by topic

Contacts for other materials can be found on the [Materials and Road Research Contacts webpage](#).

Contacts for Approved Products can be found at the [Approved/Qualified Products Contact webpage](#).

Materials Lab. Contacts	Independent Assurance
District 1, Duluth Leila DeLuca Phone: 218-725-2738 D1.duluth.lab.dot@state.mn.us	Nadine Miller Phone: 218-725-2737 Cell: 218-348-6297 nadine.miller@state.mn.us
District 2, Bemidji Jason Kissel Phone: 218-755-6542 jason.kissel@state.mn.us Mike Murphy (Concrete & Aggregates) Phone: 218-755-6593 mike.murphy@state.mn.us Dustin Reese (Bituminous) Phone: 218-755-6593 dustin.reese@state.mn.us	Ray Wesley Cell: 218-766-6949 raymond.wesley@state.mn.us
District 3A, Baxter Tom Boser Phone: 218-828-5755 tom.boser@state.mn.us	Matt Miles Cell: 218-232-6748 matt.miles@state.mn.us
District 3B, Saint Cloud Nick Fisher Phone: 320-2236500 nicholas.fisher@state.mn.us Andy Kostreba Phone: 320-223-6554 andy.kostreba@state.mn.us	Travis Erickson Cell: 320-291-3582 travis.erickson@state.mn.us
District 4, Detroit Lakes Bruce Bryngelson Phone: 218-846-3614 bruce.bryngelson@state.mn.us Wayne Koons	Casey Clarke Cell: 218-849-7393

2024 SALT Schedule of Materials Control – Local Government Agency

Phone: 218-846-3617 wayne.koons@state.mn.us	casey.clarke@state.mn.us
Metro District, Maplewood Lab Brent Sculley Phone 651-366-5409 brent.scolley@state.mn.us	Waters Edge Phone: 651-234-7356 Zachary Lyrek-Hanks Phone: 651-775-1018 zachary.Lyrek-Hanks@state.mn.us West Karl Sinclair Phone: 651-775-0998 karl.sinclair@state.mn.us East Kris Westerbur Phone: 651-755-1151 kristopher.westerbur@state.mn.us Kaleb Kollmann Phone: 651-478-0339 kaleb.kollmann@state.mn.us
District 6, Rochester Scott Swanson Phone: 507-286-7580 scott.a.swanson@state.mn.us Jeff Bale (Aggregates) Phone: 507-286-7586 jeff.bale@state.mn.us Joe Drees (Bluminous) Phone: 507-286-7582 joe.drees@state.mn.us Gary Vinge Phone: 507-286-7585 gary.vinge@sate.mn.us	Dennis Hayes Cell: 507-251-0138 dennis.hayes@state.mn.us
District 7, Mankato Lee McLaughlin Phone: 507-304-6189 lee.mclaughlin@state.mn.us	Mitch Jordahl Cell: 507-380-9619 mitch.jordahl@state.mn.us
District 8, Willmar and Marshall Jon Vlaminck Phone: 320-214-6348 Cell: 320-894-7409 jon.vlaminck@state.mn.us District 8B, Marshall Matt Steinbronn Phone: 507-537-2068 matthew.steinbronn@state.mn.us	Paul Janke Cell: 320-212-5739 paul.janke@state.mn.us

Sample Sizes

Lbs.

Bituminous	35	Aggregate for Gradation QC/QA
	80	for each plus #4 Aggregate Type for Quality Testing
	35	for each minus #4 Aggregate Type for Quality Testing
	80	for each RAP material for Quality Testing
	10	RAS (shingles) for Processed Gradation and Quality Testing
	65	for Mix Properties (QC/QA) 3 full 6" by 12"-cylinder molds for QA
	90	for TSR (QC/QA) 4 full 6" by 12"-cylinder molds for QA
	90	for Aggregate Specific Gravity QC/QA
	-	1 quart of Asphalt Binder QA
	-	1/2 gallon for Asphalt Emulsion QA
Grading & Base	30	Aggregate for Gradation (Companion sample from 60 lb. split).
	25	Moisture Density Test – Proctor (Companion from 50 lb. split).
	30	Aggregate Quality/Percent Crushing Test - 1 per source
Ready-Mix Concrete	25	Gradation 3/4" plus
	10	Gradation 3/4" minus
	6	Gradation CA 70 & #7
	1	Gradation - Sand (500 g), CA 80, #89.
	4.4	Moisture Test Coarse Aggregate (2000 g)
	1.1	Moisture Test Fine Aggregate (500 g)
	50	Quality 3/4" plus - lab sample
	30	Quality 3/4" minus - lab sample
	30	Fine Aggregate - lab sample
	10	3/4" Plus for the -200 Coarse Aggregate Test (5000 grams)
	6	3/4" Minus for the -200 Coarse Aggregate Test (2500 grams)
	5	Cement, Blended Cement, Fly Ash
	-	1/2-pint plastic container for admixtures.

**ATTACHMENT A
PRIME CONTRACTOR RESPONSE**

RESPONSIBLE CONTRACTOR VERIFICATION AND CERTIFICATION OF COMPLIANCE

STATE PROJECT NUMBER: _____

This form includes changes by statutory references from the Laws of Minnesota 2015, chapter 64, sections 1-9. This form must be submitted with the response to this solicitation. A response received without this form, will be rejected.

Minn. Stat. § 16C.285, Subd. 7. **IMPLEMENTATION.** ... any prime contractor or subcontractor or motor carrier that does not meet the minimum criteria in subdivision 3 or fails to verify that it meets those criteria is not a responsible contractor and is not eligible to be awarded a construction contract for the project or to perform work on the project...

Minn. Stat. § 16C.285, Subd. 3. **RESPONSIBLE CONTRACTOR, MINIMUM CRITERIA.** "Responsible contractor" means a contractor that conforms to the responsibility requirements in the solicitation document for its portion of the work on the project and verifies that it meets the following minimum criteria:

- | | |
|-----|---|
| (1) | <p>The Contractor:</p> <ul style="list-style-type: none">(i) is in compliance with workers' compensation and unemployment insurance requirements;(ii) is in compliance with Department of Revenue and Department of Employment and Economic Development registration requirements if it has employees;(iii) has a valid federal tax identification number or a valid Social Security number if an individual; and(iv) has filed a certificate of authority to transact business in Minnesota with the Secretary of State if a foreign corporation or cooperative. |
| (2) | <p>The contractor or related entity is in compliance with and, during the three-year period before submitting the verification, has not violated section 177.24, 177.25, 177.41 to 177.44, 181.03, 181.101, 181.13, 181.14, or 181.722, and has not violated United States Code, title 29, sections 201 to 219, or United States Code, title 40, sections 3141 to 3148. For purposes of this clause, a violation occurs when a contractor or related entity:</p> <ul style="list-style-type: none">(i) repeatedly fails to pay statutorily required wages or penalties on one or more separate projects for a total underpayment of \$25,000 or more within the three-year period, provided that a failure to pay is "repeated" only if it involves two or more separate and distinct occurrences of underpayment during the three-year period;(ii) has been issued an order to comply by the commissioner of Labor and Industry that has become final;(iii) has been issued at least two determination letters within the three-year period by the Department of Transportation finding an underpayment by the contractor or related entity to its own employees;(iv) has been found by the commissioner of Labor and Industry to have repeatedly or willfully violated any of the sections referenced in this clause pursuant to section 177.27;(v) has been issued a ruling or findings of underpayment by the administrator of the Wage and Hour Division of the United States Department of Labor that have become final or have been upheld by an administrative law judge or the Administrative Review Board; or(vi) has been found liable for underpayment of wages or penalties or misrepresenting a construction worker as an independent contractor in an action brought in a court having jurisdiction. Provided that, if the contractor or related entity contests a determination of underpayment by the Department of Transportation in a contested case proceeding, a violation does not occur until the contested case proceeding has concluded with a determination that the contractor or related entity underpaid wages or penalties;* |

(3)	The contractor or related entity is in compliance with and, during the three-year period before submitting the verification, has not violated section 181.723 or chapter 326B. For purposes of this clause, a violation occurs when a contractor or related entity has been issued a final administrative or licensing order;*
(4)	The contractor or related entity has not, more than twice during the three-year period before submitting the verification, had a certificate of compliance under section 363A.36 revoked or suspended based on the provisions of section 363A.36, with the revocation or suspension becoming final because it was upheld by the Office of Administrative Hearings or was not appealed to the office;*
(5)	The contractor or related entity has not received a final determination assessing a monetary sanction from the Department of Administration or Transportation for failure to meet targeted group business, disadvantaged business enterprise, or veteran-owned business goals, due to a lack of good faith effort, more than once during the three-year period before submitting the verification;*
	* Any violations, suspensions, revocations, or sanctions, as defined in clauses (2) to (5), occurring prior to July 1, 2014, shall not be considered in determining whether a contractor or related entity meets the minimum criteria.
(6)	The contractor or related entity is not currently suspended or debarred by the federal government or the state of Minnesota or any of its departments, commissions, agencies, or political subdivisions that have authority to debar a contractor; and
(7)	All subcontractors and motor carriers that the contractor intends to use to perform project work have verified to the contractor through a signed statement under oath by an owner or officer that they meet the minimum criteria listed in clauses (1) to (6).

Minn. Stat. § 16C.285, Subd. 5. SUBCONTRACTOR VERIFICATION.

A prime contractor or subcontractor shall include in its verification of compliance under subdivision 4 a list of all of its first-tier subcontractors that it intends to retain for work on the project. Prior to execution of a construction contract, and as a condition precedent to the execution of a construction contract, the apparent successful prime contractor shall submit to the contracting authority a supplemental verification under oath confirming compliance with subdivision 3, clause (7). Each contractor or subcontractor shall obtain from all subcontractors with which it will have a direct contractual relationship a signed statement under oath by an owner or officer verifying that they meet all of the minimum criteria in subdivision 3 prior to execution of a construction contract with each subcontractor.

If a prime contractor or any subcontractor retains additional subcontractors on the project after submitting its verification of compliance, the prime contractor or subcontractor shall obtain verifications of compliance from each additional subcontractor with which it has a direct contractual relationship and shall submit a supplemental verification confirming compliance with subdivision 3, clause (7), within 14 days of retaining the additional subcontractors.

A prime contractor shall submit to the contracting authority upon request copies of the signed verifications of compliance from all subcontractors of any tier pursuant to subdivision 3, clause (7). A prime contractor and subcontractors shall not be responsible for the false statements of any subcontractor with which they do not have a direct contractual relationship. A prime contractor and subcontractors shall be responsible for false statements by their first-tier subcontractors with which they have a direct contractual relationship only if they accept the verification of compliance with actual knowledge that it contains a false statement.

Subd. 5a. Motor carrier verification. A prime contractor or subcontractor shall obtain annually from all motor carriers with which it will have a direct contractual relationship a signed statement under oath by an owner or officer verifying that they meet all of the minimum criteria in subdivision 3 prior to execution of a construction contract with each motor carrier. A prime contractor or subcontractor shall require each such motor carrier to provide it with immediate written notification in the event that the motor carrier no longer meets one or more of the minimum criteria in subdivision 3 after submitting its annual verification. A motor carrier shall be ineligible to perform work on a project covered by this section if it does not meet all the minimum criteria in subdivision 3. Upon request, a prime contractor or subcontractor shall submit to the contracting authority the signed verifications of compliance from all motor carriers providing for-hire transportation of materials, equipment, or supplies for a project.

Minn. Stat. § 16C.285, Subd. 4. VERIFICATION OF COMPLIANCE.

A contractor responding to a solicitation document of a contracting authority shall submit to the contracting authority a signed statement under oath by an owner or officer verifying compliance with each of the minimum criteria in subdivision 3, with the exception of clause (7), at the time that it responds to the solicitation document.

A contracting authority may accept a signed statement under oath as sufficient to demonstrate that a contractor is a responsible contractor and shall not be held liable for awarding a contract in reasonable reliance on that statement. A prime contractor, subcontractor, or motor carrier that fails to verify compliance with any one of the required minimum criteria or makes a false statement under oath in a verification of compliance shall be ineligible to be awarded a construction contract on the project for which the verification was submitted.

A false statement under oath verifying compliance with any of the minimum criteria may result in termination of a construction contract that has already been awarded to a prime contractor or subcontractor or motor carrier that submits a false statement. A contracting authority shall not be liable for declining to award a contract or terminating a contract based on a reasonable determination that the contractor failed to verify compliance with the minimum criteria or falsely stated that it meets the minimum criteria. A verification of compliance need not be notarized. An electronic verification of compliance made and submitted as part of an electronic bid shall be an acceptable verification of compliance under this section provided that it contains an electronic signature as defined in section 325L.02, paragraph (h).

CERTIFICATION

By signing this document I certify that I am an owner or officer of the company, and I certify under oath that:

- 1) My company meets each of the Minimum Criteria to be a responsible contractor as defined herein and is in compliance with Minn. Stat. § 16C.285, and**
- 2) if my company is awarded a contract, I will submit Attachment A-1 prior to contract execution, and**
- 3) if my company is awarded a contract, I will also submit Attachment A-2 as required.**

Authorized Signature of Owner or Officer:

Printed Name:

Title:

Date:

Company Name:

NOTE: Minn. Stat. § 16C.285, Subd. 2, (c) If only one prime contractor responds to a solicitation document, a contracting authority may award a construction contract to the responding prime contractor even if the minimum criteria in subdivision 3 are not met.

ATTACHMENT A-1

FIRST-TIER SUBCONTRACTORS LIST

SUBMIT PRIOR TO EXECUTION OF A CONSTRUCTION CONTRACT

STATE PROJECT NUMBER: _____

Minn. Stat. § 16C.285, Subd. 5. A prime contractor or subcontractor shall include in its verification of compliance under subdivision 4 a list of all of its first-tier subcontractors that it intends to retain for work on the project. Prior to execution of a construction contract, and as a condition precedent to the execution of a construction contract, the apparent successful prime contractor shall submit to the contracting authority a supplemental verification under oath confirming compliance with subdivision 3, clause (7). Each contractor or subcontractor shall obtain from all subcontractors with which it will have a direct contractual relationship a signed statement under oath by an owner or officer verifying that they meet all of the minimum criteria in subdivision 3 prior to execution of a construction contract with each subcontractor.

FIRST TIER SUBCONTRACTOR NAMES* (Legal name of company as registered with the Secretary of State)	Name of city where company home office is located

*Attach additional sheets as needed for submission of all first-tier subcontractors.

SUPPLEMENTAL CERTIFICATION FOR ATTACHMENT A-1	
By signing this document I certify that I am an owner or officer of the company, and I certify under oath that: All first-tier subcontractors listed on attachment A-1 have verified through a signed statement under oath by an owner or officer that they meet the minimum criteria to be a responsible contractor as defined in Minn. Stat. § 16C.285.	
Authorized Signature of Owner or Officer:	Printed Name:
Title:	Date:
Company Name:	

ATTACHMENT A-2

ADDITIONAL SUBCONTRACTORS LIST

PRIME CONTRACTOR TO SUBMIT AS SUBCONTRACTORS ARE ADDED TO THE PROJECT

STATE PROJECT NUMBER: _____

This form must be submitted to the Project Manager or individual as identified in the solicitation document.

Minn. Stat. § 16C.285, Subd. 5. ... If a prime contractor or any subcontractor retains additional subcontractors on the project after submitting its verification of compliance, the prime contractor or subcontractor shall obtain verifications of compliance from each additional subcontractor with which it has a direct contractual relationship and shall submit a supplemental verification confirming compliance with subdivision 3, clause (7), within 14 days of retaining the additional subcontractors. ...

ADDITIONAL SUBCONTRACTOR NAMES* (Legal name of company as registered with the Secretary of State)	Name of city where company home office is located

*Attach additional sheets as needed for submission of all additional subcontractors.

SUPPLEMENTAL CERTIFICATION FOR ATTACHMENT A-2	
By signing this document I certify that I am an owner or officer of the company, and I certify under oath that: All additional subcontractors listed on Attachment A-2 have verified through a signed statement under oath by an owner or officer that they meet the minimum criteria to be a responsible contractor as defined in Minn. Stat. § 16C.285.	
Authorized Signature of Owner or Officer:	Printed Name:
Title:	Date:
Company Name:	

THIS PAGE INTENTIONALLY
LEFT BLANK

NON-COLLUSION AFFIDAVIT

The following Non-Collusion Affidavit shall be executed by the bidder:

State Project No. _____

Federal Project No. _____

State of Minnesota _____)

) ss

County of _____)

I, _____, do state under penalty of
(name of person signing this affidavit)

perjury under 28 U.S.C. 1746 of the laws of the United States:

(1) that I am the authorized representative of _____

(name of person, partnership or corporation submitting this proposal)

and that I have the authority to make this affidavit for and on behalf of said bidder;

(2) that, in connection with this proposal, the said bidder has not either directly or indirectly entered into any agreement, participated in any collusion or otherwise taken any action in restraint of free competitive bidding;

(3) that, to the best of my knowledge and belief, the contents of this proposal have not been communicated by the bidder or by any of his/her employees or agents to any person who is not an employee or agent of the bidder or of the surety on any bond furnished with the proposal and will not be communicated to any person who is not an employee or agent of the bidder or of said surety prior to the official opening of the proposal, and

(4) that I have fully informed myself regarding the accuracy of the statements made in this affidavit.

Signed: _____
(bidder or his authorized representative)

THIS PAGE INTENTIONALLY
LEFT BLANK

PIPESTONE COUNTY HIGHWAY DEPARTMENT
SCHEDULE OF BID PRICES
FOR
SAP 059-647-001

The Schedule of Bid Prices Sheet(s) has been intentionally left out of the "PDF" print of this proposal.

The Schedule of Bid Prices must be obtained from the Pipestone County Highway Department by submitting your company name, address, phone no., fax no., and email address via email to highway@pcmn.us (PREFERRED) or by calling 507-825-1245.

It is YOUR RESPONSIBILITY to obtain the Schedule of Bid Prices Sheet(s).

Obtaining the Schedule of Bid Prices places you on the plan holders list. You will also receive any addendums that may be issued for this project.

If you are a supplier or subcontractor and would like to be placed on the plan holders list please submit the required information to the email address listed above.

NOTICE TO BIDDERS

Replace this sheet with Schedule of Bid Prices sheet(s) and return the ENTIRE proposal with your bid.

THIS PAGE IS BLANK

12/3/78

12/3/78

THIS PAGE INTENTIONALLY LEFT BLANK

State Aid Project No. SAP 059-647-001

GRAND TOTAL \$ _____

The undersigned hereby acknowledges that all requirements included in the proposal, addenda, amendments, plans, standard specifications, and supplemental specifications are a part of this bid and contract.

Signed: _____

PROPOSAL GUARANTY required by 1208 of the Specifications: "A (certified check) (bond), prepared as required by 1208 of the Specifications and payable to the Pipestone County Treasurer, in an amount equal to at least 5% of the total amount of the bid is submitted herewith as a proposal guaranty.

NON-COLLUSION AFFIDAVIT: A Non-Collusion Affidavit is found in this proposal which must be signed by each bidder.

RECEIPT OF ADDENDA as required by 1210 of the Specifications:

The undersigned hereby acknowledges receipt of and has considered:

Addendum No. ____ Dated _____ Addendum No. ____ Dated _____

Addendum No. ____ Dated _____ Addendum No. ____ Dated _____

Signed: _____

EXECUTION OF PROPOSAL as required by 1206 of the Specifications:

This proposal dated the ____ day of _____, 20

Signed: _____, P.O. Address _____ as an individual.

Signed: _____, P.O. Address _____ as an individual.

doing business under the name and style of

Signed: _____, for _____ a partnership.

NAME

BUSINESS ADDRESS

Signed: _____, for _____ a corporation,

incorporated under the laws of the State of Minnesota

Name of President _____ Business Address _____

Name of Vice-President _____ Business Address _____

Name of Secretary _____ Business Address _____

Name of Treasurer _____ Business Address _____

(NOTE: Signatures shall comply with 1206 of the Specifications.)