


08/05/24 10:19:36AM H:\JBN\6000\6059\Multi-Project RFP\CAD\Plans\Drain 27\001-COVER.dwg

DESIGN DATA				
Traffic	Average Daily			
Current N/A	Pass: N/A	Trucks: N/A	Total: N/A	
Forecast N/A	Pass: N/A	Trucks: N/A	Total: N/A	
Clear Zone Distance: 2 FT		Design Speed: 20 MPH		
Minimum Sight Dist. for Stopping:N/A		Bridges: N/A		
Sight Dist. for No Passing Zone: N/A				
Pavement Design Life: N/A				


DESIGNERS
DEREK KAYSER



STATE COUNTY MAP

NORTH DAKOTA  
DEPARTMENT OF TRANSPORTATION

TMA-TAU-8-984(177)  
SN-25-A0  
CASS COUNTY  
DRAIN 27 TRAIL CROSSING  
TIMBERLINE TO MILWAUKEE TRAIL  
GRADING, SHARED USE PATH, AND BOX CULVERT



STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	23946	1	1

GOVERNING SPECIFICATIONS	Date Published and Adopted by the North Dakota Department of Transportation
Standard Specifications	4/1/2023
Supplemental Specifications	NONE

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
TMA-TAU-8-984(177)	0.160	0.160



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.

APPROVED DATE 8/20/2024

HOUSTON ENGINEERING INC




8/20/2024

APPROVED DATE 8/22/2024


FARGO  
CITY ENGINEER

TABLE OF CONTENTS						STATE	PROJECT NO.	SECTION NO.	SHEET NO.
						ND	TMA-TAU-8-984(177)	2	1
PLAN SECTIONS			LIST OF STANDARD DRAWINGS						
Section	Page(s)	Description	Number	Description					
1	1	Title Sheet	D-260-1	Erosion And Siltation Controls - Silt Fence					
2	1	Table of Contents	D-261-1	Erosion Control - Fiber Roll Placement Details					
4	1	Scope of Work	D-704-9	Construction Sign Details - Terminal And Guide Signs					
6	1 - 2	Notes	D-704-10	Construction Sign Details - Regulatory Signs					
6	3	Environmental Notes	D-704-11, 11A	Construction Sign Details - Warning Signs					
8	1	Quantities	D-704-13	Barricade And Channelizing Device Details					
10	1	Basis of Estimate	D-704-14	Construction Sign Punching And Mounting Details					
11	1	Data Tables	D-704-23	Short Term Urban Detour And Lane Closure On A Divided Highway Layouts					
20	1	General Details							
30	1 - 2	Typical Sections							
40	1 - 2	Removals							
60	1 - 4	Plan & Profile							
75	1 - 2	Wetland Impacts							
76	1	Temporary Erosion Control							
77	1 - 2	Permanent Erosion Control							
80	1 - 2	Layouts							
82	1	Alignment Definition							
85	1	Landscaping							
90	1	Paving Layouts							
100	1 - 2	Work Zone Traffic Control							
170	1 - 3	Box Culverts							
200	1 - 11	Cross Sections							

08/05/24 10:19:48AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\004-SCOPE OF WORK.dwg



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	4	1



LEGEND:  
SIDEWALK CONCRETE 5IN  
(ON 2" BASE)




THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024


Scope of Work

Drain 27 Trail

NOTES

- 100-P01 COORDINATION OF PROJECTS: Other projects may be under contract in the vicinity of this project during the 2025 construction season.
- 100-P02 PROJECT COMPLETION: Phase and schedule construction activities to meet the following requirements:  
  
Substantial Completion: Complete all work except for clearing and grubbing and turf establishment within 40 calendar days of mobilizing to the site and no later than September 12, 2025.  
  
Final Completion: Complete all work by October 15, 2025.
- 100-P03 SITE ACCESS: Access the site only from 25th St S. Close the right southbound lane of 25th St S as necessary per Standard Drawing 704-23. Do not operate equipment on or impact the existing levees adjacent to or within the project limits. It is anticipated concrete may need to be buggied or pumped for the construction of the trail due to the space constraints.  
  
It is anticipated concrete box culverts will be installed as single cell units due to the limited space onsite. It is assumed the box culvert segments will be delivered to the project site via the single lane closure on 25<sup>th</sup> St and carried into position within Drain 27 with construction equipment.  
  
Alternative construction methods are acceptable provided no additional traffic, flood control features, environmental areas, wetlands, other waters, or trees will be impacted during construction. Repair or replace any damage to existing infrastructure that results from construction operations.
- 100-P04 WEEKLY LOOK AHEAD SCHEDULE: Submit a Weekly Look Ahead Schedule at the end of each week or at such other time of the week as determined by the Engineer. Include those work activities that are scheduled to begin or are in progress for the next three weeks on the form provided.  
  
Pay estimates may be withheld if the required schedules are not received. Receipt of a pay estimate does not relieve the Contractor of the requirement to provide the schedules. Include all costs for the Weekly Look Ahead Schedule in the price bid for other items.
- 100-P05 PRECONSTRUCTION MEETING: Organize, schedule, and attend a meeting with private utility companies and subcontractors at least 7 days prior to the start of construction for coordination purposes.

- 105-110 PAVEMENT SWEEPING: Sweep paved areas that were used by construction traffic before opening these areas to public traffic.  
  
Sweep all newly constructed pavement no more than 24 hours before a scheduled final inspection.  
  
Use a vacuum or pick-up type sweeper to perform this work.
- 105-P01 NOISE RESTRICTIONS: Do not perform construction activities or moving of equipment between the hours of 10:00 pm and 7:00 am except for sawing of new concrete. Notify residents within ½ block of the work area by 7:30 pm when sawing is planned to occur during these hours.
- 105-P02 LOCATION OF EXISTING UTILITIES: Existing utilities have been shown for reference. Such utilities have been plotted from record drawings. The location of private utilities shown on the plans are approximate.  
  
All existing utilities may not be shown. The location of existing utilities is not guaranteed. Determine the exact location of, and protection of, the existing utilities.  
  
Before commencing any excavation or construction, determine the location and seek aid in locating all public and private utilities.  
  
Contact and coordinate with utility owners to allow access to their own utilities to perform the relocations and/or inspections. Schedule work accordingly so as not to delay or prevent each utility from maintaining their relocation schedule.  
  
Include all costs to complete this work in the price bid for other items.
- 203-010 SHRINKAGE: 15 percent additional volume is included for shrinkage in earth embankment.
- 203-360 COMPACTION AND DENSITY CONTROL: Compact material as specified in Section 203.04 G.2.b, "ND T 99".  
  
Manipulate embankment material with disking equipment.
- 203-385 AVERAGE HAUL: No average haul has been computed for this project.
- 203-P01 BORROW EXCAVATION: Provide contractor optioned borrow material. Payment for borrow material will be done based on plan quantity. No measurement will be completed. If material underrun or overrun is encountered, no price adjustment will be considered.





NOTES

251-P01 SEEDING CLASS III: Use the following seed mix for all permanent seeding.

Species	Percent by Weight	Purity	Germination
Perennial Ryegrass	40%	90%	85%
Creeping Red Fescue	30%	90%	85%
Annual Ryegrass	15%	90%	85%
Kentucky Bluegrass	15%	90%	85%

Rate of Seeding = 220 Lbs/Acre

Remove all stumps, brush, sticks, roots, stones larger than 1/2 inch in diameter, concrete chunks, rebar, wire or other material that may hinder seeding and maintenance operations. Dispose of any accumulated material at no additional cost to the City/State.

704-P01 TEMPORARY TRAFFIC CONTROL: Utilize pedestrian channelization as shown in Section 100 while work is active. Open the full width of the existing path by moving pedestrian channelization to the edge of the path at the conclusion of each working day. Close the right southbound lane of 25<sup>th</sup> Street S as necessary during construction. Utilize layouts as shown in Standard Drawing 704-23. Remove lane closure at the end of each working day.

750-P01 SIDEWALK CONCRETE: Provide at least two employees with a current ACI concrete flatwork technician or flatwork finisher certification. At least one of those employees must be onsite performing quality control and guidance during all concrete forming, placement of reinforcement steel, dowel bars, and tie bars, pouring, finishing, and curing operations.

More information about the ACI Flatwork Finisher training schedule can be found by going to [www.ndconcrete.com](http://www.ndconcrete.com) or by calling 701-223-2770.

750-P02 SIDEWALK CONCRETE: Provide concrete materials with a maximum water to cementitious ratio of 0.42. Provide a concrete mix with a maximum of 620 lbs total cementitious content including fly ash and slag cement. Provide a concrete mix with at least 20% of the cementitious content, by mass, as fly ash or slag cement.

750-P03 SIDEWALK CONCRETE: Provide ½” thick expansion material. Provide a minimum of ½” diameter reinforcement.

Expansion Joints – Coat the “free” end of the smooth dowel with an approved lubricant and covered with an approved metal or plastic dowel cap or sleeve.

Completely remove concrete to the nearest planned longitudinal and transverse joint if uncontrolled cracking occurs. Remove and replace the concrete sidewalk using a method approved by Engineer at the Contractor’s expense.

Match the existing elevation of all adjoining concrete within +/- 1/8”. Remove and replace any placed concrete not properly matching elevations as deemed by the Engineer at the Contractor’s expense.


970-P01 REPLANT TREES: Replant trees at locations determined by the Engineer in the field. Protect all trees within the work area that are not noted for removal or replanting. Minimize damage to the critical root zone (CRZ). The CRZ is an area defined by the diameter of the tree as measured at a point 4.5 feet above the ground line. For every 1 inch of tree diameter, a 1 foot clear zone must be established to protect the CRZ. Establish and mark out the CRZ areas prior to construction or staging.

Submit a plan outlining tree damage minimization procedures to the engineer for approval 7 days prior to beginning work within the CRZ. Contact the Engineer prior to cutting or damaging any branch or root over 4” diameter. Clean cut exposed roots and backfill as quickly as possible to avoid drying out.

If damage is caused to any existing tree due to failure to adhere to the tree protection requirements, damage will be assessed to determine if the damage can be repaired or if the tree must be removed. Use a certified arborist to complete any action plan to repair damaged trees at no additional cost. If damage is severe and tree removal is necessary, the tree’s appraised value, as determined by the Engineer utilizing the most recent edition of the Guide for Plant Appraisal by the Council of Tree and Landscape Appraisers, will be deducted from the contract.

Complete spading and planting operations under favorable weather conditions between May 1 and June 15 or between September 1 and October 15. Replant all trees following the specifications in Section 7000 of the City of Fargo’s Standard Specifications for Construction and in Section 20 of the plans.

Include all costs to spade, transport, replant, maintain and establish identified trees in the price bid for “Replant Trees”.




STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	6	3

**ENVIRONMENTAL NOTES**

ENVIRONMENTAL NOTES (EN): The North Dakota Department of Transportation has made environmental commitments to secure approval of this project. The following environmental notes are requirements to comply with these commitments:

EN-1 TEMPORARY WETLAND IMPACT: Temporary impact areas within wetlands and or other waters are incorporated into the plans for this project. Remove temporary fill placed and sedimentation in wetlands or other waters. Restore these wetlands to preconstruction contours.

- Permits  
USACE 404 Permit  
NDPDES Permit  
City of Fargo Floodplain Permit



Estimated Quantities

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	8	1

SPEC	CODE	ITEM DESCRIPTION	UNIT	DRAIN 27 TRAIL	TOTAL
103	0100	CONTRACT BOND	L SUM	1	1
201	0330	CLEARING & GRUBBING	L SUM	1	1
203	0103	COMMON EXCAVATION-TYPE C	CY	550	550
203	0109	TOPSOIL	CY	604	604
203	0140	BORROW-EXCAVATION	CY	40	40
210	0050	BOX CULVERT EXCAVATION	EA	1	1
210	0210	FOUNDATION FILL	CY	348	348
210	0405	FOUNDATION PREPARATION-BOX CULVERT	EA	1	1
216	0100	WATER	M GAL	33	33
251	0300	SEEDING CLASS III	ACRE	0.242	0.242
251	2000	TEMPORARY COVER CROP	ACRE	0.444	0.444
253	0201	HYDRAULIC MULCH	ACRE	0.686	0.686
256	0200	RIPRAP GRADE II	CY	654	654
260	0100	SILT FENCE UNSUPPORTED	LF	30	30
260	0101	REMOVE SILT FENCE UNSUPPORTED	LF	30	30
261	0112	FIBER ROLLS 12IN	LF	2394	2394
261	0113	REMOVE FIBER ROLLS 12IN	LF	1182	1182
606	1009	10FT X 9FT PRECAST RCB CULVERT	LF	72	72
606	5009	10FT X 9FT PRECAST RCB END SECTION	EA	4	4
702	0100	MOBILIZATION	L SUM	1	1
704	1000	TRAFFIC CONTROL SIGNS	UNIT	276	276
704	1052	TYPE III BARRICADE	EA	2	2
704	1056	PEDESTRIAN CHANNELIZATION	LF	270	270
704	1060	DELINEATOR DRUMS	EA	11	11
704	1067	TUBULAR MARKERS	EA	11	11
704	1086	SEQUENCING ARROW PANEL-TYPE B	EA	1	1
709	0100	GEOSYNTHETIC MATERIAL TYPE G	SY	349	349
709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	981	981
750	0125	SIDEWALK CONCRETE 5IN	SY	1065	1065
970	0075	WOOD MULCH	SF	1392	1392
970	0300	BENCH	EA	1	1
970	1000	TREES	EA	6	6
970	1030	PERENNIALS GROUP A	EA	59	59

**BASIS OF ESTIMATE**


Sidewalk Concrete 5IN					
Station Range	Length LF	Width LF	Surface Area SF	Depth IN	Area SY
Sta 101+10.28 to Sta 101+30.20	-	-	91.55	5	10
Sta 101+41.93 to Sta 101+50.30	-	-	60.30	5	7
Sta 900+36.18 to Sta 900+59.73	-	-	112.12	5	12
Sta 900+59.73 to Sta 901+05.61	45.88	10.00	-	5	51
Sta 901+05.61 to Sta 901+37.11	-	-	91.32	5	10
Sta 101+30.20 to Sta 109+40.35	810.15	10.00	-	5	900
Sta 1000+00.00 to Sta 1000+28.58	-	-	92.91	5	10
Sta 1000+28.58 to Sta 1000+69.82	41.24	10.00	-	5	46
Sta 1000+69.82 to Sta 1000+87.56	-	-	89.14	5	10
Sta 109+40.35 to Sta 109+56.35	-	-	81.07	5	9
Total					1,065

Aggregate Base Course CL 5*					
Station Range	Length LF	Width LF	Surface Area SF	Depth IN	Volume CY
Sta 101+10.28 to Sta 101+30.20	-	-	101.48	2	0.63
Sta 101+41.93 to Sta 101+50.30	-	-	72.12	2	0.45
Sta 900+36.18 to Sta 900+59.73	-	-	123.86	2	0.76
Sta 900+59.73 to Sta 901+05.61	45.88	11.00	-	2	3.12
Sta 901+05.61 to Sta 901+37.11	-	-	89.64	2	0.55
Sta 101+30.20 to Sta 109+40.35	810.15	11.00	-	2	55.01
Sta 1000+00.00 to Sta 1000+28.58	-	-	91.24	2	0.56
Sta 1000+28.58 to Sta 1000+69.82	41.24	11.00	-	2	2.80
Sta 1000+69.82 to Sta 1000+87.56	-	-	97.98	2	0.60
Sta 109+40.35 to Sta 109+56.35	-	-	89.06	2	0.55
Total					65.03

\*Included in price bid for Sidewalk Concrete 5IN.

**Water**  
25 MGal/Mile for Dust Palliative  
20 Gal/Ton for Aggregates  
10 Gal/CY for Embankment

**Conversions**  
Aggregate Base Course CL 5 – 1.875 TON/CY





08/16/24 08:17:27AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\011-DATA TABLES.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	11	1

Drain 27 Trail								
Station	Distance (LF)	Excavation			Embankment			Mass Ordinate (CY)
		Area (SF)	Volume (CY)	Accumulated Volume (CY)	Area (SF)	Adjusted Volume (CY)*	Accumulated Volume (CY)	
101+10.28		1.24			0.00			
101+50.00	39.72	5.29	5	5	9.15	8	8	-3
102+00.00	50.00	8.86	13	18	19.57	31	39	-21
102+50.00	50.00	4.97	13	31	19.37	41	80	-49
103+00.00	50.00	104.68	102	133	381.10	426	506	-373
103+50.00	50.00	10.54	107	240	0.04	406	912	-672
104+00.00	50.00	1.44	11	251	1.19	1	913	-662
104+50.00	50.00	3.64	5	256	3.19	5	918	-662
105+00.00	50.00	1.61	5	261	0.00	3	921	-660
105+50.00	50.00	2.80	4	265	0.00	0	921	-656
106+00.00	50.00	3.27	6	271	0.63	1	922	-651
106+50.00	50.00	0.87	4	275	0.00	1	923	-648
107+00.00	50.00	0.61	1	276	0.52	1	924	-648
107+50.00	50.00	0.60	1	277	0.00	1	925	-648
108+00.00	50.00	0.18	1	278	0.30	0	925	-647
108+50.00	50.00	3.94	4	282	0.00	0	925	-643
109+00.00	50.00	1.14	5	287	5.67	6	931	-644
109+50.00	50.00	3.86	5	292	0.00	6	937	-645
109+56.35	6.35	2.25	1	293	0.00	0	937	-644
Box Culverts				293		-384	553	-260
Total				293	Total			553

Drain 27 Trail East								
Station	Distance (LF)	Excavation			Embankment			Mass Ordinate (CY)
		Area (SF)	Volume (CY)	Accumulated Volume (CY)	Area (SF)	Adjusted Volume (CY)*	Accumulated Volume (CY)	
1000+00.00		0.73			0.53			
1000+50.00	50.00	2.53	3	3	14.26	16	16	-13
1000+87.56	37.56	0.19	2	5	0.03	11	27	-22
Total				5	Total			27

Drain 27								
Station	Distance (LF)	Excavation			Embankment			Mass Ordinate (CY)
		Area (SF)	Volume (CY)	Accumulated Volume (CY)	Area (SF)	Adjusted Volume (CY)*	Accumulated Volume (CY)	
0+00.00		74.65			0.00			
0+29.28	29.28	212.10	155	155	0.00	0	0	155
Box Culverts Gap								
1+01.26		200.49		155	0.00		0	155
1+20.22	18.96	52.34	89	244	0.00	0	0	244
Total				244	Total			0

Drain 27 Trail West								
Station	Distance (LF)	Excavation			Embankment			Mass Ordinate (CY)
		Area (SF)	Volume (CY)	Accumulated Volume (CY)	Area (SF)	Adjusted Volume (CY)*	Accumulated Volume (CY)	
900+36.18		0.04			0.00			
900+50.00	13.82	0.16	0	0	0.04	0	0	0
901+00.00	50.00	3.18	3	3	4.92	5	5	-2
901+37.09	37.09	3.88	5	8	1.05	5	10	-2
Total				8	Total			10

Earthwork Summary							
Location	Excavation (CY)	Embankment (CY)	Common Excavation - Type C (CY) Pay Item	Borrow Excavation (CY) Pay Item	Topsoil Stripping (CY) Pay Item	Topsoil Placement (CY)	Topsoil Waste (CY)
Drain 27 Trail	550	590	550	40	604	348	256

Topsoil Stripping based on 6" depth.  
Topsoil Placement based on 10.7" depth.  
Include all costs to strip and place topsoil and waste excess topsoil in the price bid for "Topsoil".



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




8/16/2024

Data Tables


Drain 27 Trail

08/05/24 10:19:58AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\020-GENERAL DETAILS.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	20	1




25% FLARES




4.5' REINFORCEMENT

SIDEWALK WIDTH	PANELS (L'xW')
6'	5'x6'
8'	4.5'x4'
10'	5'x5'


JOINT DIMENSION




10' REINFORCEMENT




SIDEWALK CROSS SECTION



SIDEWALK REINFORCEMENT



CONCRETE APRON FOR SIDEWALK/BIKETRAIL



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

General Details

Drain 27 Trail




08/05/24 10:20:02AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\020-GENERAL DETAILS.dwg


	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	20	3

NOTES:

1. REFER TO CITY OF FARGO SECTION 7000 SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. PLANT FIRST FLAIR ROOT 1" to 2" ABOVE SURROUNDING GRADE.
3. TREES LOCATED IN LAWN TO HAVE 4" DEPTH BY 6' DIAMETER WOOD MULCH, UNLESS OTHERWISE NOTED.
4. KEEP MULCH 6" AWAY FROM TRUNK.
5. REFER TO 'TREE ROOT BALL PREPARATION' FOR ADDITIONAL INFORMATION.



TREE PLANTING DETAIL  
NOT TO SCALE



ON SLOPE TREE PLANTING DETAIL  
NOT TO SCALE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024


General Details

Drain 27 Trail




08/12/24 11:46:53AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\030-TYPICAL SECTIONS.dwg


STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	30	1



TYPICAL PROPOSED SECTION  
SHARED USE PATH NOT TO SCALE  
STA 101+10.28 TO STA 102+50.00  
STA 900+36.18 TO STA 901+37.11



TYPICAL PROPOSED SECTION  
SHARED USE PATH NOT TO SCALE  
STA 102+50.00 TO STA 102+70.00  
STA 103+20.00 TO STA 103+50.00




TYPICAL PROPOSED SECTION  
SHARED USE PATH NOT TO SCALE  
STA 103+50.00 TO STA 109+56.35  
STA 1000+00.00 TO STA 1000+87.56

**THE CITY OF**  
**Fargo**  
FAR MORE

**Engineering Inc.**  
Proj. No. 6059-0205  
Houston  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




8/12/2024


Typical Sections

Drain 27 Trail

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	30	2



TYPICAL PROPOSED SECTION  
SHARED USE PATH NOT TO SCALE  
STA 102+70.00 TO STA 102+80.00  
STA 103+10.00 TO STA 103+20.00



TYPICAL PROPOSED SECTION  
PATH DRAIN CROSSING NOT TO SCALE  
STA 102+80.00 TO STA 103+10.00



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Typical Sections

Drain 27 Trail



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	40	1

SPEC CODE	BID ITEM	QTY	UNIT
201 0330	CLEARING & GRUBBING STA 101+00 TO STA 106+00	1	L SUM

LEGEND:  
X CLEARING & GRUBBING

Tree Removal		
Tree Size	Station	Offset
6"	101+55	26' Rt
6"	103+23	57' Rt
24"	103+20	61' Rt
6"	103+94	0' Lt
12"	104+27	22' Rt
3"	104+34	2' Lt
6"	104+56	11' Rt
12"	104+64	10' Lt
3"	104+86	3' Lt
3"	104+85	11' Rt
3"	104+92	2' Rt
3"	105+09	9' Rt

NOTES:  
1. INCLUDE ALL COSTS FOR THE REMOVAL OF TREES, REGARDLESS OF SIZE, IN THE PRICE BID FOR "CLEARING & GRUBBING".

08/05/24 10:20:22AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\040-REMOVALS 1.dwg



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Removals

Drain 27 Trail



STATE

PROJECT NO.

SECTION NO.

SHEET NO.

ND

TMA-TAU-8-984(177)

40

2

LEGEND:



CLEARING & GRUBBING


NOTES:

1. INCLUDE ALL COSTS FOR THE REMOVAL OF TREES, REGARDLESS OF SIZE, IN THE PRICE BID FOR "CLEARING & GRUBBING".



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065


ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Removals

Drain 27 Trail




Drain 27

Tree Removal		
Tree Size	Station	Offset
10"	101+72	5' Lt
3"	101+83	7' Lt
12"	101+83	5' Lt
12"	101+94	5' Lt
18"	101+91	18' Rt
10"	101+95	5' Rt
12"	101+96	3' Rt
12"	101+97	1' Lt
6"	102+02	15' Lt
8"	102+07	15' Lt
12"	102+05	10' Rt
10"	102+13	2' Rt
3"	102+19	13' Lt
12"	102+22	18' Rt
12"	102+24	18' Rt
8"	102+33	24' Rt
10"	102+34	28' Rt
18"	102+37	16' Rt
12"	102+41	2' Rt
6"	102+47	1' Rt
10"	102+41	3' Lt
12"	102+52	5' Lt
8"	102+51	16' Lt
18"	102+61	33' Lt


Tree Removal		
Tree Size	Station	Offset
18"	102+68	27' Lt
6"	103+20	50' Lt
18"	103+36	20' Lt
6"	103+39	18' Lt
6"	103+37	4' Lt
6"	103+41	6' Lt
3"	103+42	1' Rt
10"	103+43	7' Rt
6"	103+36	15' Rt
3"	103+41	16' Rt
12"	103+36	17' Rt
12"	103+38	20' Rt
3"	103+41	21' Rt
3"	103+42	23' Rt
6"	103+40	23' Rt
6"	103+40	26' Rt
6"	103+42	32' Rt
12"	103+29	23' Rt
6"	103+22	25' Rt
12"	103+22	27' Rt
18"	103+38	39' Rt
12"	103+54	11' Rt
12"	103+52	2' Rt
3"	103+66	3' Rt



08/05/24 10:20:47AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\060-P & P 1.dwg



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	60	1



- LEGEND:
- SIDEWALK CONCRETE 5IN
  - RIPRAP GRADE III  
SEE SECTION 170 FOR DIMENSIONS
  - LANDING: 1.5% PREFERRED SLOPE  
(2% MAXIMUM) ALL DIRECTIONS



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)





8/12/2024

Plan & Profile

Drain 27 Trail

08/05/24 10:20:50AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\060-P & P 1.dwg



STATE

PROJECT NO.

SECTION NO.


SHEET NO.

ND



TMA-TAU-8-984(177)

60

2



LEGEND:

-  SIDEWALK CONCRETE 5IN
-  LANDING: 1.5% PREFERRED SLOPE (2% MAXIMUM) ALL DIRECTIONS



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Plan & Profile

Drain 27 Trail









08/21/24 04:09:05PM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\075-WETLAND IMPACTS.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	75	1

Wetland Impact Table																			
Wetland Number	Location	Wetland Feature	USACE Jurisdictional Wetlands¹	Wetland Impacts Acre(s)		USFWS Easement Impacts Acre(s)		Wetland Mitigation											
								Mitigation Required			USACE/11990 Bank		11990 Bank		USFWS Bank		Onsite		
				Temp.	Perm.	Temp.	Perm.	EO 11990	USACE	USFWS	Location	Acre(s)	Location	Acre(s)	Location	Acre(s)	Mitigation Location; Ratio	Acre(s)	Constructed Site #
1a	Sec. 35, T139N, R49W	Depression	Y	0.000	0.000	0.000	0.000	N	N	N									
				0.000	0.000	0.000	0.000												

Other Waters Impact Table															
Other Waters											Other Water Mitigation				
Number	Location	Type	Size		Feature	USACE Jurisdictional <sup>1</sup>	Impacts to Other Waters				Mitigation Required			USACE Mitigation Bank	
			Acre(s)	Linear Feet			Acre(s)		Linear Feet		EO 11990	USACE	USFWS	Location	Acre(s)
OW 1b	Sec. 35, T139N, R49W	Stream	0.937	1862.86	Natural	Y	0.011	0.043	30.93	102.09	Y	Y	N	Ducks Unlimited; 2:1	0.086
OW 1c	Sec. 35, T139N, R49W	Modified Stream	0.234	564.75	Natural	Y	0.000	0.000	0.00	0.00	N	N	N	N/A	N/A
		Totals	1.171	2427.61			0.011	0.043	25.88	102.09					0.043

<sup>1</sup> A wetland Jurisdictional Determination has not been issued by the USACE. All wetlands are assumed to be Jurisdictional.

Impact Summary Table			
Permanent Impact Summary		Temporary Impacts and additional information	
Wetland Type	Total (Acres)	Wetland Type	Total (Acres / Lf)
Natural/JD	0.000	Temporary JD	0.000
Natural/Non-JD	0.000	Non-JD Temporary	0.000
Artificial/JD	0.000	Permanent JD > 0.10	0.000
Artificial /Non-JD	0.000	Permanent OW	0.043 / 102.09
Total	0.000	Temporary OW	0.011 / 30.93

Mitigation Summary Table					
	Location	Onsite Acre(s)	11990 Bank Acre(s)	USACE/11990 Bank Acre(s)	USFWS Bank Acre(s)
USACE Only	Ducks Unlimited			0.086	
EO 11990 Only					
USACE/11990					
USFWS					
	Total			0.086	




THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




REGISTERED PROFESSIONAL ENGINEER  
ADAM M. RUPP  
PE-10407  
DATE  
NORTH DAKOTA

8/21/2024


Wetland Impacts

Drain 27 Trail

08/21/24 04:09:10PM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\075-WETLAND IMPACTS.dwg



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	75	2



- LEGEND:**
- FLOW DIRECTION
  - OTHER WATERS TEMPORARY IMPACT
  - OTHER WATERS PERMANENT IMPACT
  - SIDEWALK CONCRETE 5IN

THE CITY OF  
**Fargo**  
FAR MORE

Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/21/2024

Wetland Impacts


Drain 27 Trail



08/05/24 10:55:16AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\076-TEMP EROSION CONTROL.dwg



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	76	1



SPEC CODE	BID ITEM	QTY	UNIT
251 2000	TEMPORARY COVER CROP STA 101+10 TO STA 109+56	0.444	ACRE
253 0201	HYDRAULIC MULCH STA 101+10 TO STA 109+56	0.444	ACRE
260 0100	SILT FENCE UNSUPPORTED STA 102+80 TO STA 103+10	30	LF
260 0101	REMOVE SILT FENCE UNSUPPORTED STA 102+80 TO STA 103+10	30	LF
261 0112	FIBER ROLLS 12IN STA 101+10 TO STA 109+56	1182	LF
261 0113	REMOVE FIBER ROLLS 12IN STA 101+10 TO STA 109+56	1182	LF

- LEGEND:
- FLOW DIRECTION
  - TEMPORARY COVER CROP  
HYDRAULIC MULCH
  - SILT FENCE UNSUPPORTED
  - FIBER ROLLS 12IN
  - SIDEWALK CONCRETE 5IN

THE CITY OF  
**Fargo**  
FAR MORE

Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



Temporary Erosion Control


Drain 27 Trail



08/12/24 11:47:01AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\077-PERM EROSION CONTROL 1.dwg



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	77	1



SPEC CODE	BID ITEM	QTY	UNIT
251 0300	SEEDING CLASS III STA 101+10 TO STA 109+56	0.242	ACRE
253 0201	HYDRAULIC MULCH STA 101+10 TO STA 109+56	0.242	ACRE
256 0200	RIPRAP GRADE II STA 101+10 TO STA 103+50	654	CY
261 0112	FIBER ROLLS 12IN STA 101+10 TO STA 109+56	1212	LF
709 0155	GEOSYNTHETIC MATERIAL TYPE RR STA 101+10 TO STA 103+50	981	SY

- LEGEND:
- FLOW DIRECTION
  - SEEDING CLASS III  
HYDRAULIC MULCH
  - RIPRAP GRADE II
  - FIBER ROLLS 12IN
  - SIDEWALK CONCRETE 5IN



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




Permanent Erosion Control

Drain 27 Trail



08/12/24 11:47:08AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\077-PERM EROSION CONTROL 2.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	77	2




- LEGEND:**
- SEEDING CLASS III  
HYDRAULIC MULCH
  - RIPRAP GRADE II
  - SIDEWALK CONCRETE 5IN



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




8/12/2024

Permanent Erosion Control

Drain 27 Trail




08/05/24 10:21:50AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\080-LAYOUTS 1.dwg



Point Table					
Point #	Description	Northing	Easting	Station	Offset
700	SW-PI	439167.7583	2888984.4295	101+10.28	1.00
701	SW-PI	439168.2607	2888985.2942	101+10.28	0.00
702	SW-PI	439145.4452	2888990.4301	101+30.20	10.00
703	SW-PI	439123.2660	2889030.3822	101+71.02	10.00
704	SW-PI	439088.7569	2888992.5719	900+59.73	10.00
705	SW-PI	439062.0715	2888991.8062	900+36.18	1.00
706	SW-PI	439061.8620	2888992.7840	900+36.18	0.00

Point Table					
Point #	Description	Northing	Easting	Station	Offset
800	SW-PI	438943.6557	2889733.6664	109+56.35	0.00
801	SW-PI	438942.5141	2889734.6394	109+56.35	1.50
802	SW-PI	438925.7101	2889726.2462	109+40.35	10.00
803	SW-PI	438909.2031	2889688.6662	109+02.30	10.00
804	SW-PI	438881.4101	2889725.5088	1000+69.82	10.00
805	SW-PI	438860.1027	2889726.5132	1000+87.56	0.00
806	SW-PI	438860.5070	2889727.4278	1000+87.56	1.00



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	80	1



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065



ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



LAYOUTS

Drain 27 Trail

08/05/24 10:21:58AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\080-LAYOUTS 2.dwg



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	80	2



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)





8/12/2024

Layouts

Drain 27 Trail

08/05/24 10:22:01AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\082-ALIGNMENT DEFINITION.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	82	1



Line Table: Alignments – Drain 27					
Number	PI Station	Northing	Easting	Distance	Direction
L7	0+00.00	439062.3786	2889155.0118	29.28	N02°35'23.23"E
L8	0+29.28	439091.6299	2889156.3349	72.00	N00°10'20.26"E
L9	1+01.28	439163.6296	2889156.5514	18.95	N06°57'36.08"E

Line Table: Alignments – Drain 27 Trail West					
Number	PI Station	Northing	Easting	Distance	Direction
L5	900+00.00	439025.8473	2888989.7110	25.00	N03°33'32.85"E
C4	900+94.51	439120.1713	2888995.5778	112.11	N89°12'16.97"E

Line Table: Alignments – Drain 27 Trail					
Number	PI Station	Northing	Easting	Distance	Direction
L1	100+00.00	439269.9930	2888942.8043	100.00	S22°18'10.84"E
C1	101+51.06	439130.2354	2889000.1317	89.66	N89°12'16.97"E
L2	101+89.66	439130.9441	2889051.1850	274.40	N89°12'16.97"E
C2	105+07.82	439135.3602	2889369.3165	83.29	S47°24'37.48"E
L3	105+47.35	439105.7476	2889401.5317	235.11	S47°24'37.48"E
C3	108+94.86	438870.5733	2889657.3752	180.65	N46°20'01.87"E
L4	109+63.11	438948.1829	2889738.6851	36.89	N46°20'01.87"E

Line Table: Alignments – Drain 27 Trail East					
Number	PI Station	Northing	Easting	Distance	Direction
C5	1000+49.37	438905.4732	2889706.4585	87.32	S23°50'47.12"E
L6	1000+87.32	438860.3190	2889726.4176	62.68	S23°50'47.12"E



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)





8/12/2024

Alignment Definition

Drain 27 Trail






PERENNIAL PLANTING  
NO SCALE

SPEC CODE	BID ITEM	QTY	UNIT
970 0075	WOOD MULCH		
	STA 101+30 TO STA 101+71	772	SF
	STA 109+02 TO STA 109+40	620	SF
	TOTAL	1392	SF
970 0300	BENCH		
	STA 101+48	1	EA
970 1000	TREES		
	STA 101+30 TO STA 101+71	3	EA
	STA 109+02 TO STA 109+40	3	EA
	TOTAL	6	EA
970 1030	PERENNIALS GROUP A		
	STA 101+30 TO STA 101+71	33	EA
	STA 109+02 TO STA 109+40	26	EA
	TOTAL	59	EA

PLANT SCHEDULE

<u>TREES</u>	<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>	<u>SIZE</u>	<u>QTY</u>	<u>REMARKS</u>	
UP	Ulmus americana 'Princeton'	Princeton American Elm	2.5" Cal.	6		
<u>PERENNIALS</u>	<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>	<u>SIZE</u>	<u>QTY</u>	<u>REMARKS</u>	
CK	Calamagrostis x acutiflora 'Karl Foerster'	Karl Foerster Feather Reed Grass	3 gal.	25		
SH	Sporobolus heterolepis	Prairie Dropseed	3 gal.	34		
<u>GROUND COVERS</u>	<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>	<u>SIZE</u>	<u>SPACING</u>	<u>QTY</u>	<u>REMARKS</u>
	MULCH	SHREDDED HARDWOOD	MULCH		1,393 sf	



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)






8/12/2024



Landscaping

Drain 27 Trail

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	TMA-TAU-8-984(177)	90	1


SPEC	CODE	BID ITEM	QTY	UNIT
750	0125	SIDEWALK CONCRETE 5IN		
		STA 101+10 TO STA 106+00	612	SY
		STA 106+00 TO STA 109+56	453	SY
		TOTAL	1065	SY

- LEGEND:
-  SIDEWALK CONCRETE 5IN
  -  CONTRACTION JOINT
  -  EXPANSION JOINT



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Paving Layouts

Drain 27 Trail

08/05/24 10:22:18AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drawn 27\090-PAVING LAYOUTS.dwg






08/05/24 10:22:27AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\100-TRAFFIC CONTROL.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	100	2

LEGEND:

- PEDESTRIAN CHANNELIZATION
- WORK ZONE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




8/12/2024

Work Zone Traffic Control


Drain 27 Trail

08/12/24 11:45:53AM H:\JBN\6000\6059 Multi-Project RFP\CAD\Plans\Drain 27\170\_BoxCulvert\_Layout.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	170	1



PLAN




ELEVATION AT  $\bar{\ell}$  BARREL

For a single barrel box culvert with 9" thick roof, 10" floor and 8" walls,the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (SINGLE)		FACTORED DESIGN SHEARS (SINGLE)	
WALL MOMENT	-9,380 FT-LBS	WALL SHEAR	3,460 LBS
ROOF MOMENTS		ROOF SHEARS	
CORNER	-3,060 FT-LBS	CORNER	10,490 LBS
BOTTOM	21,960 FT-LBS	FLOOR SHEARS	
		CORNER	9,040 LBS
FLOOR MOMENTS			
CORNER	-2,270 FT-LBS		
TOP	21,960 FT-LBS		

For a double barrel box culvert with 9" thick roof, 10" floor and 8" walls,the following total factored moments and shears would result from the application of the required loads:

FACTORED DESIGN MOMENTS (DOUBLE)		FACTORED DESIGN SHEARS (DOUBLE)	
WALL MOMENT	-6,190 FT-LBS	WALL SHEAR	3,610 LBS
ROOF MOMENTS		ROOF SHEARS	
CORNER	-2,170 FT-LBS	CORNER	9,310 LBS
BOTTOM	16,120 FT-LBS	WALL	12,000 LBS
TOP	-14,340 FT-LBS	FLOOR SHEARS	
		CORNER	6,110 LBS
FLOOR MOMENTS		WALL	9,960 LBS
CORNER	-2,290 FT-LBS		
TOP	10,000 FT-LBS		
BOTTOM	-14,530 FT-LBS		



END VIEW

DESIGN LOADING:

HL-93 Live Load  
Maximum Fill Height = 6'-0"  
Minimum Fill Height = 2'-0"

DESIGN DATA:

Barrel Inside Width = 10'-0"  
Barrel Inside Height = 9'-0"  
Barrel Length = 36'-0"  
Skew Angle = 0°

HYDRAULIC DATA:

Drainage Area	25.7	sq mi
Stream Gradient	0.0009	ft/ft
Design Frequency	10	yr
Design Discharge	800	cfs
Design Headwater Stage	895.85	ft
Design Tailwater Stage	895.31	ft
Velocity Through Culvert	3.6	fps
100-Year Frequency Discharge*	N/A	cfs
100-Year Frequency Headwater	906.00	ft
Overtopping Stage	899.10	ft
Overtopping Discharge	1450	cfs

\*100-Year Frequency Is Controlled By Backwater Effects From The Red River



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)




8/12/2024

Box Culvert Layout

Drain 27 Trail

08/12/24 11:46:20AM H:\JBN\6000\6059\6059 Multi-Project RFP\CAD\Plans\Drain 27\170\_BoxCulvert\_Layout.dwg

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	170	2



ELEVATION AT ̢ BARREL

NOTES:

PLACE A 1'-0" MINIMUM DEPTH OF FOUNDATION FILL AND BEDDING UNDER THE FLOOR. PROVIDE BEDDING IN ACCORDANCE WITH SECTION 606.E.1. REMOVE AND REPLACE ALL UNSOUND MATERIAL UNDER THE BOX WITH FOUNDATION FILL. THE ENGINEER WILL DETERMINE THE DEPTH REQUIRED.

PLACE ALL BEDDING PRIOR TO PLACING BOX CULVERT SECTIONS.

EXTEND GEOSYNTHETIC MATERIAL AND FOUNDATION FILL TO THE END OF THE APRON.


CONTRACTOR IS TO EXCAVATE TO A SUITABLE SUBGRADE AS DETERMINED BY THE ENGINEER AND BACKFILL WITH FOUNDATION FILL AS NEEDED. MUCK DEPTH IS ANTICIPATED TO BE APPROXIMATELY 2.5' BELOW EXISTING CHANNEL BOTTOM. ADDITIONAL SUBGRADE EXCAVATION BELOW THE LIMITS SHOWN WILL BE CONSIDERED INCIDENTAL TO BOX CULVERT INSTALLATION.

NOTES:

THE INTENT OF THIS DETAIL IS TO SHOW ONLY THE PLACEMENT OF THE CONTROLLED DENSITY BACKFILL BETWEEN ADJACENT BARRELS. THE REPRESENTATION OF THE SIZE OF BARRELS IS ARBITRARY.

EMBED THE # 4 OR 6" INTO THE SIDE OF ONE OF THE BOX CULVERT END SECTIONS MAINTAINING A 3" MINIMUM CLEARANCE FROM THE OTHER BOX CULVERT. SPACING MEASURED 1'-0" FROM THE BOTTOM OF THE BOX AND SPACED AT 1'-0" UP THE FRONT FACE.

INSTALL THE # 4 BARS ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS, WITH A HIGH STRENGTH ADHESIVE SPECIFICALLY INTENDED FOR CONCRETE ANCHORAGE AND THAT MEETS THE REQUIREMENTS OF SECTION 806.02.



CONTROLLED DENSITY BACKFILL DETAIL

BOX CULVERT BID ITEM

SPEC	ITEM DESCRIPTION	UNIT	QUANTITY
210	BOX CULVERT EXCAVATION	EA	1
210	FOUNDATION FILL	CY	348
210	FOUNDATION PREPARATION-BOX CULVERT	EA	1
256	RIPRAP GRADE II	CY	654
606	10FT X 9FT PRECAST RCB CULVERT	LF	72
606	10FT X 9FT PRECAST RCB END SECTION	EA	4
709	GEOSYNTHETIC MATERIAL TYPE G	SY	349
709	GEOSYNTHETIC MATERIAL TYPE RR	SY	981



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Box Culvert Details

Drain 27 Trail



08/12/24 11:46:32AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\170\_BoxCulvert\_Layout.dwg

NOTES

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	170	3

- 100 SCOPE OF WORK: Work at this site consists of installing two lines of 10' x 9' x 36'-0" precast concrete box culverts.
- 210 ORDINARY BACKFILL: Compact material as specified in Section 203.04 E.2.a, "ND T 180."
- 606 JOINTS: Provide joints in accordance with Section 606.E.3, with the exception that a 12" minimum width waterproof membrane is allowable around the exterior surfaces of the box culvert walls and roof
- 606 PRECAST SECTION: Tie the barrel sections together with 1"Ø tie bolts as shown on Standard Drawing D-714-22. Place two ties per exterior wall joint, located at third points of the wall clear height.

Payment for "10Ft X 9Ft Precast RCB End Section" includes the apron, cutoff wall, parapet and wingwalls. Attach the apron to the last barrel section, the wingwalls and the cutoff wall. Attach the wingwalls to the last barrel section. Provide a welded tie type system for the connections of the apron to the box and wingwalls. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates or other approved method so the inside corner surface is smooth.

Use ASTM A36 steel for bolts, plates, angles, and studs. Use heavy hex nuts meeting the requirements of ASTM A563 and washers meeting ASTM F436, Type 1. Provide welded pipe sleeves meeting the requirements of ASTM A53, Grade B. Galvanize hardware and structural steel according to Section 854.

Welders are to meet the requirements of Section 105.06 D. Galvanize field welds according to Section 854.02.

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive ¾" diameter reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for ½" diameter reinforcing bars to attach the parapet. Cast parapet against the section. Install the bars according to the manufacturer's recommendations, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section

Provide a distance of 1'-0" between separate precast units. Fill this gap with a controlled density backfill. Use a controlled density backfill consisting of cement, water, pozzolanic materials, and fillers. Use a material that is fluid on placement to flow around and fill voids in the backfill area. Use a material that is able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.

MIX DESIGNS

Mix Design 1		Mix Design 2 (No Fly Ash)	
Cement	100 LBS	Cement	165 LBS
Fly Ash	300 LBS	Fly Ash	NA
Fine Aggregate	2600 LBS	Fine Aggregate	2600 LBS
Water	70 GALS	Water	50 GALS

For the 12" cap, use a weatherproof and freeze/thaw resistant, non-shrink cement grout material such as Sikagrout 212, BASF Masterflow 928, Euclid NS grout, or an approved equal

which complies with ASTM C1107.

Include the controlled density backfill and materials used for the 12" cap in the price bid for each specific culvert section, 10ft x 9ft precast RCB culvert.



THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



8/12/2024

Box Culvert Notes

Drain 27 Trail

08/05/24 10:22:42AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail

STATE

PROJECT NO.

SECTION NO.




SHEET NO.

ND

TMA-TAU-8-984(177)

200

1



THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail



08/05/24 10:22:43AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail

STATE

PROJECT NO.

SECTION NO.




SHEET NO.

ND

TMA-TAU-8-984(177)

200

3



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail



08/05/24 10:22:43AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drawn 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail

STATE

PROJECT NO.

SECTION NO.




SHEET NO.

ND

TMA-TAU-8-984(177)

200

4



THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail

08/05/24 10:22:43AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail

STATE

PROJECT NO.

SECTION NO.




SHEET NO.

ND

TMA-TAU-8-984(177)

200

5



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail

08/05/24 10:22:44AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail

STATE

PROJECT NO.

SECTION NO.




SHEET NO.

ND

TMA-TAU-8-984(177)

200

6



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail








08/05/24 10:22:45AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drawn 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail West

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	200	8





THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)



Cross Sections

Drain 27 Trail

08/05/24 10:22:45AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail West

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	200	9





THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail

08/05/24 10:22:45AM H:\JBN\6000\6059\6059-0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail East

STATE

PROJECT NO.

SECTION NO.




SHEET NO.

ND

TMA-TAU-8-984(177)

200

10



Proj. No. 6059-0205  
Houston  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)


Cross Sections

Drain 27 Trail

08/05/24 10:22:45AM H:\JBN\6000\6059\6059\_0205 Multi-Project RFP\CAD\Plans\Drain 27\200-CROSS SECTIONS.dwg

ALIGNMENT: Drain 27 Trail East

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TMA-TAU-8-984(177)	200	11





THE CITY OF  
**Fargo**  
FAR MORE



Proj. No. 6059-0205  
**Houston**  
Engineering Inc.  
Ph: 701.237.5065

ALL ELEVATIONS ARE BASED ON  
THE U.S.G.S. VERTICAL DATUM OF 1988.  
(UNLESS NOTED OTHERWISE)

Cross Sections

Drain 27 Trail