



CONTRACTS AND SPECIFICATIONS BUREAU Proposal

Proposal ID: 55-0183-116

Letting Date: May 20, 2025

Call Order: 153

Proposal Work Type: HMA RESURFACING

DBE Goal: 2.0%

Contracting Authority: IOWA DEPARTMENT OF TRANSPORTATION

Proposal Guaranty: \$500,000.00

This proposal includes the following project(s):

Project Number: NHSX-018-3(116)--3H-55

County: KOSSUTH

Project Work Type: HMA RESURFACING

Route: U.S. 18

Location: ECL Algona to 0.8 mi E of Co Rd P60

Road System: PRIMARY ROAD (on NHS)

Federal Aid - Wages: Federal Aid - Predetermined Wages are in Effect



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Contract Time

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

Site ID	Site Details			Liquidated Damages
00	Late Start Date	08/04/2025	160 WORK DAYS	\$2,000.00
	Overall Site			
01	No Start Date Specified		15 WORK DAYS	\$2,000.00
	Includes all work in phase 1.			
02	No Start Date Specified		40 WORK DAYS	\$2,000.00
	Included all work in phase 2. See details below.			

(*) - Indicates Cost Plus Time Site. See Schedule of Items for Cost Per Unit



Contracts and Specifications Bureau

4/8/2025 12:30 PM

Notes

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

Notes :

*** Work Restrictions ***

Phase 3 may begin in 2025.

*** Site 02***

Site 02 includes all work in phase 2. Must be completed in 2026.



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

Note	Description
001.2023	*** STANDARD SPECIFICATIONS -- SERIES 2023 *** The Iowa Department of Transportation STANDARD SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, SERIES 2023, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications AND Special Provisions shall apply to construction work on this contract.
005.23004.01	*** REVISIONS TO GS-23004 *** 2601.03, C, 1, b, Seed Mixture. Add note to Table 2601.03-1: *For 2025 construction season only, Canada wildrye (<i>Elymus canadensis</i>) may be substituted with an equal application rate of Virginia wildrye (<i>Elymus virginicus</i>).
410.11	*** STORM WATER POLLUTION PREVENTION PLAN *** A Storm Water Pollution Prevention Plan has been developed by the Contracting Authority for one or more projects on this contract. See the project plans (or other contract document) for specific Storm Water Pollution Prevention Plan details.
500.01	*** WINTER WORK *** The free time allowed between November 15 and April 1 will not be permitted on this project. The Contractor shall work during the winter on all working days as defined in Article 1101.03 'Working Day'.
720.101	*** R-O-W CERTIFICATE *** This Estimating Proposal has an attachment of the "RIGHT OF WAY CERTIFICATE". This attachment is a part of the proposal form.
720.121	*** POINT 25 Utility Data *** This Estimating Proposal has an attachment of the "POINT 25 Utility Data". This attachment is a part of the proposal form.
DS-23032	DEVELOPMENTAL SPECIFICATIONS FOR ELECTRONIC TICKETING



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Specifications List

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

Note	Description
DS-23061	DEVELOPMENTAL SPECIFICATIONS FOR PREFORMED THERMOPLASTIC PAVEMENT MARKINGS
FHWA-1273.09	FHWA-1273: REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS -- REVISED OCTOBER 23, 2023 23 U.S.C. 133(i) requires application of Davis Bacon predetermined wages on certain projects on roads functionally classified as a local road or a rural minor collector. This supersedes the applicability described in FHWA-1273 Section IV.
GS-23004	GENERAL SUPPLEMENTAL SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION
IA25-81.0	PREDETERMINED WAGE RATE - GENERAL DECISION NUMBER IA20250081 FOR HEAVY AND HIGHWAY CONSTRUCTION -- STATEWIDE (EXCEPT SCOTT COUNTY) Note: The Contractor shall review the contract documents and is responsible for identifying which zone(s), as defined in the Predetermined Wage Rate specification, apply to the work on the contract. *** Additional Requirement *** The Prime Contractor shall submit certified payrolls for itself and each approved Subcontractor weekly to the Project Engineer. The Contractor may use the Iowa D.O.T. Certified Payroll form or other approved form. The Contractor shall list the craft for each employee covered by the Predetermined Wage Rates. The Prime Contractor shall sign each of the Subcontractor's payrolls to acknowledge the submittal of the Certified Payroll.



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	2102-2710070 EXCAVATION, CLASS 10, ROADWAY AND BORROW	27,592.000 CY	_____.	_____	_____.	_____
0020	2102-2710090 EXCAVATION, CLASS 10, WASTE	5,610.000 CY	_____.	_____	_____.	_____
0030	2105-8425015 TOPSOIL, STRIP, SALVAGE AND SPREAD	14,885.000 CY	_____.	_____	_____.	_____
0040	2115-0100000 MODIFIED SUBBASE	27,309.100 CY	_____.	_____	_____.	_____
0050	2121-7425020 GRANULAR SHOULDERS, TYPE B	883.700 TON	_____.	_____	_____.	_____
0060	2123-7450000 SHOULDER CONSTRUCTION, EARTH	683.890 STA	_____.	_____	_____.	_____
0070	2125-2225050 RESHAPING DITCHES	10.000 STA	_____.	_____	_____.	_____
0080	2212-5070310 PATCHES, FULL-DEPTH REPAIR	1,411.100 SY	_____.	_____	_____.	_____
0090	2212-5070330 PATCHES BY COUNT (REPAIR)	62.000 EACH	_____.	_____	_____.	_____
0100	2213-2713300 EXCAVATION, CLASS 13, FOR WIDENING	6,932.800 CY	_____.	_____	_____.	_____
0110	2213-7100400 RELOCATION OF MAIL BOXES	3.000 EACH	_____.	_____	_____.	_____
0120	2214-5145150 PAVEMENT SCARIFICATION	2,583.300 SY	_____.	_____	_____.	_____



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001

ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	2303-1041750 HOT MIX ASPHALT HIGH TRAFFIC, BASE COURSE, 3/4 IN. MIX	29,770.040 TON	_____.	_____	_____.	_____
0140	2303-1042500 HOT MIX ASPHALT HIGH TRAFFIC, INTERMEDIATE COURSE, 1/2 IN. MIX	20,995.290 TON	_____.	_____	_____.	_____
0150	2303-1043504 HOT MIX ASPHALT HIGH TRAFFIC, SURFACE COURSE, 1/2 IN. MIX, FRICTION L-4	15,258.440 TON	_____.	_____	_____.	_____
0160	2303-1258344 ASPHALT BINDER, PG 58-34H, HIGH TRAFFIC	3,961.420 TON	_____.	_____	_____.	_____
0170	2303-6911000 HOT MIX ASPHALT PAVEMENT SAMPLES	LUMP SUM	LUMP SUM		_____.	_____
0180	2303-7000610 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE LABORATORY VOIDS (FORMULA - BY PAY FACTOR)	31,971.500 EACH		1.00000	31,971.50	
0190	2303-7000620 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA MIXTURE FIELD VOIDS (FORMULA - BY PAY FACTOR)	31,971.500 EACH		1.00000	31,971.50	
0200	2312-8260051 GRANULAR SURFACING ON ROAD, CLASS A CRUSHED STONE	3,371.000 TON	_____.	_____	_____.	_____
0210	2317-7000120 PAYMENT ADJUSTMENT INCENTIVE/DISINCENTIVE FOR HMA PAVEMENT SMOOTHNESS (BY SCHEDULE)	24,672.000 EACH		1.00000	24,672.00	



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001

ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	2318-1001100 COLD IN-PLACE RECYCLED ASPHALT PAVEMENT	79,737.900 SY	_____.	_____	_____.	_____
0230	2318-1001220 ASPHALT STABILIZING AGENT (FOAMED ASPHALT)	352.600 TON	_____.	_____	_____.	_____
0240	2401-6745650 REMOVAL OF EXISTING STRUCTURES	LUMP SUM	LUMP SUM		_____.	_____
0250	2416-0100018 APRONS, CONCRETE, 18 IN. DIA.	24.000 EACH	_____.	_____	_____.	_____
0260	2416-0100024 APRONS, CONCRETE, 24 IN. DIA.	4.000 EACH	_____.	_____	_____.	_____
0270	2416-0100030 APRONS, CONCRETE, 30 IN. DIA.	3.000 EACH	_____.	_____	_____.	_____
0280	2416-0101036 REMOVE AND REINSTALL CONCRETE PIPE APRONS LESS THAN OR EQUAL TO 36 IN.	3.000 EACH	_____.	_____	_____.	_____
0290	2416-0101136 REMOVE AND REINSTALL CONCRETE PIPE APRONS GREATER THAN 36 IN.	2.000 EACH	_____.	_____	_____.	_____
0300	2416-0102236 APRON, LOW CLEARANCE CONCRETE, EQUIVALENT DIAMETER 36 IN.	4.000 EACH	_____.	_____	_____.	_____
0310	2416-1180018 CULVERT, CONCRETE ROADWAY PIPE, 18 IN. DIA.	12.000 LF	_____.	_____	_____.	_____
0320	2416-1180024 CULVERT, CONCRETE ROADWAY PIPE, 24 IN. DIA.	44.000 LF	_____.	_____	_____.	_____



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0330	2416-1180030 CULVERT, CONCRETE ROADWAY PIPE, 30 IN. DIA.	34.000 LF	_____.	_____	_____.	_____
0340	2416-1180048 CULVERT, CONCRETE ROADWAY PIPE, 48 IN. DIA.	48.000 LF	_____.	_____	_____.	_____
0350	2416-1202236 CULVERT, 3000D LOW CLEARANCE CONCRETE ROADWAY PIPE, EQUIVALENT DIAMETER 36 IN.	186.000 LF	_____.	_____	_____.	_____
0360	2416-1541036 REMOVE AND REINSTALL RIGID PIPE CULVERT LESS THAN OR EQUAL TO 36 IN.	24.000 LF	_____.	_____	_____.	_____
0370	2417-0225015 APRONS, METAL, 15 IN. DIA.	2.000 EACH	_____.	_____	_____.	_____
0380	2417-0225018 APRONS, METAL, 18 IN. DIA.	6.000 EACH	_____.	_____	_____.	_____
0390	2422-0360018 APRONS, UNCLASSIFIED, 18 IN. DIA.	10.000 EACH	_____.	_____	_____.	_____
0400	2422-1722015 CULVERT, UNCLASSIFIED ENTRANCE PIPE, 15 IN. DIA.	32.000 LF	_____.	_____	_____.	_____
0410	2422-1722018 CULVERT, UNCLASSIFIED ENTRANCE PIPE, 18 IN. DIA.	192.000 LF	_____.	_____	_____.	_____
0420	2502-4388050 INTAKE, STANDPIPE, AS PER PLAN	9.000 EACH	_____.	_____	_____.	_____
0430	2502-8212034 SUBDRAIN, LONGITUDINAL, (SHOULDER) 4 IN. DIA.	39,712.000 LF	_____.	_____	_____.	_____



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0440	2502-8225010 SUBDRAIN OUTLET, 500-10	176.000 EACH				
0450	2506-4984000 FLOWABLE MORTAR	14.100 CY				
0460	2507-3250005 ENGINEERING FABRIC	12.800 SY				
0470	2507-6800061 REVTMENT, CLASS E	5.400 TON				
0480	2510-6745850 REMOVAL OF PAVEMENT	11,241.800 SY				
0490	2520-3350015 FIELD OFFICE	1.000 EACH				
0500	2524-6765010 REMOVE AND REINSTALL SIGN AS PER PLAN	11.000 EACH				
0510	2524-6765220 REMOVAL OF TYPE B SIGN ASSEMBLY	25.000 EACH				
0520	2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS	561.000 LF				
0530	2524-9325001 TYPE A SIGNS, SHEET ALUMINUM	225.500 SF				
0540	2524-9325150 INSTALL TYPE A SIGN	21.000 EACH				
0550	2526-8285000 CONSTRUCTION SURVEY	LUMP SUM	LUMP SUM			



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0560	2527-9263155 PRE-CUT SYMBOLS AND LEGENDS, PREFORMED THERMOPLASTIC MARKING MATERIAL	16.000 EACH				
0570	2527-9263181 PAVEMENT MARKINGS REMOVED	1.990 STA				
0580	2527-9263209 PAINTED PAVEMENT MARKINGS, WATERBORNE OR SOLVENT-BASED	3,755.190 STA				
0590	2527-9270112 GROOVES CUT FOR PAVEMENT MARKINGS	1,106.340 STA				
0600	2528-2518000 SAFETY CLOSURE	6.000 EACH				
0610	2528-8445110 TRAFFIC CONTROL	LUMP SUM	LUMP SUM			
0620	2528-8445113 FLAGGERS	200.000 EACH		575.00000		115,000.00
0630	2528-8445115 PILOT CARS	50.000 EACH		865.00000		43,250.00
0640	2529-2242304 CD JOINT ASSEMBLY	8.000 EACH				
0650	2533-4980005 MOBILIZATION	LUMP SUM	LUMP SUM			
0660	2548-0000100 MILLED SHOULDER RUMBLE STRIPS, HMA SURFACE	713.200 STA				
0670	2548-0000115 ENGINEERED EMULSION FOR FOG SEAL (SHOULDER RUMBLE STRIPS)	772.200 GAL				



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	2548-0000310 MILLED CENTERLINE RUMBLE STRIPS, HMA SURFACE	353.180 STA				
0690	2601-2634100 MULCHING	21.660 ACRE				
0700	2601-2636015 NATIVE GRASS SEEDING	10.280 ACRE				
0710	2601-2636043 SEEDING AND FERTILIZING (RURAL)	11.380 ACRE				
0720	2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING	21.660 ACRE				
0730	2602-0000020 SILT FENCE	2,075.000 LF				
0740	2602-0000030 SILT FENCE FOR DITCH CHECKS	3,360.000 LF				
0750	2602-0000071 REMOVAL OF SILT FENCE OR SILT FENCE FOR DITCH CHECKS	5,435.000 LF				
0760	2602-0000101 MAINTENANCE OF SILT FENCE OR SILT FENCE FOR DITCH CHECK	543.000 LF				
0770	2602-0000312 PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 12 IN. DIA.	700.000 LF				
0780	2602-0000351 REMOVAL OF PERIMETER AND SLOPE OR DITCH CHECK SEDIMENT CONTROL DEVICE	700.000 LF				



4/8/2025 12:30 PM

Contracts and Specifications Bureau

Proposal Schedule of Items

Proposal ID: 55-0183-116

Call Order: 153

Letting Date: May 20, 2025

SECTION: 0001
ROADWAY ITEMS

Proposal Line Number	Item Number Item Description	Item Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0790	2602-0010010 MOBILIZATIONS, EROSION CONTROL	1.000 EACH		600.00000		600.00
0800	2602-0010020 MOBILIZATIONS, EMERGENCY EROSION CONTROL	1.000 EACH		1,200.00000		1,200.00

Section: 0001

Total:

_____.

Total Bid:

_____.